



Alabama Department of Environmental Management  
adem.alabama.gov

1400 Coliseum Blvd. 36110-2400 ■ Post Office Box 301463  
Montgomery, Alabama 36130-1463  
(334) 271-7700 ■ FAX (334) 271-7950

JUL 09 2015

Mr. David J. Norton, Chairman  
Heflin Water Works and Sewer Board  
Post Office Box 488  
Heflin, AL 36264

RE: Draft Permit  
NPDES Permit No. AL0056146  
Heflin Lagoon  
Cleburne County, Alabama

Dear Mr. Norton:

Transmitted herein is a draft of the referenced permit. Please be aware Part IV.G. of Permit which requires the Permittee to create a Mercury Minimization Plan.

We would appreciate your comments on the permit within **30 days** of the date of this letter. Please direct any comments of a technical or administrative nature to the undersigned.

By copy of this letter and the draft permit, we are also requesting comments within the same time frame from EPA.

Please be aware that, if you are not already participating in the Department's web-based electronic environmental (E2) Reporting System Program for submittal of discharge monitoring reports (DMRs), Part I.C.1.c of your permit will require you to apply for participation in the E2 Program within 180 days of the effective date of the permit unless valid justification as to why you cannot participate is submitted in writing. The E2 Program allows ADEM to electronically validate, acknowledge receipt, and upload data to the state's central wastewater database. This improves the accuracy of reported compliance data and reduces costs to both the regulated community and ADEM. The Permittee Participation Package may be downloaded online at <https://e2.adem.alabama.gov/npdes> or you may obtain a hard copy by submitting a written request or by emailing [e2admin@adem.alabama.gov](mailto:e2admin@adem.alabama.gov).

The Alabama Department of Environmental Management encourages you to voluntarily consider pollution prevention practices and alternatives at your facility. Pollution Prevention may assist you in complying with effluent limitations, and possibly reduce or eliminate monitoring requirements.

Should you have any questions, please contact the undersigned by email at [storbert@adem.state.al.us](mailto:storbert@adem.state.al.us) or by phone at (334) 271-7800.

Sincerely,

A handwritten signature in black ink, appearing to read "Shanda Torbert".

Shanda Torbert  
Municipal Section  
Water Division

Enclosure

cc: Mr. Mark Nuhfer/Environmental Protection Agency  
Ms. Elaine Snyder/U.S. Fish and Wildlife Service  
Ms. Elizabeth Brown/Alabama Historical Commission  
Advisory Council on Historic Preservation  
Department of Conservation and Natural Resources



# NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT

PERMITTEE: HEFLIN WATER WORKS AND SEWER BOARD  
POST OFFICE BOX 488  
HEFLIN, ALABAMA 36264

FACILITY LOCATION: HEFLIN LAGOON (0.6) MGD  
U.S. HIGHWAY 78 WEST  
HEFLIN, ALABAMA  
CLEBURNE COUNTY

PERMIT NUMBER: AL0056146

RECEIVING WATERS: TALLAPOOSA RIVER

*In accordance with and subject to the provisions of the Federal Water Pollution Control Act, as amended, 33 U.S.C. §§1251-1378 (the "FWPCA"), the Alabama Water Pollution Control Act, as amended, Code of Alabama 1975, §§ 22-22-1 to 22-22-14 (the "AWPCA"), the Alabama Environmental Management Act, as amended, Code of Alabama 1975, §§22-22A-1 to 22-22A-15, and rules and regulations adopted thereunder, and subject further to the terms and conditions set forth in this permit, the Permittee is hereby authorized to discharge into the above-named receiving waters.*

ISSUANCE DATE:

EFFECTIVE DATE:

EXPIRATION DATE:

**Draft**

---

Alabama Department of Environmental Management

**MUNICIPAL SECTION**  
**NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES)**  
**PERMIT**

**TABLE OF CONTENTS**

<b>PART I</b>	<b>DISCHARGE LIMITATIONS, CONDITIONS, AND REQUIREMENTS .....</b>	<b>4</b>
A.	DISCHARGE LIMITATIONS AND MONITORING REQUIREMENTS .....	4
1.	Outfall 0011 Discharge Limits .....	4
2.	Outfall 0011 Discharge Limits (continued) .....	5
3.	Outfall 001T Discharge Limits - Toxicity.....	6
B.	DISCHARGE MONITORING AND RECORD KEEPING REQUIREMENTS .....	7
1.	Representative Sampling.....	7
2.	Measurement Frequency .....	7
3.	Test Procedures.....	7
4.	Recording of Results .....	7
5.	Records Retention and Production .....	8
6.	Reduction, Suspension or Termination of Monitoring and/or Reporting.....	8
7.	Monitoring Equipment and Instrumentation .....	8
C.	DISCHARGE REPORTING REQUIREMENTS .....	8
1.	Reporting of Monitoring Requirements .....	8
2.	Noncompliance Notification .....	10
D.	OTHER REPORTING AND NOTIFICATION REQUIREMENTS.....	11
1.	Anticipated Noncompliance.....	11
2.	Termination of Discharge .....	11
3.	Updating Information.....	11
4.	Duty to Provide Information .....	11
E.	SCHEDULE OF COMPLIANCE .....	11
1.	Compliance with discharge limits.....	11
2.	Schedule .....	12
<b>PART II</b>	<b>OTHER REQUIREMENTS, RESPONSIBILITIES, AND DUTIES .....</b>	<b>13</b>
A.	OPERATIONAL AND MANAGEMENT REQUIREMENTS.....	13
1.	Facilities Operation and Maintenance.....	13
2.	Best Management Practices (BMP) .....	13
3.	Certified Operator .....	13
B.	OTHER RESPONSIBILITIES.....	13
1.	Duty to Mitigate Adverse Impacts .....	13
2.	Right of Entry and Inspection .....	13
C.	BYPASS AND UPSET .....	13
1.	Bypass.....	13
2.	Upset.....	14
D.	DUTY TO COMPLY WITH PERMIT, RULES, AND STATUTES .....	14
1.	Duty to Comply.....	14
2.	Removed Substances.....	14
3.	Loss or Failure of Treatment Facilities .....	14
4.	Compliance With Statutes and Rules .....	15
E.	PERMIT TRANSFER, MODIFICATION, SUSPENSION, REVOCATION, AND REISSUANCE .....	15
1.	Duty to Reapply or Notify of Intent to Cease Discharge .....	15
2.	Change in Discharge .....	15
3.	Transfer of Permit .....	15
4.	Permit Modification and Revocation .....	15
5.	Termination.....	16
6.	Suspension .....	16

7.	Stay .....	16
F.	COMPLIANCE WITH TOXIC POLLUTANT STANDARD OR PROHIBITION .....	17
G.	NOTICE TO DIRECTOR OF INDUSTRIAL USERS.....	17
H.	PROHIBITIONS .....	17
<b>PART III ADDITIONAL REQUIREMENTS, CONDITIONS, AND LIMITATIONS.....</b>		<b>18</b>
A.	CIVIL AND CRIMINAL LIABILITY.....	18
1.	Tampering .....	18
2.	False Statements.....	18
3.	Permit Enforcement .....	18
4.	Relief from Liability .....	18
B.	OIL AND HAZARDOUS SUBSTANCE LIABILITY .....	18
C.	PROPERTY AND OTHER RIGHTS.....	18
D.	AVAILABILITY OF REPORTS .....	18
E.	EXPIRATION OF PERMITS FOR NEW OR INCREASED DISCHARGES .....	19
F.	COMPLIANCE WITH WATER QUALITY STANDARDS.....	19
G.	GROUNDWATER .....	19
H.	DEFINITIONS.....	19
I.	SEVERABILITY .....	22
<b>PART IV SPECIFIC REQUIREMENTS, CONDITIONS, AND LIMITATIONS.....</b>		<b>23</b>
A.	SLUDGE MANAGEMENT PRACTICES .....	23
1.	Applicability .....	23
2.	Submitting Information.....	23
3.	Reopener or Modification .....	23
B.	EFFLUENT TOXICITY LIMITATIONS AND BIOMONITORING REQUIREMENTS FOR CHRONIC TOXICITY.....	23
1.	Chronic Toxicity Test .....	23
2.	General Test Requirements .....	23
3.	Reporting Requirements .....	24
4.	Additional Testing Requirements .....	24
5.	Test Methods.....	24
6.	Effluent Toxicity Testing Reports.....	24
C.	TOTAL RESIDUAL CHLORINE (TRC) REQUIREMENTS.....	26
D.	PLANT CLASSIFICATION.....	26
E.	POLLUTANT SCANS.....	26
F.	PERMIT REQUIREMENT FOR DAM .....	26

## PART I DISCHARGE LIMITATIONS, CONDITIONS, AND REQUIREMENTS

### A. DISCHARGE LIMITATIONS AND MONITORING REQUIREMENTS

1. Outfall 0011 Discharge Limits

During the period beginning on the effective date of this permit and lasting through the expiration date of this permit, the Permittee is authorized to discharge from Outfall 0011, which is described more fully in the Permittee's application. Such discharge shall be limited and monitored by the Permittee as specified below:

Parameter	Discharge Limitations*						Monitoring Requirements**				
	Monthly Average	Weekly Average	Monthly Average	Weekly Average	Daily Minimum	Daily Maximum	Percent Removal	(1) Sample Location	(2) Sample Type	(3) Measurement Frequency	(4) Seasonal
pH	*****	*****	*****	*****	6.0 S.U.	9.0 S.U.	*****	E	GRAB	E	*****
00400 I 0 0											
Solids, Total Suspended	450 lbs/day	675 lbs/day	90.0 mg/l	135 mg/l	*****	*****	*****	E	COMP24	E	*****
00530 I 0 0											
Solids, Total Suspended	REPORT lbs/day	REPORT lbs/day	REPORT mg/l	REPORT mg/l	*****	*****	*****	I	COMP24	E	*****
00530 G 0 0											
Nitrogen, Ammonia Total (As N)	75.0 lbs/day	112 lbs/day	15.0 mg/l	22.5 mg/l	*****	*****	*****	E	COMP24	E	S
00610 I 0 0											
Nitrogen, Ammonia Total (As N)	100 lbs/day	150 lbs/day	20.0 mg/l	30.0 mg/l	*****	*****	*****	E	COMP24	E	W
00610 I 0 0											
Nitrogen, Kjeldahl Total (As N)	150.1 lbs/day	225.2 lbs/day	30.0 mg/l	45.0 mg/l	*****	*****	*****	E	COMP24	E	S
00625 I 0 0											
Nitrogen, Kjeldahl Total (As N)	200.2 lbs/day	300.2 lbs/day	40.0 mg/l	60.0 mg/l	*****	*****	*****	E	COMP24	E	W
00625 I 0 0											
Nitrite Plus Nitrate Total (As N)	REPORT lbs/day	REPORT lbs/day	REPORT mg/l	REPORT mg/l	*****	*****	*****	E	COMP24	G See Note 5	S
00630 I 0 0											
Phosphorus, Total (As P)	REPORT lbs/day	REPORT lbs/day	REPORT mg/l	REPORT mg/l	*****	*****	*****	E	COMP24	G See Note 5	S
00665 I 0 0											
Flow, In Conduit or Thru Treatment Plant	REPORT MGD	*****	*****	*****	*****	REPORT MGD	*****	E	CONTIN	A	*****
50050 I 0 0											

\* See Part II.C.1. (Bypass); Part II.C.2. (Upset)

\*\* Monitoring Requirements

(1) Sample Location

I - Influent

E - Effluent

X - End Chlorine Contact Chamber

K - Percent Removal of the Monthly Avg. Influent Concentration

from the Monthly Avg. Effluent Concentration.

RS - Receiving Stream

(2) Sample Type:

CONTIN - Continuous

INSTAN - Instantaneous

COMP-8 - 8-Hour Composite

COMP24 - 24-Hour Composite

GRAB - Grab

CALCTD - Calculated

(3) Measurement Frequency: See also Part I.B.2.

A - 7 days per week F - 2 days per month

B - 5 days per week G - 1 day per month

C - 3 days per week H - 1 day per quarter

D - 2 days per week J - Annual

E - 1 day per week Q - For Effluent Toxicity

Testing, see Provision IV.B.

(4) Seasonal Limits:

S = Summer (April - October)

W = Winter (November - March)

ECS = E. coli Summer (June - September)

ECW = E. coli Winter (October - May)

(5) If only one sampling event occurs during the month, the sample result shall be reported on the DMR as both the monthly average, weekly average, and/or the daily maximum.

**Limits for Outfall 0011 continued on the next page.**

2. Outfall 0011 Discharge Limits (continued)

During the period beginning on the effective date of this permit and lasting through the expiration date of this permit, the Permittee is authorized to discharge from Outfall 0011, which is described more fully in the Permittee's application. Such discharge shall be limited and monitored by the Permittee as specified below:

Parameter	Discharge Limitations*						Monitoring Requirements**				
	Monthly Average	Weekly Average	Monthly Average	Weekly Average	Daily Minimum	Daily Maximum	Percent Removal	(1) Sample Location	(2) Sample Type	(3) Measurement Frequency	(4) Seasonal
Chlorine, Total Residual 50060 I 0 0	*****	*****	0.539 mg/l	*****	*****	0.932 mg/l	*****	E	GRAB	E See Note 5	*****
E. Coli 51040 I 0 0	*****	*****	126 col/100mL	*****	*****	487 col/100mL	*****	E	GRAB	E	ECS
E. Coli 51040 I 0 0	*****	*****	548 col/100mL	*****	*****	2507 col/100mL	*****	E	GRAB	E	ECW
BOD, Carbonaceous 05 Day, 20C 80082 I 0 0	100 lbs/day	150 lbs/day	20.0 mg/l	30.0 mg/l	*****	*****	*****	E	COMP24	E	S
BOD, Carbonaceous 05 Day, 20C 80082 I 0 0	125 lbs/day	187 lbs/day	25.0 mg/l	37.5 mg/l	*****	*****	*****	E	COMP24	E	W
BOD, Carbonaceous 05 Day, 20C 80082 G 0 0	REPORT lbs/day	REPORT lbs/day	REPORT mg/l	REPORT mg/l	*****	*****	*****	I	COMP24	E	*****
BOD, Carb-5 Day, 20 Deg C, Percent Remvl 80091 K 0 0	*****	*****	*****	*****	*****	*****	85.0%	K	CALCTD	G	*****
Solids, Suspended Percent Removal 81011 K 0 0	*****	*****	*****	*****	*****	*****	65.0%	K	CALCTD	G	*****

\* See Part II.C.1. (Bypass); Part II.C.2. (Upset)

\*\* Monitoring Requirements

(1) Sample Location

I – Influent

E – Effluent

X – End Chlorine Contact Chamber

K - Percent Removal of the Monthly Avg. Influent Concentration

from the Monthly Avg. Effluent Concentration.

RS - Receiving Stream

(2) Sample Type:

CONTIN - Continuous

INSTAN - Instantaneous

COMP-8 - 8-Hour Composite

COMP24 - 24-Hour Composite

GRAB – Grab

CALCTD - Calculated

(3) Measurement Frequency: See also Part I.B.2.

A - 7 days per week

B - 5 days per week

C - 3 days per week

D - 2 days per week

E - 1 day per week

(4) Seasonal Limits:

S = Summer (April – October)

W = Winter (November – March)

ECS = E. coli Summer (June – September)

ECW = E. coli Winter (October – May)

Q - For Effluent Toxicity

Testing, see Provision IV.B.

(5) See Part IV.C. for Total Residual Chlorine (TRC). Monitoring for TRC is applicable if chlorine is utilized for disinfection purposes. If monitoring is not applicable during the monitoring period, enter “NODI=9” on the monthly DMR.

3. Outfall 001T Discharge Limits - Toxicity

Outfall 001T represents the same physical outfall as Outfall 0011. The Department uses the 001T designation for all samples collected and analyzed for Toxicity testing, which is described more fully in the Permittee's application. Such discharge shall be limited and monitored by the Permittee as specified below:

Parameter	Discharge Limitations*					Monitoring Requirements**			
	Monthly Average	Weekly Average	Monthly Average	Weekly Average	Daily Minimum	Daily Maximum	Percent Removal	(1) Sample Location	(2) Sample Type
Toxicity, Ceriodaphnia Chronic 61426 1 0 0	*****	Pass = 0 Fail = 1	*****	*****	*****	*****	*****	E	COMP24
Toxicity, Pimephales Chronic 61428 1 0 0	*****	Pass = 0 Fail = 1	*****	*****	*****	*****	*****	E	COMP24

\* See Part II.C.1. (Bypass); Part II.C.2. (Upset)

\*\* Monitoring Requirements

(1) Sample Location

I - Influent

E - Effluent

X - End Chlorine Contact Chamber

K - Percent Removal of the Monthly Avg. Influent Concentration

from the Monthly Avg. Effluent Concentration.

RS - Receiving Stream

(2) Sample Type:

CONTIN - Continuous

INSTAN - Instantaneous

COMP-8 - 8-Hour Composite

COMP24 - 24-Hour Composite

GRAB - Grab

CALCTD - Calculated

(3) Measurement Frequency: See also Part I.B.2.

A - 7 days per week F - 2 days per month

B - 5 days per week G - 1 day per month

C - 3 days per week H - 1 day per quarter

D - 2 days per week J - Annual

E - 1 day per week Q - For Effluent Toxicity

Testing, see Provision IV.B.

(4) Seasonal Limits:

S = Summer (April - October)

W = Winter (November - March)

ECS = E. coli Summer (June - September)

ECW = E. coli Winter (October - May)

**B. DISCHARGE MONITORING AND RECORD KEEPING REQUIREMENTS****1. Representative Sampling**

Sample collection and measurement actions shall be representative of the volume and nature of the monitored discharge and shall be in accordance with the provisions of this permit. The effluent sampling point shall be at the nearest accessible location just prior to discharge and after final treatment, unless otherwise specified in the permit.

**2. Measurement Frequency**

Measurement frequency requirements found in Provision I.A. shall mean:

- a. Seven days per week shall mean daily.
- b. Five days per week shall mean any five days of discharge during a calendar weekly period of Sunday through Saturday.
- c. Three days per week shall mean any three days of discharge during a calendar week.
- d. Two days per week shall mean any two days of discharge during a calendar week.
- e. One day per week shall mean any day of discharge during a calendar week.
- f. Two days per month shall mean any two days of discharge during the month that are no less than seven days apart. However, if discharges occur only during one seven-day period in a month, then two days per month shall mean any two days of discharge during that seven day period.
- g. One day per month shall mean any day of discharge during the calendar month.
- h. Quarterly shall mean any day of discharge during each calendar quarter.
- i. The Permittee may increase the frequency of sampling, listed in Provisions I.B.2.a through I.B.2.h; however, all sampling results are to be reported to the Department.

**3. Test Procedures**

For the purpose of reporting and compliance, Permittees shall use one of the following procedures:

- a. For parameters with an EPA established Minimum Level (ML), report the measured value if the analytical result is at or above the ML and report "0" for values below the ML. Test procedures for the analysis of pollutants shall conform to 40 CFR Part 136 and guidelines published pursuant to Section 304(h) of the FWPCA, 33 U.S.C. Section 1314(h). If more than one method for analysis of a substance is approved for use, a method having a minimum level lower than the permit limit shall be used. If the minimum level of all methods is higher than the permit limit, the method having the lowest minimum level shall be used and a report of less than the minimum level shall be reported as zero and will constitute compliance, however should EPA approve a method with a lower minimum level during the term of this permit the Permittee shall use the newly approved method.
- b. For pollutants parameters without an established ML, an interim ML may be utilized. The interim ML shall be calculated as 3.18 times the Method Detection Level (MDL) calculated pursuant to 40 CFR Part 136, Appendix B.

Permittees may develop an effluent matrix-specific ML, where an effluent matrix prevents attainment of the established ML. However, a matrix specific ML shall be based upon proper laboratory method and technique. Matrix-specific MLs must be approved by the Department, and may be developed by the Permittee during permit issuance, reissuance, modification, or during compliance schedule.

In either case the measured value should be reported if the analytical result is at or above the ML and "0" reported for values below the ML.

- c. For parameters without an EPA established ML, interim ML, or matrix-specific ML, a report of less than the detection limit shall constitute compliance if the detection limit of all analytical methods is higher than the permit limit. For the purpose of calculating a monthly average, "0" shall be used for values reported less than the detection limit.

The Minimum Level utilized for procedures a and b above shall be reported on the Permittee's DMR. When an EPA approved test procedure for analysis of a pollutant does not exist, the Director shall approve the procedure to be used.

**4. Recording of Results**

For each measurement or sample taken pursuant to the requirements of this permit, the Permittee shall record the following information:

- a. The facility name and location, point source number, date, time and exact place of sampling;



- b. The name(s) of person(s) who obtained the samples or measurements;
  - c. The dates and times the analyses were performed;
  - d. The name(s) of the person(s) who performed the analyses;
  - e. The analytical techniques or methods used, including source of method and method number; and
  - f. The results of all required analyses.
5. Records Retention and Production
- a. The Permittee shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by the permit, and records of all data used to complete the above reports or the application for this permit, for a period of at least three years from the date of the sample measurement, report or application. This period may be extended by request of the Director at any time. If litigation or other enforcement action, under the AWPCA and/or the FWPCA, is ongoing which involves any of the above records, the records shall be kept until the litigation is resolved. Upon the written request of the Director or his designee, the Permittee shall provide the Director with a copy of any record required to be retained by this paragraph. Copies of these records should not be submitted unless requested.
  - b. All records required to be kept for a period of three years shall be kept at the permitted facility or an alternate location approved by the Department in writing and shall be available for inspection.
6. Reduction, Suspension or Termination of Monitoring and/or Reporting
- a. The Director may, with respect to any point source identified in Provision I.A. of this permit, authorize the Permittee to reduce, suspend or terminate the monitoring and/or reporting required by this permit upon the submission of a written request for such reduction, suspension or termination by the Permittee, supported by sufficient data which demonstrates to the satisfaction of the Director that the discharge from such point source will continuously meet the discharge limitations specified in Provision I.A. of this permit.
  - b. It remains the responsibility of the Permittee to comply with the monitoring and reporting requirements of this permit until written authorization to reduce, suspend or terminate such monitoring and/or reporting is received by the Permittee from the Director.
7. Monitoring Equipment and Instrumentation
- All equipment and instrumentation used to determine compliance with the requirements of this permit shall be installed, maintained, and calibrated in accordance with the manufacturer's instructions or, in the absence of manufacturer's instructions, in accordance with accepted practices. At a minimum, flow measurement devices shall be calibrated at least once every 12 months.

## C. DISCHARGE REPORTING REQUIREMENTS

1. Reporting of Monitoring Requirements
- a. The Permittee shall conduct the required monitoring in accordance with the following schedule:
    - (1) **MONITORING REQUIRED MORE FREQUENTLY THAN MONTHLY AND MONTHLY** shall be conducted during the first full month following the effective date of coverage under this permit and every month thereafter.
    - (2) **QUARTERLY MONITORING** shall be conducted at least once during each calendar quarter. Calendar quarters are the periods of January through March, April through June, July through September, and October through December. The Permittee shall conduct the quarterly monitoring during the first complete calendar quarter following the effective date of this permit and is then required to monitor once during each quarter thereafter. Quarterly monitoring should be reported on the last DMR due for the quarter (i.e., March, June, September and December DMRs).
    - (3) **SEMIANNUAL MONITORING** shall be conducted at least once during the period of January through June and at least once during the period of July through December. The Permittee shall conduct the semiannual monitoring during the first complete calendar semiannual period following the effective date of this permit and is then required to monitor once during each semiannual period thereafter. Semiannual monitoring may be done anytime during the semiannual period, unless restricted elsewhere in this permit, but it should be reported on the last DMR due for the month of the semiannual period (i.e., June and December DMRs).
    - (4) **ANNUAL MONITORING** shall be conducted at least once during the period of January through December. The Permittee shall conduct the annual monitoring during the first complete calendar annual period following the effective date of this permit and is then required to monitor once during each annual period thereafter.

Annual monitoring may be done anytime during the year, unless restricted elsewhere in this permit, but it should be reported on the December DMR.

- b. The Permittee shall submit discharge monitoring reports (DMRs) on the forms approved by the Department and in accordance with the following schedule:
- (1) **REPORTS OF MORE FREQUENTLY THAN MONTHLY AND MONTHLY TESTING** shall be submitted on a monthly basis. The first report is due on the 28th day of the month following the month the permit becomes effective. The reports shall be submitted so that they are received by the Department no later than the 28th day of the month following the reporting period.
  - (2) **REPORTS OF QUARTERLY TESTING** shall be submitted on a quarterly basis. The first report is due on the 28th day of the month following the month the permit becomes effective. The reports shall be submitted so that they are received by the Department no later than the 28th day of the month following the reporting period.
  - (3) **REPORTS OF SEMIANNUAL TESTING** shall be submitted on a semiannual basis. The reports are due on the 28th day of JANUARY and the 28th day of JULY. The reports shall be submitted so that they are received by the Department no later than the 28th day of the month following the reporting period.
  - (4) **REPORTS OF ANNUAL TESTING** shall be submitted on an annual basis. Unless specified elsewhere in the permit, the first report is due on the 28th day of JANUARY. The reports shall be submitted so that they are received by the Department no later than the 28th day of the month following the reporting period.
- c. The Department is utilizing a web-based electronic environmental (E2) DMR reporting system for submittal of DMRs. **If the permittee is not already participating in the E2 DMR system, the permittee must apply for participation in the system within 180 days of coverage under this permit unless the facility submits in writing valid justification as to why they cannot participate and the Department approves in writing utilization of hard copy DMR submittals.** Once the permittee is enrolled in the E2 DMR system, the permittee must utilize the system for the submittal of DMRs unless otherwise allowed by this permit. To participate in the E2 DMR system, the Permittee Participation Package may be downloaded online at <https://e2.adem.alabama.gov/npdes>. If the E2 DMR system is down (i.e., electronic submittal of DMR data is unable to be completed due to technical problems originating with the Department's system: this could include entry/submittal issues with an entire set of DMRs or individual parameters), the permittee is not relieved of their obligation to submit DMR data to the Department by the required submittal date. However, if the E2 DMR system is down on the 28<sup>th</sup> day of the month or is down for an extended period of time as determined by the Department when a DMR is required to be submitted, the facility may submit the data in an alternate manner and format acceptable to the Department. Preapproved alternate acceptable methods include faxing, e-mailing, mailing, or hand-delivery of data such that they are received by the required reporting date. Within five calendar days of the E2 DMR system resuming operation, the permittee shall enter the data into the E2 DMR system, unless an alternate timeframe is approved by the Department. An attachment should be included with the E2 DMR submittal verifying the original submittal date (date of the fax, copy of dated e-mail, or hand-delivery stamped date). If a permittee is allowed to submit via the US Postal Service, the DMR must be legible and bear an original signature. Photo and electronic copies of the signature are not acceptable and shall not satisfy the reporting requirements of this permit. If the permittee, using approved analytical methods as specified in Provision I.B.2, monitors any discharge from a point source for a limited substance identified in Provision I.A of this permit more frequently than required by this permit, the results of such monitoring shall be included in the calculation and reporting of values on the DMR form and the increased frequency shall be indicated on the DMR form. In the event no discharge from a point source identified in Provision I.A of this permit and described more fully in the permittee's application occurs during a monitoring period, the permittee shall report "No Discharge" for such period on the appropriate DMR form.
- d. All reports and forms required to be submitted by this permit, the AWPCA and the Department's Rules and regulations, shall be electronically signed (or, if allowed by the Department, traditionally signed) by a "responsible official" of the permittee as defined in ADEM Administrative Code Rule 335-6-6-.09 or a "duly authorized representative" of such official as defined in ADEM Administrative Code Rule 335-6-6-.09 and shall bear the following certification:
- "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."**
- e. The Permittee may certify in writing that a discharge will not occur for an extended period of time and after such certification shall not be required to submit monitoring reports. Written notification of a planned resumption of discharge shall be submitted at least 30 days prior to resumption of the discharge. If an unplanned resumption of

discharge occurs, written notification shall be submitted within 7 days of the resumption. In any case, all discharges shall comply with all provisions of this permit.

- f. All reports and forms required to be submitted by this permit, the AWPCA and the Department's Rules, shall be addressed to:

**Alabama Department of Environmental Management  
Municipal Section, Water Division  
Post Office Box 301463  
Montgomery, Alabama 36130-1463**

Certified and Registered Mail shall be addressed to:

**Alabama Department of Environmental Management  
Municipal Section, Water Division  
1400 Coliseum Boulevard  
Montgomery, Alabama 36110-2059**

DMRs required to be submitted by this permit shall be addressed to:

**Alabama Department of Environmental Management  
Environmental Data Section, Permits & Services Division  
Post Office Box 301463  
Montgomery, Alabama 36130-1463**

- g. If this permit is a reissuance, then the permittee shall continue to submit DMRs in accordance with the requirements of their previous permit until such time as DMRs are due as discussed in Part I.C.1.b. above.

**2. Noncompliance Notification**

- a. The Permittee must notify the Department if, for any reason, the Permittee's discharge:

- (1) Does not comply with any daily minimum or maximum discharge limitation for an effluent characteristic specified in Provision I. A. of this permit which is denoted by an "(X)"
- (2) Potentially threatens human health or welfare,
- (3) Threatens fish or aquatic life
- (4) Causes an in-stream water quality criterion to be exceeded;
- (5) Does not comply with an applicable toxic pollutant effluent standard or prohibition established under Section 307(a) of the FWPCA, 33 U.S.C. Section 1317(a);
- (6) Contains a quantity of a hazardous substance that may be harmful to public health or welfare under Section 311(b)(4) of the FWPCA, 33 U.S.C. Section 1321(b)(4);
- (7) Exceeds any discharge limitation for an effluent parameter listed in Part I.A as a result of an unanticipated bypass or upset; or
- (8) Is an unpermitted direct or indirect discharge of a pollutant to a water of the state (Note that unpermitted discharges properly reported to the Department under any other requirement are not required to be reported under this provision)

The Permittee shall orally or electronically report any of the above occurrences, describing the circumstances and potential effects, to the Department within 24-hours after the Permittee becomes aware of the occurrence of such discharge. In addition to the oral or electronic report, the Permittee shall submit a written report to the Director or Designee, as provided in Provision I.C.2.c, no later than five days after becoming aware of the occurrence of such discharge or occurrence.

- b. If for any reason, the Permittee's discharge does not comply with any limitation of this permit, then the Permittee must submit a written report to the Director or Designee, as provided in Provision I.C.2.c below. This report must be submitted with the next Discharge Monitoring Report required to be submitted by Provision I.C.1 of this permit after becoming aware of the occurrence of such noncompliance.
- c. Form 421 must be submitted to the Director or Designee in accordance with Provisions I.C.2a. or b. The completed form must document the following information:
- (1) A description of the discharge and cause of noncompliance;
  - (2) The period of noncompliance, including exact dates, times, and duration of the noncompliance. If not corrected by the due date of the written report, then the Permittee is to state the anticipated timeframe that is expected to transpire before the noncompliance is resolved; and

- (3) A description of the steps taken by the Permittee and the steps planned to be taken by the Permittee to reduce or eliminate the noncompliant discharge, including all steps taken to prevent recurrence.
- d. Immediate notification

The permittee shall provide notification to the Director, the public, the county health department, and any other affected entity such as public water systems, as soon as possible upon becoming aware of any notifiable sanitary sewer overflow. The Permittee shall also report notification of the noncompliance event to any other affected entity such as the public.
- e. The Permittee shall keep an updated record of all known wastewater discharge points that are not authorized as permitted outfalls, including but not limited to SSOs. The Permittee shall submit annual Municipal Water Pollution Prevention Plan (MWPP) reports to the Department each year by May 31st for the prior calendar year period beginning January 1st and ending December 31st. The Annual MWPP Reports shall contain a list of all known wastewater discharge points that are not authorized as permitted outfalls and any discharges that occur prior to the headworks of the wastewater treatment plant covered by this permit. The MWPP shall also provide a list of any discharges reported in accordance with Provision I.C.2.a. The Permittee shall submit with its Annual MWPP Report the following information for each known unpermitted discharge that occurs:
  - (1) The cause of the discharge;
  - (2) Date, duration and volume of discharge (estimate if unknown);
  - (3) Description of the source (e.g., manhole, lift station);
  - (4) Location of the discharge, by street address or any other appropriate method;
  - (5) The ultimate destination of the flow (e.g., surface waterbody, municipal separate storm sewer to surface waterbody). Location should be shown on a USGS quad sheet or copy thereof; and
  - (6) Corrective actions or plans to eliminate future discharges.
- f. The Permittee shall report SSO and other illicit or anomalous discharge events on Form 415 in accordance with Part I.C.2.a. This form is available on the ADEM web page or upon request from the Permittee.

#### **D. OTHER REPORTING AND NOTIFICATION REQUIREMENTS**

##### **1. Anticipated Noncompliance**

The Permittee shall give the Director written advance notice of any planned changes or other circumstances regarding a facility which may result in noncompliance with permit requirements.

##### **2. Termination of Discharge**

The Permittee shall notify the Director, in writing, when all discharges from any point source(s) identified in Provision I. A. of this permit have permanently ceased. This notification shall serve as sufficient cause for instituting procedures for modification or termination of the permit.

##### **3. Updating Information**

- a. The Permittee shall inform the Director of any change in the Permittee's mailing address or telephone number or in the Permittee's designation of a facility contact or office having the authority and responsibility to prevent and abate violations of the AWPCA, the Department's Rules and the terms and conditions of this permit, in writing, no later than ten (10) days after such change. Upon request of the Director or his designee, the Permittee shall furnish the Director with an update of any information provided in the permit application.
- b. If the Permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to the Director, it shall promptly submit such facts or information with a written explanation for the mistake and/or omission.

##### **4. Duty to Provide Information**

The Permittee shall furnish to the Director, within a reasonable time, any information which the Director or his designee may request to determine whether cause exists for modifying, revoking and re-issuing, suspending, or terminating this permit, in whole or in part, or to determine compliance with this permit.

#### **E. SCHEDULE OF COMPLIANCE**

##### **I. Compliance with discharge limits**

The Permittee shall achieve compliance with the discharge limitations specified in Provision I. A. in accordance with the following schedule:

COMPLIANCE SHALL BE ATTAINED ON THE EFFECTIVE DATE OF THIS PERMIT

2. Schedule

No later than 14 calendar days following a date identified in the above schedule of compliance, the permittee shall submit either a report of progress or, in the case of specific actions being required by identified dates, a written notice of compliance or noncompliance. In the latter case, the notice shall include the cause of noncompliance, any remedial actions taken, and the probability of meeting the next scheduled requirement.

## **PART II OTHER REQUIREMENTS, RESPONSIBILITIES, AND DUTIES**

### **A. OPERATIONAL AND MANAGEMENT REQUIREMENTS**

#### **1. Facilities Operation and Maintenance**

The Permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the Permittee to achieve compliance with the conditions of the permit. Proper operation and maintenance includes effective performance, adequate funding, adequate operator staffing and training, and adequate laboratory and process controls, including appropriate quality assurance procedures. This provision requires the operation of backup or auxiliary facilities only when necessary to achieve compliance with the conditions of the permit.

#### **2. Best Management Practices (BMP)**

- a. Dilution water shall not be added to achieve compliance with discharge limitations except when the Director or his designee has granted prior written authorization for dilution to meet water quality requirements.
- b. The Permittee shall prepare, implement, and maintain a Spill Prevention, Control and Countermeasures (SPCC) Plan in accordance with 40 C.F.R. Section 112 if required thereby.
- c. The Permittee shall prepare, submit for approval and implement a BMP Plan for containment of any or all process liquids or solids, in a manner such that these materials do not present a significant potential for discharge, if so required by the Director or his designee. When submitted and approved, the BMP Plan shall become a part of this permit and all requirements of the BMP Plan shall become requirements of this permit.

#### **3. Certified Operator**

The Permittee shall not operate any wastewater treatment plant unless the competency of the operator to operate such plant has been duly certified by the Director pursuant to AWPCA, and meets the requirements specified in ADEM Administrative Code, Rule 335-10-1.

### **B. OTHER RESPONSIBILITIES**

#### **1. Duty to Mitigate Adverse Impacts**

The Permittee shall promptly take all reasonable steps to mitigate and minimize or prevent any adverse impact on human health or the environment resulting from noncompliance with any discharge limitation specified in Provision I. A. of this permit, including such accelerated or additional monitoring of the discharge and/or the receiving waterbody as necessary to determine the nature and impact of the noncomplying discharge.

#### **2. Right of Entry and Inspection**

The Permittee shall allow the Director, or an authorized representative, upon the presentation of proper credentials and other documents as may be required by law to:

- (1) Enter upon the Permittee's premises where a regulated facility or activity or point source is located or conducted, or where records must be kept under the conditions of the permit;
- (2) Have access to and copy, at reasonable times, any records that must be kept under the conditions of the permits;
- (3) Inspect any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under the permit; and
- (4) Sample or monitor, for the purposes of assuring permit compliance or as otherwise authorized by the AWPCA, any substances or parameters at any location.

### **C. BYPASS AND UPSET**

#### **1. Bypass**

- a. Any bypass is prohibited except as provided in b. and c. below:
- b. A bypass is not prohibited if:
  - (1) It does not cause any discharge limitation specified in Provision I. A. of this permit to be exceeded;
  - (2) It enters the same receiving stream as the permitted outfall; and
  - (3) It is necessary for essential maintenance of a treatment or control facility or system to assure efficient operation of such facility or system.
- c. A bypass is not prohibited and need not meet the discharge limitations specified in Provision I. A. of this permit if:
  - (1) It is unavoidable to prevent loss of life, personal injury, or severe property damage;

- (2) There are no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime (this condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of equipment downtime or preventive maintenance); and
  - (3) The Permittee submits a written request for authorization to bypass to the Director at least ten (10) days prior to the anticipated bypass (if possible), the Permittee is granted such authorization, and the Permittee complies with any conditions imposed by the Director to minimize any adverse impact on human health or the environment resulting from the bypass.
  - d. The Permittee has the burden of establishing that each of the conditions of Provision II. C. 1. b. or c. have been met to qualify for an exception to the general prohibition against bypassing contained in a. and an exemption, where applicable, from the discharge limitations specified in Provision I. A. of this permit.
2. Upset
- a. A discharge which results from an upset need not meet the discharge limitations specified in Provision I. A. of this permit if:
    - (1) No later than 24-hours after becoming aware of the occurrence of the upset, the Permittee orally reports the occurrence and circumstances of the upset to the Director or his designee; and
    - (2) No later than five (5) days after becoming aware of the occurrence of the upset, the Permittee furnishes the Director with evidence, including properly signed, contemporaneous operating logs, or other relevant evidence, demonstrating that:
      - (i) An upset occurred;
      - (ii) The Permittee can identify the specific cause(s) of the upset;
      - (iii) The Permittee's facility was being properly operated at the time of the upset; and
      - (iv) The Permittee promptly took all reasonable steps to minimize any adverse impact on human health or the environment resulting from the upset.
  - b. The Permittee has the burden of establishing that each of the conditions of Provision II C. 2. a. of this permit have been met to qualify for an exemption from the discharge limitations specified in Provision I. A. of this permit.

#### **D. DUTY TO COMPLY WITH PERMIT, RULES, AND STATUTES**

##### **1. Duty to Comply**

- a. The Permittee must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the AWPCA and the FWPCA and is grounds for enforcement action, for permit termination, revocation and reissuance, suspension, modification, or denial of a permit renewal application.
- b. The necessity to halt or reduce production or other activities in order to maintain compliance with the conditions of the permit shall not be a defense for a Permittee in an enforcement action.
- c. The discharge of a pollutant from a source not specifically identified in the permit application for this permit and not specifically included in the description of an outfall in this permit is not authorized and shall constitute noncompliance with this permit.
- d. The Permittee shall take all reasonable steps, including cessation of production or other activities, to minimize or prevent any violation of this permit or to minimize or prevent any adverse impact of any permit violation.
- e. Nothing in this permit shall be construed to preclude or negate the Permittee's responsibility to apply for, obtain, or comply with other Federal, State, or Local Government permits, certifications, or licenses or to preclude from obtaining other federal, state, or local approvals, including those applicable to other ADEM programs and regulations.

##### **2. Removed Substances**

Solids, sludges, filter backwash, or any other pollutant or other waste removed in the course of treatment or control of wastewaters shall be disposed of in a manner that complies with all applicable Department Rules.

##### **3. Loss or Failure of Treatment Facilities**

Upon the loss or failure of any treatment facilities, including but not limited to the loss or failure of the primary source of power of the treatment facility, the Permittee shall, where necessary to maintain compliance with the discharge limitations specified in Provision I. A. of this permit, or any other terms or conditions of this permit, cease, reduce, or otherwise control production and/or all discharges until treatment is restored. If control of discharge during loss or failure of the

primary source of power is to be accomplished by means of alternate power sources, standby generators, or retention of inadequately treated effluent, the Permittee must furnish to the Director within six months a certification that such control mechanisms have been installed.

4. Compliance With Statutes and Rules

- a. This permit has been issued under ADEM Administrative Code, Chapter 335-6-6. All provisions of this chapter, that are applicable to this permit, are hereby made a part of this permit. A copy of this chapter may be obtained for a small charge from the Office of General Counsel, Alabama Department of Environmental Management, 1400 Coliseum Boulevard Montgomery, Alabama 36110-2059.
- b. This permit does not authorize the noncompliance with or violation of any Laws of the State of Alabama or the United States of America or any regulations or rules implementing such laws. FWPCA, 33 U.S.C. Section 1319, and Code of Alabama 1975, Section 22-22-14.

**E. PERMIT TRANSFER, MODIFICATION, SUSPENSION, REVOCATION, AND REISSUANCE**

1. Duty to Reapply or Notify of Intent to Cease Discharge

- a. If the Permittee intends to continue to discharge beyond the expiration date of this permit, the Permittee shall file a complete permit application for reissuance of this permit at least 180 days prior to its expiration. If the Permittee does not intend to continue discharge beyond the expiration of this permit, the Permittee shall submit written notification of this intent which shall be signed by an individual meeting the signatory requirements for a permit application as set forth in ADEM Administrative Code Rule 335-6-6-.09.
- b. Failure of the Permittee to apply for reissuance at least 180 days prior to permit expiration will void the automatic continuation of the expiring permit provided by ADEM Administrative Code Rule 335-6-6-.06 and should the permit not be reissued for any reason any discharge after expiration of this permit will be an unpermitted discharge.

2. Change in Discharge

Prior to any facility expansion, process modification or any significant change in the method of operation of the Permittee's treatment works, the Permittee shall provide the Director with information concerning the planned expansion, modification or change. The Permittee shall apply for a permit modification at least 180 days prior to any facility expansion, process modification, any significant change in the method of operation of the Permittee's treatment works or other actions that could result in the discharge of additional pollutants or increase the quantity of a discharged pollutant or could result in an additional discharge point. This condition applies to pollutants that are or that are not subject to discharge limitations in this permit. No new or increased discharge may begin until the Director has authorized it by issuance of a permit modification or a reissued permit.

3. Transfer of Permit

This permit may not be transferred or the name of the Permittee changed without notice to the Director and subsequent modification or revocation and reissuance of the permit to identify the new Permittee and to incorporate any other changes as may be required under the FWPCA or AWPCA. In the case of a change in name, ownership or control of the Permittee's premises only, a request for permit modification in a format acceptable to the Director is required at least 30 days prior to the change. In the case of a change in name, ownership or control of the Permittee's premises accompanied by a change or proposed change in effluent characteristics, a complete permit application is required to be submitted to the Director at least 180 days prior to the change. Whenever the Director is notified of a change in name, ownership or control, he may decide not to modify the existing permit and require the submission of a new permit application.

4. Permit Modification and Revocation

- a. This permit may be modified or revoked and reissued, in whole or in part, during its term for cause, including but not limited to, the following:
  - (1) If cause for termination under Provision II. E. 5. of this permit exists, the Director may choose to revoke and reissue this permit instead of terminating the permit;
  - (2) If a request to transfer this permit has been received, the Director may decide to revoke and reissue or to modify the permit; or
  - (3) If modification or revocation and reissuance is requested by the Permittee and cause exists, the Director may grant the request.
- b. This permit may be modified during its term for cause, including but not limited to, the following:
  - (1) If cause for termination under Provision II. E. 5. of this permit exists, the Director may choose to modify this permit instead of terminating this permit;



- (2) There are material and substantial alterations or additions to the facility or activity generating wastewater which occurred after permit issuance which justify the application of permit conditions that are different or absent in the existing permit;
- (3) The Director has received new information that was not available at the time of permit issuance and that would have justified the application of different permit conditions at the time of issuance;
- (4) A new or revised requirement(s) of any applicable standard or limitation is promulgated under Sections 301(b)(2)(C), (D), (E), and (F), and 307(a)(2) of the FWPCA;
- (5) Errors in calculation of discharge limitations or typographical or clerical errors were made;
- (6) To the extent allowed by ADEM Administrative Code, Rule 335-6-6-.17, when the standards or regulations on which the permit was based have been changed by promulgation of amended standards or regulations or by judicial decision after the permit was issued;
- (7) To the extent allowed by ADEM Administrative Code, Rule 335-6-6-.17, permits may be modified to change compliance schedules;
- (8) To agree with a granted variance under 301(c), 301(g), 301(h), 301(k), or 316(a) of the FWPCA or for fundamentally different factors;
- (9) To incorporate an applicable 307(a) FWPCA toxic effluent standard or prohibition;
- (10) When required by the reopener conditions in this permit;
- (11) When required under 40 CFR 403.8(e) (compliance schedule for development of pretreatment program);
- (12) Upon failure of the state to notify, as required by Section 402(b)(3) of the FWPCA, another state whose waters may be affected by a discharge permitted by this permit;
- (13) When required to correct technical mistakes, such as errors in calculation, or mistaken interpretations of law made in determining permit conditions; or
- (14) When requested by the Permittee and the Director determines that the modification has cause and will not result in a violation of federal or state law, regulations or rules.

#### 5. Termination

This permit may be terminated during its term for cause, including but not limited to, the following:

- a. Violation of any term or condition of this permit;
- b. The Permittee's misrepresentation or failure to disclose fully all relevant facts in the permit application or during the permit issuance process or the Permittee's misrepresentation of any relevant facts at any time;
- c. Materially false or inaccurate statements or information in the permit application or the permit;
- d. A change in any condition that requires either a temporary or permanent reduction or elimination of the permitted discharge;
- e. The Permittee's discharge threatens human life or welfare or the maintenance of water quality standards;
- f. Permanent closure of the facility generating the wastewater permitted to be discharged by this permit or permanent cessation of wastewater discharge;
- g. New or revised requirements of any applicable standard or limitation that is promulgated under Sections 301(b)(2)(C), (D), (E), and (F), and 307(a)(2) of the FWPCA that the Director determines cannot be complied with by the Permittee; or
- h. Any other cause allowed by the ADEM Administrative Code, Chapter 335-6-6.

#### 6. Suspension

This permit may be suspended during its term for noncompliance until the Permittee has taken action(s) necessary to achieve compliance.

#### 7. Stay

The filing of a request by the Permittee for modification, suspension or revocation of this permit, in whole or in part, does not stay any permit term or condition.

**F. COMPLIANCE WITH TOXIC POLLUTANT STANDARD OR PROHIBITION**

If any applicable effluent standard or prohibition (including any schedule of compliance specified in such effluent standard or prohibition) is established under Section 307(a) of the FWPCA, 33 U.S.C. Section 1317(a), for a toxic pollutant discharged by the Permittee, and such standard or prohibition is more stringent than any discharge limitation on the pollutant specified in Provision I. A. of this permit or controls a pollutant not limited in Provision I. A. of this permit, this permit shall be modified to conform to the toxic pollutant effluent standard or prohibition, and the Permittee shall be notified of such modification. If this permit has not been modified to conform to the toxic pollutant effluent standard or prohibition before the effective date of such standard or prohibition, the Permittee shall attain compliance with the requirements of the standard or prohibition within the time period required by the standard or prohibition and shall continue to comply with the standard or prohibition until this permit is modified or reissued.

**G. NOTICE TO DIRECTOR OF INDUSTRIAL USERS**

1. The Permittee shall not allow the introduction of wastewater, other than domestic wastewater, from a new direct discharger prior to approval and permitting, if applicable, of the discharge by the Department.
2. The Permittee shall not allow an existing indirect discharger to increase the quantity or change the character of its wastewater, other than domestic wastewater, prior to approval and permitting, if applicable, of the increased discharge by the Department.
3. The Permittee shall report to the Department any adverse impact caused or believed to be caused by an indirect discharger on the treatment process, quality of discharged water, or quality of sludge. Such report shall be submitted within seven days of the Permittee becoming aware of the adverse impacts.

**H. PROHIBITIONS**

The Permittee shall not allow, and shall take effective enforcement action to prevent and terminate, the introduction of any of the following into its treatment works by industrial users:

1. Pollutants which create a fire or explosion hazard in the treatment works;
2. Pollutants which will cause corrosive structural damage to the treatment works, or dischargers with a pH lower than 5.0 s.u., unless the works are specifically designed to accommodate such discharges;
3. Solid or viscous pollutants in amounts which will cause obstruction of flow in sewers, or other interference with the treatment works;
4. Pollutants, including oxygen demanding pollutants, released in a discharge of such volume or strength as to cause interference in the treatment works;
5. Heat in amounts which will inhibit biological activity in the treatment plant resulting in interference or in such quantities that the temperature of the treatment plant influent exceeds 40°C (104° F) unless the treatment plant is designed to accommodate such heat; and
6. Pollutants in amounts which exceed any applicable pretreatment standard under Section 307 of FWPCA or any approved revisions thereof.

## **PART III      ADDITIONAL REQUIREMENTS, CONDITIONS, AND LIMITATIONS**

### **A.   CIVIL AND CRIMINAL LIABILITY**

#### **1.   Tampering**

Any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained or performed under the permit shall, upon conviction, be subject to penalties as provided by the AWPCA.

#### **2.   False Statements**

Any person who knowingly makes any false statement, representation, or certification in any record or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or noncompliance shall, upon conviction, be subject to penalties as provided by the AWPCA.

#### **3.   Permit Enforcement**

- a.   Any NPDES permit issued or reissued by the Department is a permit for the purpose of the AWPCA and the FWPCA, and as such, any terms, conditions, or limitations of the permit are enforceable under state and federal law.
- b.   Any person required to have a NPDES permit pursuant to ADEM Administrative Code Chapter 335-6-6 and who discharges pollutants without said permit, who violates the conditions of said permit, who discharges pollutants in a manner not authorized by the permit, or who violates applicable orders of the Department or any applicable rule or standard of the Department, is subject to any one or combination of the following enforcement actions under applicable state statutes:
  - (1)   An administrative order requiring abatement, compliance, mitigation, cessation, clean-up, and/or penalties;
  - (2)   An action for damages;
  - (3)   An action for injunctive relief; or
  - (4)   An action for penalties.
- c.   If the Permittee is not in compliance with the conditions of an expiring or expired permit the Director may choose to do any or all of the following provided the Permittee has made a timely and complete application for reissuance of the permit:
  - (1)   Initiate enforcement action based upon the permit which has been continued;
  - (2)   Issue a notice of intent to deny the permit reissuance. If the permit is denied, the owner or operator would then be required to cease the activities authorized by the continued permit or be subject to enforcement action for operating without a permit;
  - (3)   Reissue the new permit with appropriate conditions; or
  - (4)   Take other actions authorized by these rules and AWPCA.

#### **4.   Relief from Liability**

Except as provided in Provision II. C. 1. (Bypass) and Provision II. C. 2. (Upset), nothing in this permit shall be construed to relieve the Permittee of civil or criminal liability under the AWPCA or FWPCA for noncompliance with any term or condition of this permit.

### **B.   OIL AND HAZARDOUS SUBSTANCE LIABILITY**

Nothing in this permit shall be construed to preclude the institution of any legal action or relieve the Permittee from any responsibilities, liabilities or penalties to which the Permittee is or may be subject under Section 311 of the FWPCA, 33 U.S.C. Section 1321.

### **C.   PROPERTY AND OTHER RIGHTS**

This permit does not convey any property rights in either real or personal property, or any exclusive privileges, nor does it authorize any injury to persons or property or invasion of other private rights, or any infringement of federal, state, or local laws or regulations, nor does it authorize or approve the construction of any physical structures or facilities or the undertaking of any work in any waters of the state or of the United States.

### **D.   AVAILABILITY OF REPORTS**

Except for data determined to be confidential under Code of Alabama 1975, Section 22-22-9(c), all reports prepared in accordance with the terms of this permit shall be available for public inspection at the offices of the Department. Effluent data shall not be considered confidential.

**E. EXPIRATION OF PERMITS FOR NEW OR INCREASED DISCHARGES**

1. If this permit was issued for a new discharger or new source, this permit shall expire eighteen months after the issuance date if construction of the facility has not begun during the eighteen-month period.
2. If this permit was issued or modified to allow the discharge of increased quantities of pollutants to accommodate the modification of an existing facility and if construction of this modification has not begun during the eighteen month period after issuance of this permit or permit modification, this permit shall be modified to reduce the quantities of pollutants allowed to be discharged to those levels that would have been allowed if the modification of the facility had not been planned.
3. Construction has begun when the owner or operator has:
  - a. Begun, or caused to begin as part of a continuous on-site construction program:
    - (1) Any placement, assembly, or installation of facilities or equipment; or
    - (2) Significant site preparation work including clearing, excavation, or removal of existing buildings, structures, or facilities which are necessary for the placement, assembly, or installation of new source facilities or equipment; or
  - b. Entered into a binding contractual obligation for the purpose of placement, assembly, or installation of facilities or equipment which are intended to be used in its operation within a reasonable time. Options to purchase or contracts which can be terminated or modified without substantial loss, and contracts for feasibility, engineering, and design studies do not constitute a contractual obligation under this paragraph.
4. Final plans and specifications for a waste treatment facility at a new source or new discharger, or a modification to an existing waste treatment facility must be submitted to and examined by the Department prior to initiating construction of such treatment facility by the Permittee.
5. Upon completion of construction of waste treatment facilities and prior to operation of such facilities, the Permittee shall submit to the Department a certification from a registered professional engineer, licensed to practice in the State of Alabama, that the treatment facilities have been built according to plans and specifications submitted to and examined by the Department.

**F. COMPLIANCE WITH WATER QUALITY STANDARDS**

1. On the basis of the Permittee's application, plans, or other available information, the Department has determined that compliance with the terms and conditions of this permit should assure compliance with the applicable water quality standards.
2. Compliance with permit terms and conditions notwithstanding, if the Permittee's discharge(s) from point sources identified in Provision I. A. of this permit cause or contribute to a condition in contravention of state water quality standards, the Department may require abatement action to be taken by the Permittee in emergency situations or modify the permit pursuant to the Department's Rules, or both.
3. If the Department determines, on the basis of a notice provided pursuant to this permit or any investigation, inspection or sampling, that a modification of this permit is necessary to assure maintenance of water quality standards or compliance with other provisions of the AWPCA or FWPCA, the Department may require such modification, and, in cases of emergency, the Director may prohibit the discharge until the permit has been modified.

**G. GROUNDWATER**

Unless specifically authorized under this permit, this permit does not authorize the discharge of pollutants to groundwater. Should a threat of groundwater contamination occur, the Director may require groundwater monitoring to properly assess the degree of the problem, and the Director may require that the Permittee undertake measures to abate any such discharge and/or contamination.

**H. DEFINITIONS**

1. Average monthly discharge limitation – means the highest allowable average of "daily discharges" over a calendar month, calculated as the sum of all "daily discharges" measured during a calendar month divided by the number of "daily discharges" measured during that month (zero discharge days shall not be included in the number of "daily discharges" measured and a less than detectable test result shall be treated as a concentration of zero if the most sensitive EPA approved method was used).
2. Average weekly discharge limitation - means the highest allowable average of "daily discharges" over a calendar week, calculated as the sum of all "daily discharges" measured during a calendar week divided by the number of "daily discharges" measured during that week (zero discharge days shall not be included in the number of "daily discharges" measured and a less than detectable test result shall be treated as a concentration of zero if the most sensitive EPA approved method was used).

3. Arithmetic Mean – means the summation of the individual values of any set of values divided by the number of individual values.
4. AWPCA – means the Alabama Water Pollution Control Act.
5. BOD – means the five-day measure of the pollutant parameter biochemical oxygen demand.
6. Bypass – means the intentional diversion of waste streams from any portion of a treatment facility.
7. CBOD – means the five-day measure of the pollutant parameter carbonaceous biochemical oxygen demand.
8. Daily discharge – means the discharge of a pollutant measured during any consecutive 24-hour period in accordance with the sample type and analytical methodology specified by the discharge permit.
9. Daily maximum – means the highest value of any individual sample result obtained during a day.
10. Daily minimum – means the lowest value of any individual sample result obtained during a day.
11. Day – means any consecutive 24-hour period.
12. Department – means the Alabama Department of Environmental Management.
13. Director – means the Director of the Department.
14. Discharge – means "[t]he addition, introduction, leaking, spilling or emitting of any sewage, industrial waste, pollutant or other waste into waters of the state". Code of Alabama 1975, Section 22-22-1(b)(9).
15. Discharge Monitoring Report (DMR) – means the form approved by the Director to accomplish reporting requirements of an NPDES permit.
16. DO – means dissolved oxygen.
17. 8HC – means 8-hour composite sample, including any of the following:
  - a. The mixing of at least 8 equal volume samples collected at constant time intervals of not more than 1 hour over a period of not less than 8 hours between the hours of 6:00 a.m. and 6:00 p.m. If the sampling period exceeds 8 hours, sampling may be conducted beyond the 6:00 a.m. to 6:00 p.m. period.
  - b. A sample continuously collected at a constant rate over period of not less than 8 hours between the hours of 6:00 a.m. and 6:00 p.m. If the sampling period exceeds 8 hours, sampling may be conducted beyond the 6:00 a.m. to 6:00 p.m. period.
18. EPA – means the United States Environmental Protection Agency.
19. FC – means the pollutant parameter fecal coliform.
20. Flow – means the total volume of discharge in a 24-hour period.
21. FWPCA – means the Federal Water Pollution Control Act.
22. Geometric Mean – means the Nth root of the product of the individual values of any set of values where N is equal to the number of individual values. The geometric mean is equivalent to the antilog of the arithmetic mean of the logarithms of the individual values. For purposes of calculating the geometric mean, values of zero (0) shall be considered one (1).
23. Grab Sample – means a single influent or effluent portion which is not a composite sample. The sample(s) shall be collected at the period(s) most representative of the discharge.
24. Indirect Discharger – means a nondomestic discharger who discharges pollutants to a publicly owned treatment works or a privately owned treatment facility operated by another person.
25. Industrial User – means those industries identified in the Standard Industrial Classification manual, Bureau of the Budget 1967, as amended and supplemented, under the category "Division D – Manufacturing" and such other classes of significant waste producers as, by regulation, the Director deems appropriate.
26. MGD – means million gallons per day.
27. Monthly Average – means the arithmetic mean of all the composite or grab samples taken for the daily discharges collected in one month period. The monthly average for flow is the arithmetic mean of all flow measurements taken in a one month period.
28. New Discharger – means a person, owning or operating any building, structure, facility or installation:
  - a. From which there is or may be a discharge of pollutants;
  - b. From which the discharge of pollutants did not commence prior to August 13, 1979, and which is not a new source; and

- c. Which has never received a final effective NPDES permit for dischargers at that site.
29. NH3-N – means the pollutant parameter ammonia, measured as nitrogen.
30. Notifiable sanitary sewer overflow – means an overflow, spill, release or diversion of wastewater from a sanitary sewer system that:
- Reaches a surface water of the State; or
  - May imminently and substantially endanger human health based on potential for public exposure including but not limited to close proximity to public or private water supply wells or in areas where human contact would be likely to occur.
31. Permit application – means forms and additional information that is required by ADEM Administrative Code Rule 335-6-6-.08 and applicable permit fees.
32. Point source – means "any discernible, confined and discrete conveyance, including but not limited to any pipe, channel, ditch, tunnel, conduit, well, discrete fissure, container, rolling stock, concentrated animal feeding operation, or vessel or other floating craft, . . . from which pollutants are or may be discharged." Section 502(14) of the FWPCA, 33 U.S.C. Section 1362(14).
33. Pollutant – includes for purposes of this permit, but is not limited to, those pollutants specified in Code of Alabama 1975, Section 22-22-1(b)(3) and those effluent characteristics specified in Provision I. A. of this permit.
34. Privately Owned Treatment Works – means any devices or system which is used to treat wastes from any facility whose operator is not the operator of the treatment works, and which is not a "POTW".
35. Publicly Owned Treatment Works – means a wastewater collection and treatment facility owned by the State, municipality, regional entity composed of two or more municipalities, or another entity created by the State or local authority for the purpose of collecting and treating municipal wastewater.
36. Receiving Stream – means the "waters" receiving a "discharge" from a "point source".
37. Severe property damage – means substantial physical damage to property, damage to the treatment facilities which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production.
38. Significant Source – means a source which discharges 0.025 MGD or more to a POTW or greater than five percent of the treatment work's capacity, or a source which is a primary industry as defined by the U.S. EPA or which discharges a priority or toxic pollutant.
39. TKN – means the pollutant parameter Total Kjeldahl Nitrogen.
40. TON – means the pollutant parameter Total Organic Nitrogen.
41. TRC – means Total Residual Chlorine.
42. TSS – means the pollutant parameter Total Suspended Solids.
43. 24HC – means 24-hour composite sample, including any of the following:
- The mixing of at least 8 equal volume samples collected at constant time intervals of not more than 2 hours over a period of 24 hours;
  - A sample collected over a consecutive 24-hour period using an automatic sampler composite to one sample. As a minimum, samples shall be collected hourly and each shall be no more than one twenty-fourth (1/24) of the total sample volume collected; or
  - A sample collected over a consecutive 24-hour period using an automatic composite sampler composited proportional to flow.
44. Upset – means an exceptional incident in which there is an unintentional and temporary noncompliance with technology-based permit discharge limitations because of factors beyond the reasonable control of the Permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.
45. Waters – means "[a]ll waters of any river, stream, watercourse, pond, lake, coastal, ground, or surface water, wholly or partially within the state, natural or artificial. This does not include waters which are entirely confined and retained completely upon the property of a single individual, partnership, or corporation unless such waters are used in interstate commerce." Code of Alabama 1975, Section 22-22-1(b)(2). Waters "include all navigable waters" as defined in Section 502(7) of the FWPCA, 22 U.S.C. Section 1362(7), which are within the State of Alabama.
46. Week – means the period beginning at twelve midnight Saturday and ending at twelve midnight the following Saturday.

47. Weekly (7-day and calendar week) Average – is the arithmetic mean of all samples collected during a consecutive 7-day period or calendar week, whichever is applicable. The calendar week is defined as beginning on Sunday and ending on Saturday. Weekly averages shall be calculated for all calendar weeks with Saturdays in the month. If a calendar week overlaps two months (i.e., the Sunday is in one month and the Saturday in the following month), the weekly average calculated for the calendar week shall be included in the data for the month that contains the Saturday.

#### **I. SEVERABILITY**

The provisions of this permit are severable, and if any provision of this permit or the application of any provision of this permit to any circumstance is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

## PART IV SPECIFIC REQUIREMENTS, CONDITIONS, AND LIMITATIONS

### A. SLUDGE MANAGEMENT PRACTICES

1. Applicability
  - a. Provisions of Provision IV.A. apply to a sewage sludge generated or treated in treatment works that is applied to agricultural and non-agricultural land, or that is otherwise distributed, marketed, incinerated, or disposed in landfills or surface disposal sites.
  - b. Provisions of Provision IV.A. do not apply to:
    - (1) Sewage sludge generated or treated in a privately owned treatment works operated in conjunction with industrial manufacturing and processing facilities and which receive no domestic wastewater.
    - (2) Sewage sludge that is stored in surface impoundments located at the treatment works prior to ultimate disposal.
2. Submitting Information
  - a. If applicable, the Permittee must submit annually with its Municipal Water Pollution Prevention (MWPP) report the following:
    - (1) Type of sludge stabilization/digestion method;
    - (2) Daily or annual sludge production (dry weight basis);
    - (3) Ultimate sludge disposal practice(s).
  - b. The Permittee shall provide sludge inventory data to the Director as requested. These data may include, but are not limited to, sludge quantity and quality reported in Provision IV.A.2.a as well as other specific analyses required to comply with State and Federal laws regarding solid and hazardous waste disposal.
  - c. The Permittee shall give prior notice to the Director of at least 30 days of any change planned in the Permittee's sludge disposal practices.
3. Reopener or Modification
  - a. Upon review of information provided by the Permittee as required by Provision IV.A.2. or, based on the results of an on-site inspection, the permit shall be subject to modification to incorporate appropriate requirements.
  - b. If an applicable "acceptable management practice" or if a numerical limitation for a pollutant in sewage sludge promulgated under Section 405 of FWPCA is more stringent than the sludge pollutant limit or acceptable management practice in this permit. This permit shall be modified or revoked or reissued to conform to requirements promulgated under Section 405. The Permittee shall comply with the limitations no later than the compliance deadline specified in applicable regulations as required by Section 405 of FWPCA.

### B. EFFLUENT TOXICITY LIMITATIONS AND BIOMONITORING REQUIREMENTS FOR CHRONIC TOXICITY

1. Chronic Toxicity Test
  - a. The permittee shall perform short-term chronic toxicity tests on the wastewater at Outfall 0011.
  - b. The samples shall be diluted using appropriate control water to the Instream Waste Concentration (IWC) which is **2 percent** effluent. The IWC is the actual concentration of effluent, after mixing, in the receiving stream during a 7-day, 10-year low flow period.
  - c. Any test result that shows a statistically significant reduction in survival, growth, or reproduction between the control and test samples at the 95% confidence level indicates chronic toxicity and shall constitute noncompliance with this permit.
2. General Test Requirements
  - a. A minimum of three (3) 24-hour composite samples shall be obtained for use in the above biomonitoring tests. Samples shall be collected every other day so that the laboratory receives water samples on the first, third, and fifth day of the seven-day test period. The holding time for each composite sample shall not exceed 36 hours. The control water shall be a water prepared in the laboratory in accordance with the EPA procedure described in EPA 821-R-02-013 (most current edition) or another control water selected by the Permittee and approved by the Department.
  - b. Test results shall be deemed unacceptable and the Permittee shall rerun the tests as soon as practical within the monitoring period for the following:
    - (1) For testing with *P. promelas*, effluent toxicity tests with control survival of less than 80% or if dry weight per surviving control organism is less than 0.25 mg;



- (2) For testing with *C. dubia*., if the number of young per surviving control organism is less than 15 or if less than 60% of surviving control females produce three broods; or
    - (3) If the other requirements of the EPA Test Procedure are not met.
  - c. In the event of an invalid test, upon subsequent completion of a valid test, the results of all tests, valid and invalid, are to be reported to the Department along with an explanation of the tests performed and the test results.
  - d. Toxicity tests shall be conducted for the duration of this permit in the month of **SEPTEMBER**. Should results from the Annual Toxicity test indicate that Outfall 001-1 exhibits chronic toxicity, then the Permittee must conduct the follow-up testing described in Part IV.B.4.a. In addition, the Permittee may then also be required to conduct toxicity testing in the months of MARCH, JUNE, SEPTEMBER, and DECEMBER.
3. Reporting Requirements
  - a. The Permittee shall notify the Department in writing within 48 hours after toxicity has been demonstrated by the scheduled test(s).
  - b. Biomonitoring test results obtained during each monitoring period shall be summarized and reported using the appropriate Discharge Monitoring Report (DMR) form approved by the Department. In accordance with Section 2 of this part, an effluent toxicity report containing the information in Sections 2 and 6 shall be included with the DMR. Two copies of the test results must be submitted to the Department no later than 28 days after the month that tests were performed.
4. Additional Testing Requirements
  - a. If chronic toxicity is indicated (i.e., noncompliance with permit limit), then the Permittee must perform two additional valid chronic toxicity tests in accordance with these procedures to determine the extent and duration of the toxic condition. The toxicity tests shall run consecutively beginning on the first calendar week following the date that the Permittee became aware of the permit noncompliance. The results of these follow-up tests shall be submitted to the Department no later than 28 days following the month the tests were performed.
  - b. After evaluation of the results of the follow-up tests, the Department will determine if additional action is appropriate and may require additional testing and/or toxicity reduction measures. The permittee may be required to perform a Toxicity Identification Evaluation (TIE) and/or a Toxicity Reduction Evaluation (TRE). The TIE/TRE shall be performed in accordance with the most recent protocols and guidance outlined by EPA (e.g., EPA/600/2-88/062, EPA/600/R-92/080, EPA/600/R-91-003, EPA/600/R-92/081, EPA/833/B-99/022, and/or EPA/600/6-91/005F)
5. Test Methods

The tests shall be performed in accordance with the latest edition of the "EPA Short-Term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to Freshwater Organisms." The Larval Survival and Growth Test, Method 1000.0, shall be used for the fathead minnow (*Pimephales promelas*) test and the Survival and Reproduction Test, Method 1002.0, shall be used for the cladoceran (*Ceriodaphnia dubia*) test.
6. Effluent Toxicity Testing Reports

The following information shall be submitted with each DMR unless otherwise directed by the Department. The Department may at any times suspend or reinstate this requirement or may decrease or increase the frequency of submittals.

  - a. Introduction
    - (1) Facility name, location and county
    - (2) Permit number
    - (3) Toxicity testing requirements of permit
    - (4) Name of receiving water body
    - (5) Contract laboratory information (if tests are performed under contract)
      - (a) Name of firm
      - (b) Telephone number
      - (c) Address
    - (6) Objective of test
  - b. Plant Operations
    - (1) Discharge Operating schedule (if other than continuous)
    - (2) Volume of discharge during sample collection to include Mean daily discharge on sample collection dates (MGD, CFS, GPM)
    - (3) Design flow of treatment facility at time of sampling

c. Source of Effluent and Dilution Water

(1) Effluent samples

- (a) Sampling point
- (b) Sample collection dates and times (to include composite sample start and finish times)
- (c) Sample collection method
- (d) Physical and chemical data of undiluted effluent samples (water temperature, pH, alkalinity, hardness, specific conductance, total residual chlorine (if applicable), etc.)
- (e) Lapsed time from sample collection to delivery
- (f) Lapsed time from sample collection to test initiation
- (g) Sample temperature when received at the laboratory

(2) Dilution Water

- (a) Source
- (b) Collection/preparation date(s) and time(s)
- (c) Pretreatment (if applicable)
- (d) Physical and chemical characteristics (water temperature, pH, alkalinity, hardness, specific conductance, etc.)

d. Test Conditions

- (1) Toxicity test method utilized
- (2) End point(s) of test
- (3) Deviations from referenced method, if any, and reason(s)
- (4) Date and time test started
- (5) Date and time test terminated
- (6) Type and volume of test chambers
- (7) Volume of solution per chamber
- (8) Number of organisms per test chamber
- (9) Number of replicate test chambers per treatment
- (10) Test temperature, pH, and dissolved oxygen as recommended by the method (to include ranges)
- (11) Specify if aeration was needed
- (12) Feeding frequency, amount, and type of food
- (13) Specify if (and how) pH control measures were implemented
- (14) Light intensity (mean)

e. Test Organisms

- (1) Scientific name
- (2) Life stage and age
- (3) Source
- (4) Disease(s) treatment (if applicable)

f. Quality Assurance

- (1) Reference toxicant utilized and source
- (2) Date and time of most recent chronic reference toxicant test(s), raw data, and current control chart(s). (The most recent chronic reference toxicant test shall be conducted within 30 days of the routine.)
- (3) Dilution water utilized in reference toxicant test
- (4) Results of reference toxicant test(s) (NOEC, IC25, etc.); report concentration-response relationship and evaluate test sensitivity
- (5) Physical and chemical methods utilized

g. Results

- (1) Provide raw toxicity data in tabular form, including daily records of affected organisms in each concentration (including controls) and replicate
- (2) Provide table of endpoints: NOECs, IC25s, PASS/FAIL, etc. (as required in the applicable NPDES permit)
- (3) Indicate statistical methods used to calculate endpoints
- (4) Provide all physical and chemical data required by method
- (5) Results of test(s) (NOEC, IC25, PASS/FAIL, etc.), report concentration-response relationship (definitive test only), report percent minimum significant difference (PMSD) calculated for sublethal endpoints determined by hypothesis testing.

h. Conclusions and Recommendations

- (1) Relationship between test endpoints and permit limits

(2) Actions to be taken

1/ Adapted from "Short-Term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to Freshwater Organisms", Fourth Edition, October 2002 (EPA 821-R-02-013), Section 10, Report Preparation.

**C. TOTAL RESIDUAL CHLORINE (TRC) REQUIREMENTS**

1. If chlorine is not utilized for disinfection purposes, TRC monitoring under Part I of this Permit is not required. If TRC monitoring is not required, "NODI = 9" (conditional monitoring) should be reported on the DMR forms.
2. Testing for TRC shall be conducted according to either the amperometric titration method or the DPD colorimetric method as specified in Section 408(C) or (E), Standards Methods for the Examination of Water and Wastewater, 18th edition. If chlorine is not detected prior to actual discharge to the receiving stream using one of these methods (i.e., the analytical result is less than the detection level), the Permittee shall report on the DMR form "NODI = B" or "0". The Permittee shall then be considered to be in compliance with the daily maximum concentration limit for TRC.
3. This permit contains a maximum allowable TRC level in the effluent. The Permittee is responsible for determining the minimum TRC level needed in the chlorine contact chamber to comply with E.coli limits. The effluent shall be dechlorinated if necessary to meet the maximum allowable effluent TRC level.
4. The sample collection point for effluent TRC shall be at a point downstream of the chlorine contact chamber (downstream of dechlorination if applicable). The exact location is to be approved by the Director.

**D. PLANT CLASSIFICATION**

The Permittee shall report to the Director within 30 days of the effective date of this permit, the name, address and operator number of the certified wastewater operator in responsible charge of the facility. Unless specified elsewhere in this permit, this facility shall be classified in accordance with ADEM Admin. Code R. 335-10-1-.03.

**E. POLLUTANT SCANS**

The Permittee shall sample and analyze for the pollutants listed in 40 CFR 122 Appendix J Table 2. The Permittee shall provide data from a minimum of three samples collected within the four and one half years prior to submitting a permit application. Samples must be representative of the seasonal variation in the discharge from each outfall.

**F. PERMIT REQUIREMENT FOR DAM**

No discharge should occur if the dam gates are closed. If the facility proposes to discharge with dam gates closed, a permit modification would be required.

ALABAMA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT  
WATER DIVISION – INDUSTRIAL AND MUNICIPAL SECTIONS  
**NONCOMPLIANCE NOTIFICATION FORM**

PERMITTEE NAME: \_\_\_\_\_ PERMIT NO: \_\_\_\_\_

FACILITY LOCATION: \_\_\_\_\_

DMR REPORTING PERIOD: \_\_\_\_\_

1. DESCRIPTION OF DISCHARGE: (Include outfall number (s))

2. DESCRIPTION OF NON-COMPLIANCE: (Attach additional pages if necessary):

LIST EFFLUENT VIOLATIONS (If applicable)			
Outfall Number (s)	NONCOMPLIANCE PARAMETER(S)	Result Reported (Include units)	Permit Limit (Include units)

LIST MONITORING / REPORTING VIOLATIONS (If applicable)		
Outfall Number (s)	NONCOMPLIANCE PARAMETER(S)	Monitoring / Reporting Violation (Provide description)

3. CAUSE OF NON-COMPLIANCE (Attach additional pages if necessary):

4. PERIOD OF NONCOMPLIANCE: (Include exact date(s) and time(s) or, if not corrected, the anticipated time the noncompliance is expected to continue):

5. DESCRIPTION OF STEPS TAKEN AND/OR BEING TAKEN TO REDUCE OR ELIMINATE THE NONCOMPLYING DISCHARGE AND TO PREVENT ITS RECURRENCE (attach additional pages if necessary):

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

\_\_\_\_\_  
NAME AND TITLE OF RESPONSIBLE OFFICIAL (type or print)

\_\_\_\_\_  
SIGNATURE OF RESPONSIBLE OFFICIAL / DATE SIGNED

## NPDES PERMIT RATIONALE

NPDES Permit No: **AL0056146**

Date: October 7, 2014

Permit Applicant: Heflin Water Works and Sewer Board  
Post Office Box 488  
Heflin, Alabama 36264

Location: Heflin Lagoon  
U.S. Highway 78 West  
Heflin, Alabama 36264  
Cleburne County

Draft Permit is: Initial Issuance:  
Reissuance due to expiration: **X**  
Modification of existing permit:  
Revocation and Reissuance:

Basis for Limitations: Water Quality Model: CBOD<sub>5</sub>, NH<sub>3</sub>N, and TKN  
Reissuance with no modification: pH, TSS, Percent Removals, CBOD<sub>5</sub>, NH<sub>3</sub>N,  
and TKN  
Instream calculation at 7Q10: IWC  $\approx$  2%  
Toxicity based: TRC  
Secondary Treatment Levels: CBOD<sub>5</sub> Percent Removal  
Other (described below): E. coli, pH, TSS, and TSS Percent Removal

Design Flow in Million Gallons per Day: 0.6 MGD

Description of Discharge: Outfall Number 0011; Effluent discharge to the  
Tallapoosa River, which is classified as Fish and  
Wildlife (F&W).

Discussion: This is a permit reissuance due to permit expiration. This discharge limits for Five Day Carbonaceous Biochemical Oxygen Demand (CBOD<sub>5</sub>), Total Ammonia Nitrogen (NH<sub>3</sub>N), and Total Kjeldahl Nitrogen (TKN) were developed by the Municipal Section based on a Waste Load Allocation (WLA) model performed by the Department's Water Quality Branch on July 13, 2009. The effluent limits are based upon the Howle and Turner Dams being open. However, according to the July 13, 2009 WLA model, the effluent limits for Heflin Lagoon under open dam stream flow conditions would equate to stream flow conditions should the dams ever be removed.

The summer (April through October) and winter (November through March) monthly average limits for CBOD<sub>5</sub> are 20.0 mg/L and 25.0 mg/L, respectively, while summer and winter monthly average limits for NH<sub>3</sub>N are 15.0 mg/L and 20.0 mg/L, respectively. The summer and winter monthly average limits for TKN are 30.0 mg/L and 40.0 mg/L, respectively.

The pH limits were developed in accordance with the Water-Use designation of the receiving stream and the Municipal Section's Permit Development Guidance. The daily minimum and maximum pH limits

have not changed from the previous permit. The daily minimum and daily maximum pH limits are 6.0 s.u. and 9.0 s.u., respectively.

The monthly average Total Suspended Solids (TSS) limit is established at 90.0 mg/L in accordance with ADEM's Permit Development Rationale and 40 CFR 133.105. Minimum percent removal limits of 65 percent and 85 percent are being imposed on TSS and CBOD<sub>5</sub> respectively, in accordance with 40 CFR 133.105 and 40 CFR 133.102, respectively.

The receiving stream is the Tallapoosa River and it is a Tier I stream. The stream is not listed on the current 303(d) list. There is an organic enrichment/dissolved oxygen (OE/DO) TMDL that was developed by ADEM and approved by EPA on January 18, 2007. The limits recommend for this facility by the EPA approved OE/DO TMDL has been set forth in this permit and should be protective of water quality.

This permit imposes monthly monitoring during the growing season (April through October) for the following nutrient-related parameters: Total Phosphorus (TP) and Nitrate plus Nitrite (NO<sub>2</sub> + NO<sub>3</sub>N). Monitoring for these nutrient-related parameters are being imposed so that sufficient information will be available regarding the nutrient contribution from this point source should it be necessary at some later time to impose additional nutrient limits on this discharge.

This Permittee treats a mixture of municipal and industrial wastewater. Therefore, the Department completed a Reasonable Potential Analysis (RPA) of the wastewater data submitted in Part D of the Permittee's application (i.e., per 40 CFR Part 122 Appendix J – Table 2) and DMR data submitted to the Department. The RPA indicated whether any pollutants in the treated effluent have the potential to contribute to excursions of Alabama's in-stream water quality standards. The RPA was based on a 7Q10 of 44.6 cfs, mean annual flow of 846.86 cfs, and a hardness of 24.13 mg/L and background data from monitoring station TA-2 provided by the Department's Water Quality Branch. The monitoring station collected data for Antimony, Arsenic, Cadmium, Chromium, Copper, Lead, Mercury, Nickel, Selenium, Silver, Thallium, and Zinc. The data collected from monitoring station TA-2 was below the method detection limit for each of these parameters and therefore did not affect the RPA. Based on the RPA, it was determined that there was no reasonable potential for in-stream water quality standards to be exceeded.

The Department amended ADEM Administrative Code R.335-6-10-.09 to change the bacterial indicator organisms and associated criteria for non-coastal waters from fecal coliform to *Escherichia coli* (E. coli) to be consistent with the United States Environmental Protection Agency (EPA) recommendations for protection against water-borne illnesses. As a result, this permit includes E. coli limits that are consistent with the revised regulations.

The imposed E. coli limits were determined based on the water-use classification of the receiving stream. Since the Tallapoosa River is classified as Fish & Wildlife, the E. coli limits for summer (June through September) are 126 col/100 mL (monthly average) and 487 col/100 mL (daily maximum), while the limits for the winter (October through May) are 548 col/100 mL (monthly average) and 2507 col/100 mL (daily maximum).

A monthly average and daily maximum Total Residual Chlorine (TRC) limits of 0.539 mg/L and 0.932 mg/L, respectively, are being imposed in this proposed permit. The TRC limits were developed based on EPA suggested WQ criteria and the Department's Permit Development Rationale, and should be protective of acute and chronic toxicity criteria in the receiving stream. If monitoring is not applicable during the monitoring period, enter "NODI=9" on the monthly DMR.

Based on the Department's review of the application and receiving water conditions, chronic toxicity testing is warranted in this proposed permit. Testing is required annually during the month of September.

The monitoring frequency for most parameters is one day per week. The monitoring frequency for nutrient-related parameters (TP and  $\text{NO}_2+\text{NO}_3\text{N}$ ) is once per month. Flow is to be monitored continuously as in the previous permit.  $\text{CBOD}_5$  and TSS percent removals are to be calculated monthly.

ADEM Administrative Rule 335-6-10-.12 requires applicants to new or expanded discharges to Tier II waters demonstrate that the proposed discharge is necessary for important economic or social development in the area in which the waters are located. The application submitted by the facility is not for a new discharge and discharges to a Tier II water, so the applicant is not required to demonstrate that the discharge is necessary for economic and social development.

Prepared by: S. Torbert

## TOXICITY AND DISINFECTION RATIONALE

Facility Name:	Heflin Lagoon	
NPDES Permit Number:	AL0056146	
Receiving Stream:	Tallapoosa River	
Facility Design Flow (Qw):	0.600 MGD	
Receiving Stream 7Q10:	44.600 cfs	
Receiving Stream 1Q10:	33.450 cfs	(Estimated at 0.75 * 7Q10)
Winter Headwater Flow (WHF):	112.70 cfs	
Summer Temperature for CCC:	18 deg. Celsius	
Winter Temperature for CCC:	28 deg. Celsius	
Headwater Background NH3-N Level:	0.05 mg/l	
Receiving Stream pH:	7.0 s.u.	
Headwater Background FC Level (summer):	N./A.	(Only applicable for facilities with diffusers.)
(winter)	N./A.	

The Stream Dilution Ratio (SDR) is calculated using the 7Q10 for all stream classifications.

$$\text{Stream Dilution Ratio (SDR)} = \frac{Q_w}{7Q10 + Q_w} = 2.04\%$$

### AMMONIA TOXICITY LIMITATIONS

Toxicity-based ammonia limits are calculated in accordance with the Ammonia Toxicity Protocol and the General Guidance for *Writing Water Quality Based Toxicity Permits*.

If the Limiting Dilution is less than 1%, the waterbody is considered stream-dominated and the CMC applies.

If the Limiting Dilution is greater than 1%, the waterbody is considered effluent-dominated and the CCC applies.

$$\begin{aligned} \text{Limiting Dilution} &= \frac{Q_w}{7Q10 + Q_w} \\ &= 2.04\% \quad \text{Effluent-Dominated, CCC Applies} \end{aligned}$$

Criterion Maximum Concentration (CMC):	CMC = $0.411 / (1 + 10^{(7.204 - \text{pH})}) + 58.4 / (1 + 10^{(\text{pH} - 7.204)})$
Criterion Continuous Concentration (CCC):	CCC = $[0.0577 / (1 + 10^{(7.688 - \text{pH})}) + 2.487 / (1 + 10^{(\text{pH} - 7.688))}] * \text{Min}[2.85, 1.45 * 10^{(0.028 * (25 - T))}]$

	<u>CMC</u>	<u>CCC</u>
Allowable Summer Instream NH3-N:	36.09 mg/l	4.72 mg/l
Allowable Winter Instream NH3-N:	36.09 mg/l	2.48 mg/l

$$\begin{aligned} \text{Summer NH3-N Toxicity Limit} &= \frac{[(\text{Allowable Instream NH3-N}) * (7Q10 + Q_w)] - [(\text{Headwater NH3-N}) * (7Q10)]}{Q_w} \\ &= 229.4 \text{ mg/l NH3-N at 7Q10} \end{aligned}$$

$$\begin{aligned} \text{Winter NH3-N Toxicity Limit} &= \frac{[(\text{Allowable Instream NH3-N}) * (\text{WHF} + Q_w)] - [(\text{Headwater NH3-N}) * (\text{WHF})]}{Q_w} \\ &= 297.7 \text{ mg/l NH3-N at Winter Flow} \end{aligned}$$

The ammonia limits established in the permit will be the lesser of the DO-based ammonia limit (from the wasteload allocation model) or the toxicity limits calculated above.

	<u>DO-based NH3-N limit</u>	<u>Toxicity-based NH3-N limit</u>
Summer	15.00 mg/l NH3-N	229.40 mg/l NH3-N
Winter	20.00 mg/l NH3-N	297.70 mg/l NH3-N

**Summer: The DO based limit of 15.00 mg/l NH3-N applies.**

**Winter: The DO based limit of 20.00 mg/l NH3-N applies.**



## TOXICITY TESTING REQUIREMENTS (REFERENCE: MUNICIPAL BRANCH TOXICITY PERMITTING STRATEGY)

The following factors trigger toxicity testing requirements:

1. Facility design flow is equal to or greater than 1.0 MGD (major facility).
2. There are significant industrial contributors (SID permits).

Acute toxicity testing is specified for A&I receiving streams, or for stream dilution ratios of 1% or less.

Chronic toxicity testing is specified for all other situations requiring toxicity testing.

### **Chronic toxicity testing is required**

$$\text{Instream Waste Concentration (IWC)} = \frac{Q_w}{7Q_{10} + Q_w} = 2.04\% \quad \text{Note: This number will be rounded up for toxicity testing purposes.}$$

## DISINFECTION REQUIREMENTS

Bacteria limits are required, and will be the water quality limit for the receiving stream, except where diffusers are used the limit may be adjusted for the dilution provided by the diffuser.

See the attached Disinfection Guidance for applicable stream standards.

**(Non-coastal limits apply)**

Applicable Stream Classification: **Fish & Wildlife**

Disinfection Type: **Chlorination**

Limit calculation method: **Limits based on meeting stream standards at the point of discharge.**

	Stream Standard (colonies/100ml)	Effluent Limit (colonies/100ml)
<b><u>E. Coli (applies to Non-coastal and Shellfish Harvesting Coastal)</u></b>		
Monthly limit as monthly average (October through May):	548	<b>548</b>
Monthly limit as monthly average (June through September):	126	<b>126</b>
Daily Max (October through May):	2507	<b>2507</b>
Daily Max (June through September):	487	<b>487</b>
<b><u>Enterococci (applies to Coastal)</u></b>		
Monthly limit as geometric mean (October through May):	Not applicable	<b>Not applicable</b>
Monthly limit as geometric mean (June through September):	Not applicable	<b>Not applicable</b>
Daily Max (October through May):	Not applicable	<b>Not applicable</b>
Daily Max (June through September):	Not applicable	<b>Not applicable</b>

## MAXIMUM ALLOWABLE CHLORINATION LIMITS

Toxicity-based chlorine limits are calculated in accordance with the General Guidance for Writing Water Quality Based Toxicity Permits.

Chlorine has been shown to be acutely toxic at 0.019 mg/l and chronically toxic at 0.011 mg/l.

Maximum allowable TRC in effluent:	0.539 mg/l (chronic)	(0.011)/(SDR)
Maximum allowable TRC in effluent:	0.932 mg/l (acute)	(0.019)/(SDR)

NOTE: A maximum chlorine limit will be imposed such that the instream concentration will not exceed acutely toxic concentrations in A & I streams and chronically toxic concentrations in all other streams, but may not exceed 1.0 mg/l.

Prepared By:

Shanda Torbert

Date:

10/7/2014

Q <sub>d</sub> *C <sub>d</sub> + Q <sub>d2</sub> *C <sub>d2</sub> + Q <sub>s</sub> *C <sub>s</sub> = Q <sub>r</sub> *C <sub>r</sub>								Enter Max Daily Discharge as reported by Applicant (C <sub>max</sub> )	Enter Avg Daily Discharge as reported by Applicant (C <sub>avg</sub> )	Partition Coefficient (Stream / Lake)
ID	Pollutant	Carcinogen Yes*	Type	Background from upstream source (C <sub>d</sub> ) Daily Max	Background from upstream source (C <sub>d</sub> ) Monthly Ave	Background Instream (C <sub>e</sub> ) Daily Max	Background Instream (C <sub>e</sub> ) Monthly Ave			
				µg/l	µg/l	µg/l	µg/l	µg/l	µg/l	
1	Antimony		Metals	0	0	0	0	0	0	-
2	Arsenic**	YES	Metals	0	0	0	0	0	0	0.574
3	Beryllium		Metals	0	0	0	0	0	0	-
4	Cadmium**		Metals	0	0	0	0	0	0	0.236
5	Chromium / Chromium III**		Metals	0	0	0	0	0	0	0.210
6	Chromium / Chromium VI**		Metals	0	0	0	0	0	0	-
7	Copper**		Metals	0	0	0	0	58	0	0.388
8	Lead**		Metals	0	0	0	0	0	0	0.467
9	Mercury**		Metals	0	0	0	0	0.014	0.0036	0.302
10	Nickel**		Metals	0	0	0	0	0	0	0.505
11	Selenium		Metals	0	0	0	0	0	0	-
12	Silver		Metals	0	0	0	0	0	0	-
13	Thallium		Metals	0	0	0	0	0	0	-
14	Zinc**		Metals	0	0	0	0	0	0	0.330
15	Cyanide		Metals	0	0	0	0	15	0	-
16	Total Phenolic Compounds		Metals	0	0	0	0	0	0	-
17	Hardness (As CaCO3)		Metals	0	0	0	0	69500	58700	-
18	Acrolein		VOC	0	0	0	0	0	0	-
19	Acrylonitrile*	YES	VOC	0	0	0	0	0	0	-
20	Aldrin	YES	VOC	0	0	0	0	0	0	-
21	Benzene*	YES	VOC	0	0	0	0	0	0	-
22	Bromoform*	YES	VOC	0	0	0	0	0	0	-
23	Carbon Tetrachloride*	YES	VOC	0	0	0	0	0	0	-
24	Chlordane	YES	VOC	0	0	0	0	0	0	-
25	Chlorobenzene		VOC	0	0	0	0	0	0	-
26	Chlorodibromo-Methane*	YES	VOC	0	0	0	0	0	0	-
27	Chloroethane		VOC	0	0	0	0	0	0	-
28	2-Chloro-Ethylvinyl Ether		VOC	0	0	0	0	0	0	-
29	Chloroform*	YES	VOC	0	0	0	0	0	0	-
30	4,4'-DDD	YES	VOC	0	0	0	0	0	0	-
31	4,4'-DDE	YES	VOC	0	0	0	0	0	0	-
32	4,4'-DDT	YES	VOC	0	0	0	0	0	0	-
33	Dichlorobromo-Methane*	YES	VOC	0	0	0	0	0	0	-
34	1,1-Dichloroethane		VOC	0	0	0	0	0	0	-
35	1,2-Dichloroethane*	YES	VOC	0	0	0	0	0	0	-
36	Trans-1,2-Dichloro-Ethylene		VOC	0	0	0	0	0	0	-
37	1,1-Dichloroethene*	YES	VOC	0	0	0	0	0	0	-
38	1,2-Dichloropropane		VOC	0	0	0	0	0	0	-
39	1,3-Dichloro-Propylene		VOC	0	0	0	0	0	0	-
40	Dieldrin	YES	VOC	0	0	0	0	0	0	-
41	Ethylbenzene		VOC	0	0	0	0	0	0	-
42	Methyl Bromide		VOC	0	0	0	0	0	0	-
43	Methyl Chloride		VOC	0	0	0	0	0	0	-
44	Methylene Chloride*	YES	VOC	0	0	0	0	0	0	-
45	1,1,2,2-Tetrachloro-Ethane*	YES	VOC	0	0	0	0	0	0	-
46	Tetrachloro-Ethylene*	YES	VOC	0	0	0	0	0	0	-
47	Toluene		VOC	0	0	0	0	0	0	-
48	Toxaphene	YES	VOC	0	0	0	0	0	0	-
49	Triisobutylene (TIBT)	YES	VOC	0	0	0	0	0	0	-
50	1,1,1-Trichloroethane		VOC	0	0	0	0	0	0	-
51	1,1,2-Trichloroethane*	YES	VOC	0	0	0	0	0	0	-
52	Trichloroethylene*	YES	VOC	0	0	0	0	0	0	-
53	Vinyl Chloride*	YES	VOC	0	0	0	0	0	0	-
54	p-Chloro-m-Cresol		Acids	0	0	0	0	0	0	-
55	2-Chlorophenol		Acids	0	0	0	0	0	0	-
56	2,4-Dichlorophenol		Acids	0	0	0	0	0	0	-
57	2,4-Dimethylphenol		Acids	0	0	0	0	0	0	-
58	4,6-Dinitro-O-Cresol		Acids	0	0	0	0	0	0	-
59	4-Dinitrophenol		Acids	0	0	0	0	0	0	-
60	4,6-Dinitro-2-methylphenol	YES	Acids	0	0	0	0	0	0	-
61	Dioxin (2,3,7,8-TCDD)	YES	Acids	0	0	0	0	0	0	-
62	2-Nitrophenol		Acids	0	0	0	0	0	0	-
63	4-Nitrophenol		Acids	0	0	0	0	0	0	-
64	Pentachlorophenol*	YES	Acids	0	0	0	0	0	0	-
65	Phenol		Acids	0	0	0	0	0	0	-
66	2,4,6-Trichlorophenol*	YES	Acids	0	0	0	0	0	0	-
67	Acephenylene		Bases	0	0	0	0	0	0	-
68	Acenaphthylene		Bases	0	0	0	0	0	0	-
69	Anthracene		Bases	0	0	0	0	0	0	-
70	Benidine		Bases	0	0	0	0	0	0	-
71	Benzo(A)Anthracene*	YES	Bases	0	0	0	0	0	0	-
72	Benzo(A)Pyrene*	YES	Bases	0	0	0	0	0	0	-
73	1,4-Benzo-Fluoranthene		Bases	0	0	0	0	0	0	-
74	Benzo(ghi)Perylene		Bases	0	0	0	0	0	0	-
75	Benzo(k)Fluoranthene		Bases	0	0	0	0	0	0	-
76	Bis (2-Chloroethoxy) Methane		Bases	0	0	0	0	0	0	-
77	Bis (2-Chloroethyl)-Ether*	YES	Bases	0	0	0	0	0	0	-
78	Bis (2-Chloroisopropyl) Ether		Bases	0	0	0	0	0	0	-
79	Bis (2-Ethylhexyl) Phthalate*	YES	Bases	0	0	0	0	0	0	-
80	4-Bromophenyl Phenyl Ether		Bases	0	0	0	0	0	0	-
81	Butyl Benzyl Phthalate		Bases	0	0	0	0	0	0	-
82	2-Chloronaphthalene		Bases	0	0	0	0	0	0	-
83	4-Chlorophenyl Phenyl Ether		Bases	0	0	0	0	0	0	-
84	Chrysene*	YES	Bases	0	0	0	0	0	0	-
85	Di-N-Butyl Phthalate		Bases	0	0	0	0	0	0	-
86	Di-N-Octyl Phthalate		Bases	0	0	0	0	0	0	-
87	Dibenzo(A,h)Anthracene*	YES	Bases	0	0	0	0	0	0	-
88	1,2-Dichlorobenzene		Bases	0	0	0	0	0	0	-
89	1,3-Dichlorobenzene		Bases	0	0	0	0	0	0	-
90	1,4-Dichlorobenzene		Bases	0	0	0	0	0	0	-
91	3,3-Dichlorobenzene*	YES	Bases	0	0	0	0	0	0	-
92	Diethyl Phthalate		Bases	0	0	0	0	0	0	-
93	Dimethyl Phthalate		Bases	0	0	0	0	0	0	-
94	2,4-Dinitrotoluene*	YES	Bases	0	0	0	0	0	0	-
95	2,6-Dinitrotoluene		Bases	0	0	0	0	0	0	-
96	1,2-Diphenylhydrazine		Bases	0	0	0	0	0	0	-
97	Endosulfan (alpha)	YES	Bases	0	0	0	0	0	0	-
98	Endosulfan (beta)	YES	Bases	0	0	0	0	0	0	-
99	Endosulfan sulfate	YES	Bases	0	0	0	0	0	0	-
100	Endrin	YES	Bases	0	0	0	0	0	0	-
101	Endrin Aldehyde	YES	Bases	0	0	0	0	0	0	-
102	Fluoranthene		Bases	0	0	0	0	0	0	-
103	Fluorene		Bases	0	0	0	0	0	0	-
104	Heptachlor	YES	Bases	0	0	0	0	0	0	-
105	Heptachlor Epoxide	YES	Bases	0	0	0	0	0	0	-
106	Hexachlorobenzene*	YES	Bases	0	0	0	0	0	0	-
107	Hexachlorobutadiene*	YES	Bases	0	0	0	0	0	0	-
108	Hexachlorocyclohexan (alpha)	YES	Bases	0	0	0	0	0	0	-
109	Hexachlorocyclohexan (beta)	YES	Bases	0	0	0	0	0	0	-
110	Hexachlorocyclohexan (gamma)	YES	Bases	0	0	0	0	0	0	-
111	Hexachlorocyclopentadiene		Bases	0	0	0	0	0	0	-
112	Hexachloroethane		Bases	0	0	0	0	0	0	-
113	Indeno(1,2,3-CD)Pyrene*	YES	Bases	0	0	0	0	0	0	-
114	Isoxanthone		Bases	0	0	0	0	0	0	-
115	Naphthalene		Bases	0	0	0	0	0	0	-
116	Nitrobenzene		Bases	0	0	0	0	0	0	-
117	N-Nitrosodi-N-Propylamine*	YES	Bases	0	0	0	0	0	0	-
118	N-Nitrosodi-N-Methylamine*	YES	Bases	0	0	0	0	0	0	-
119	N-Nitrosodi-N-Phenylamine*	YES	Bases	0	0	0	0	0	0	-
120	PCB-1016	YES	Bases	0	0	0	0	0	0	-
121	PCB-1221	YES	Bases	0	0	0	0	0	0	-
122	PCB-1232	YES	Bases	0	0	0	0	0	0	-
123	PCB-1242	YES	Bases	0	0	0	0	0	0	-
124	PCB-1248	YES	Bases	0	0	0	0	0	0	-
125	PCB-1254	YES	Bases	0	0	0	0	0	0	-
126	PCB-1260	YES	Bases	0	0	0	0	0	0	-
127	Phenanthrene		Bases	0	0	0	0	0	0	-
128	Pyrene		Bases	0	0	0	0	0	0	-
129	1,2,4-Trichlorobenzene		Bases	0	0	0	0	0	0	-

0.6	Enter Q <sub>e</sub> = wastewater discharge flow from facility (MGD)
0.928337	Q <sub>e</sub> = wastewater discharge flow (cfs) (this value is calculated from the MGD)
0	Enter or estimated, Q <sub>d2</sub> = background stream flow from upstream source (cfs)
44.6	Enter 7Q10, Q <sub>e</sub> = background stream flow in cfs above point of discharge
33.45	Enter or estimated, 1Q10, Q <sub>e</sub> = background stream flow in cfs above point of discharge (1Q10 estimated at 75% of 7Q10)
0	Enter flow from upstream discharge Q <sub>d2</sub> = background stream flow in MGD above point of discharge
846.86	Enter Mean Annual Flow, Q <sub>e</sub> = background stream flow in cfs above point of discharge
0	Enter 7Q2, Q <sub>e</sub> = background stream flow in cfs above point of discharge (For LWF class streams)
Enter to Left	Enter C <sub>e</sub> = background in-stream pollutant concentration in µg/l (assuming this is zero "0" unless there is data)
Q <sub>e</sub> + Q <sub>d2</sub> + Q <sub>s</sub>	Q <sub>e</sub> = resultant in-stream flow, after discharge
Calculated on other	C <sub>e</sub> = resultant in-stream pollutant concentration in µg/l in the stream (after complete mixing occurs)
24.13	Enter, Background Hardness above point of discharge (assumed 50 South of Birmingham and 100 North of Birmingham)
7.00 a.u.	Enter, Background pH above point of discharge
YES	Enter, Is discharge to a stream? "YES" Other option would be to a Lake. (This changes the partition coefficients for the metals)

\*\* Using Partition Coefficients

July 8, 2015

Modified: 8/4/09

Facility Name: Heflin Lagoon NPDES No.: AL0056146																		
Freshwater F&W classification:				Max Daily Discharge as reported by Applicant (C <sub>max</sub> )	Freshwater Acute (µg/l) Q <sub>a</sub> ≤1Q10				Avg Daily Discharge as reported by Applicant (C <sub>max</sub> )	Freshwater Chronic (µg/l) Q <sub>a</sub> = 7Q10				Human Health Consumption Fish only (µg/l) Carcinogen Q <sub>a</sub> = Annual Average Non-Carcinogen Q <sub>a</sub> = 7Q10				
ID	Pollutant	RP?	Carcinogen yes		Background from upstream source (Cd2) Daily Max	Water Quality Criteria (C <sub>c</sub> )	Draft Permit Limit (C <sub>max</sub> )	20% of Draft Permit Limit		RP?	Background from upstream source (Cd2) Monthly Ave	Water Quality Criteria (C <sub>c</sub> )	Draft Permit Limit (C <sub>max</sub> )	20% of Draft Permit Limit	RP?	Water Quality Criteria (C <sub>c</sub> )	Draft Permit Limit (C <sub>max</sub> )	20% of Draft Permit Limit
1	Antimony			0	0	-	-	-	0	0	-	-	-	-	3.73E+02	1.83E+04	3.66E+03	No
2	Arsenic		YES	0	0	592.334	21935.425	4387.085	No	0	261.324	12816.083	2563.217	No	3.03E-01	2.77E+02	5.53E+01	No
3	Beryllium			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
4	Cadmium			0	0	2.138	78.161	15.832	No	0	0.387	18.996	3.799	No	-	-	-	-
5	Chromium/ Chromium III			0	0	846.817	31359.475	6271.895	No	0	110.154	5402.247	1080.449	No	-	-	-	-
6	Chromium/ Chromium VI			0	0	16.000	592.515	118.503	No	0	11.000	539.472	107.894	No	-	-	-	-
7	Copper			0	58	9.074	336.019	67.204	No	0	6.850	335.924	67.185	No	1.30E+03	6.38E+04	1.28E+04	No
8	Lead			0	0	28.563	1057.764	211.553	No	0	1.113	54.588	10.918	No	4.24E-02	2.08E+00	4.16E-01	No
9	Mercury			0	0.014	2.400	88.877	17.775	No	0.0036	0.012	0.589	0.116	No	9.93E+02	4.87E+04	9.74E+03	No
10	Nickel			0	0	278.495	10313.255	2062.651	No	0	30.932	1517.002	303.400	No	2.43E+03	1.19E+05	2.38E+04	No
11	Selenium			0	0	20.000	740.643	148.129	No	0	5.000	245.214	49.043	No	-	-	-	-
12	Silver			0	0	0.279	10.328	2.066	No	0	-	-	-	-	-	-	-	-
13	Thallium			0	0	-	-	-	0	0	-	-	-	-	2.74E-01	1.34E+01	2.68E+00	No
14	Zinc			0	0	106.459	3942.404	788.481	No	0	107.330	5263.760	1052.752	No	1.49E+04	7.30E+05	1.46E+05	No
15	Cyanide			0	15	22.000	814.707	162.941	No	0	5.200	255.023	51.005	No	9.33E+03	4.58E+05	9.15E+04	No
16	Total Phenolic Compounds			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
17	Hardness (As CaCO3)			0	69500	-	-	-	0	56700	-	-	-	-	-	-	-	-
18	Acrolein			0	0	-	-	-	0	0	-	-	-	-	5.43E+00	2.68E+02	5.32E+01	No
19	Acrylonitrile		YES	0	0	-	-	-	0	0	-	-	-	-	1.44E-01	1.32E+02	2.63E+01	No
20	Aldrin		YES	0	0	3.000	111.096	22.219	No	0	1.300	63.756	12.751	No	2.94E-05	2.68E-02	5.37E-03	No
21	Benzene		YES	0	0	-	-	-	0	0	-	-	-	-	1.55E+01	1.41E+04	2.83E+03	No
22	Bromoform		YES	0	0	-	-	-	0	0	-	-	-	-	7.88E+01	7.19E+04	1.44E+04	No
23	Carbon Tetrachloride		YES	0	0	-	-	-	0	0	-	-	-	-	9.57E-01	8.74E+02	1.75E+02	No
24	Chlordane		YES	0	0	2.400	88.877	17.775	No	0	0.004	0.211	0.042	No	4.73E-04	4.32E-01	8.64E-02	No
25	Chlorobenzene			0	0	-	-	-	0	0	-	-	-	-	9.06E+02	4.44E+04	8.89E+03	No
26	Chlorodibromo-Methane		YES	0	0	-	-	-	0	0	-	-	-	-	7.41E+00	6.78E+03	1.35E+03	No
27	Chloroethane			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
28	2-Chloro-Ethylvinyl Ether			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
29	Chloroform		YES	0	0	-	-	-	0	0	-	-	-	-	1.02E+02	9.32E+04	1.86E+04	No
30	4,4' - DDD		YES	0	0	-	-	-	0	0	-	-	-	-	1.81E-04	1.66E-01	3.31E-02	No
31	4,4' - DDE		YES	0	0	-	-	-	0	0	-	-	-	-	1.28E-04	1.17E-01	2.34E-02	No
32	4,4' - DDT		YES	0	0	-	-	-	0	0	-	-	-	-	1.28E-04	1.17E-01	2.34E-02	No
33	Dichlorobromo-Methane		YES	0	0	-	-	-	0	0	-	-	-	-	1.00E+01	9.17E+03	1.83E+03	No
34	1, 1-Dichloroethane			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
35	1, 2-Dichloroethane		YES	0	0	-	-	-	0	0	-	-	-	-	2.14E+01	1.95E+04	3.90E+03	No
36	Trans-1, 2-Dichloro-Ethylene			0	0	-	-	-	0	0	-	-	-	-	5.91E+03	2.90E+05	5.79E+04	No
37	1, 1-Dichloroethylene		YES	0	0	-	-	-	0	0	-	-	-	-	4.17E+03	3.81E+06	7.61E+05	No
38	1, 2-Dichloropropane			0	0	-	-	-	0	0	-	-	-	-	8.49E+00	4.17E+02	8.33E+01	No
39	1, 3-Dichloro-Propylene			0	0	-	-	-	0	0	-	-	-	-	1.23E+01	6.02E+02	1.20E+02	No
40	Dieldrin		YES	0	0	0.240	8.888	1.778	No	0	0.056	2.746	0.549	No	3.12E-05	2.65E-02	5.70E-03	No
41	Ethylbenzene			0	0	-	-	-	0	0	-	-	-	-	1.24E+03	6.10E+04	1.22E+04	No
42	Methyl Bromide			0	0	-	-	-	0	0	-	-	-	-	8.71E+02	4.27E+04	8.54E+03	No
43	Methyl Chloride			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
44	Methylene Chloride		YES	0	0	-	-	-	0	0	-	-	-	-	3.46E+02	3.16E+05	6.31E+04	No
45	1, 1, 2, 2-Tetrachloro-Ethane		YES	0	0	-	-	-	0	0	-	-	-	-	2.33E+00	2.13E+03	4.28E+02	No
46	Tetrachloro-Ethylene		YES	0	0	-	-	-	0	0	-	-	-	-	1.92E+00	1.75E+03	3.50E+02	No
47	Toluene			0	0	-	-	-	0	0	-	-	-	-	8.72E+03	4.26E+05	8.56E+04	No
48	Toxaphene		YES	0	0	0.730	27.033	5.407	No	0	0.0002	0.010	0.002	No	1.62E-04	1.48E-01	2.96E-02	No
49	Tributyltin (TBT)		YES	0	0	0.460	17.035	3.407	No	0	0.072	3.531	0.706	No	-	-	-	-
50	1, 1, 1-Trichloroethane			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
51	1, 2-Trichloroethane		YES	0	0	-	-	-	0	0	-	-	-	-	9.10E+00	6.31E+03	1.66E+03	No
52	Trichloroethylene		YES	0	0	-	-	-	0	0	-	-	-	-	1.75E+01	1.60E+04	3.19E+03	No
53	Vinyl Chloride		YES	0	0	-	-	-	0	0	-	-	-	-	1.42E+00	1.30E+03	2.60E+02	No
54	P-Chloro-M-Cresol			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
55	2-Chlorophenol			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
56	2, 4-Dichlorophenol			0	0	-	-	-	0	0	-	-	-	-	8.71E+01	4.27E+03	8.54E+02	No
57	2, 4-Dimethylphenol			0	0	-	-	-	0	0	-	-	-	-	1.72E+02	8.43E+03	1.69E+03	No
58	4, 6-Dinitro-O-Cresol			0	0	-	-	-	0	0	-	-	-	-	4.98E+02	2.44E+04	4.88E+03	No
59	2, 4-Dinitrophenol			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
60	4, 6-Dinitro-2-methylphenol		YES	0	0	-	-	-	0	0	-	-	-	-	3.11E+03	1.53E+05	3.05E+04	No
61	Dioxin (2,3,7,8-TCDD)		YES	0	0	-	-	-	0	0	-	-	-	-	2.87E-06	2.44E-05	4.87E-06	No
62	2-Nitrophenol			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
63	4-Nitrophenol			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
64	Pentachlorophenol		YES	0	0	6.723	323.043	64.609	No	0	6.693	328.224	65.645	No	1.77E+00	1.81E+03	3.23E+02	No
65	Phenol			0	0	-	-	-	0	0	-	-	-	-	5.00E+05	2.45E+07	4.90E+06	No
66	2, 4, 6-Trichlorophenol		YES	0	0	-	-	-	0	0	-	-	-	-	1.41E+00	1.29E+03	2.58E+02	No
67	Acenaphthene			0	0	-	-	-	0	0	-	-	-	-	5.79E+02	2.84E+04	5.67E+03	No
68	Acenaphthylene			0	0	-	-	-	0	0	-	-	-	-	-	-	-	-
69	Anthracene			0	0	-	-	-	0	0	-	-	-	-	2.33E+04	1.14E+06	2.29E+05	No
70	Benzo(a)Anthracene			0	0	-	-	-	0	0	-	-	-	-	1.16E-04	5.69E-03	1.14E-03	No
71	Benzo(a)Pyrene		YES	0	0													

Permit Number: AL0056146

Monitoring Point: 001Q

Stage: Effluent Gross Value

Parameter Name: Mercury

Parameter Code: 71901

Monitoring Period	Monthly Average	Daily Maximum	Conc. Unit
April 2010 - June 2010	0	0	µg/L
July 2010 - September 2010	0	0	µg/L
October 2010 - December 2010	0	0	µg/L
January 2011 - March 2011	0	0	µg/L
April 2011 - June 2011	0	0	µg/L
January 2012 - March 2012	0.00069	0.00069	µg/L
April 2012 - June 2012	0	0	µg/L
July 2012 - September 2012	0	0	µg/L
October 2012 - December 2012	0	0	µg/L
January 2013 - March 2013	0.01	0.01	µg/L
April 2013 - June 2013	0.008	0.008	µg/L
July 2013 - September 2013	0.007	0.007	µg/L
October 2013 - December 2013	0.007	0.007	µg/L
January 2014 - March 2014	0.007	0.007	µg/L
April 2014 - June 2014	0.014	0.014	µg/L

<i>Average</i>	0.0036		µg/L
<i>Maximum</i>		0.014	µg/L

# Waste Load Allocation Summary

Comments included

☒ Yes ☐ No

## General Information

Information  
Verified By

BCH

Page 1

Receiving Stream Name Tallapoosa River

Year File Was Created 1984

Previous File Name

OR: Local Name (If applicable)

Facility Name Heflin Lagoon

Previous Discharger Name

Or-AKA (includes previous file name)

11 Digit HUC Code 03150108100

12 Digit HUC Code 031501080403

River Basin Tallapoosa

County Cleburne

Use Classification F&W

Date of WLA Response 7/13/2009

Discharge Latitude 33.60011

Lat/Long Method GPS

Discharge Longitude -85.59858

Site Visit Completed? ☒ Yes ☐ No

Approved TMDL?

☒ Yes ☐ No

Date of Site Visit 9/3/2004

Waterbody Impaired? ☒ Yes ☐ No

Approval Date of TMDL 10/31/2002

Antidegradation ☐ Yes ☒ No

Waterbody Tier Level Tier I

Use Support Category 4A

Other Point Sources? ☒ Yes ☐ No

## Permit Information

Permit Number AL0056146

Permit Status Active

Sources Included in Model

Tyson

Type of Discharger

- ☒ Municipal  
☐ Industrial  
☐ Semipublic/Private  
☐ Mining

## Waste Load Allocation Information

Modeled Reach Length 18.22

Miles

Date of Allocation 7/13/2009

Name of Model Used SWQM

Allocation Type 2 Seasons

Model Completed by Brian Haigler

Type of Model Used Calibrated / Verified

Allocation Developed by Water Quality Branch

# Waste Load Allocation Summary

Annual Effluent Limits	Conventional Parameters				Other Parameters						
	Qw	0.6	MGD	Qw	0.6	MGD	Qw	MGD	Qw	MGD	
Season	Summer		Season	Winter		Season			Season		
From	May		From	Dec		From			From		
Through	Nov		Through	Apr		Through			Through		
CBOD5			CBOD5	20	mg/L	CBOD5	25	mg/L	TP		
NH3-N			NH3-N	15	mg/L	NH3-N	20	mg/L	TN		
TKN			TKN	30	mg/L	TKN	40	mg/L	TSS		
D.O.			D.O.	0	mg/L	D.O.	0	mg/L			

"Monitor Only" Parameters for Effluent:		Parameter	Frequency	Parameter	Frequency
		TP	Monthly (Apr-Oct)		
		NO2+NO3-N	Monthly (Apr-Oct)		
		TKN	Monthly (Apr-Oct)		

## Water Quality Characteristics Immediately Upstream of Discharge

Parameter	Summer		Winter	
CBODu	2	mg/l	2	mg/l
NH3-N	0.0466	mg/l	0.0466	mg/l
Temperature	18	°C	28	°C
pH	7	su	7	su

## Hydrology at Discharge Location

Drainage Area Qualifier	Drainage Area	526	sq mi	Method Used to Calculate
	Stream 7Q10	44.6	cfs	ADEM Estimate w/USGS Gage Data
	Stream 1Q10	33.45	cfs	ADEM Estimate w/USGS Gage Data
	Stream 7Q2	112.7	cfs	ADEM Estimate w/USGS Gage Data
	Annual Average		cfs	

**Comments and/or Notations** Limits are based on Dam Open.  
Limits for Heflin WWTP under open dam stream flow conditions would equate to stream flow conditions should the dam ever be removed.  
See file for limits.



# Waste Load Allocation Summary

Comments included

☒ Yes ☐ No

## General Information

Information Verified By **BCH**

Page 1

Receiving Stream Name **Tallapoosa River**

Year File Was Created **1984**

Previous File Name

OR: Local Name (If applicable)

Facility Name **Heflin Lagoon**

Previous Discharger Name

Or-AKA (includes previous file name)

11 Digit HUC Code **03150108100**

12 Digit HUC Code **031501080403**

River Basin **Tallapoosa**

County **Cleburne**

Use Classification **F&W**

Date of WLA Response **7/13/2009**

Discharge Latitude **33.60011**

Lat/Long Method **GPS**

Discharge Longitude **-85.59858**

Site Visit Completed? ☒ Yes ☐ No

Approved TMDL?

☒ Yes ☐ No

Date of Site Visit **9/3/2004**

Approval Date of TMDL **10/31/2002**

Waterbody Impaired? ☒ Yes ☐ No

Antidegradation ☐ Yes ☒ No

Waterbody Tier Level **Tier I**

Use Support Category **4A**

Other Point Sources? ☒ Yes ☐ No

## Permit Information

Permit Number **AL0056146**

Permit Status **Active**

Type of Discharger

- ☒ Municipal  
☐ Industrial  
☐ Semipublic/Private  
☐ Mining

Sources Included in Model

Tyson

## Waste Load Allocation Information

Modeled Reach Length **18.22**

Miles

Date of Allocation **7/13/2009**

Name of Model Used **SWQM**

Allocation Type **2 Seasons**

Model Completed by **Brian Haigler**

Type of Model Used **Calibrated / Verified**

Allocation Developed by **Water Quality Branch**

# Waste Load Allocation Summary

Annual Effluent Limits	Conventional Parameters				Other Parameters			
	Qw	0.6	MGD		Qw	0.6	MGD	
Season	Summer				Season	Winter		
From	May				From	Dec		
Through	Nov				Through	Apr		
CBOD5	20	mg/L			TP	25	mg/L	
NH3-N	15	mg/L			TN	20	mg/L	
TKN	30	mg/L			TSS	40	mg/L	
D.O.	0	mg/L				0	mg/L	

"Monitor Only" Parameters for Effluent:	Parameter	Frequency	Parameter	Frequency
	TP	Monthly (Apr-Oct)		
	NO2+NO3-N	Monthly (Apr-Oct)		
	TKN	Monthly (Apr-Oct)		

## Water Quality Characteristics Immediately Upstream of Discharge

Parameter	Summer	Winter
CBODu	2 mg/l	2 mg/l
NH3-N	0.0466 mg/l	0.0466 mg/l
Temperature	18 °C	28 °C
pH	7 su	7 su

## Hydrology at Discharge Location

Drainage Area Qualifier	Drainage Area	526	sq mi	Method Used to Calculate
	Stream 7Q10	44.6	cfs	ADEM Estimate w/USGS Gage Data
	Stream 1Q10	33.45	cfs	ADEM Estimate w/USGS Gage Data
	Stream 7Q2	112.7	cfs	ADEM Estimate w/USGS Gage Data
	Annual Average		cfs	

**Comments and/or Notations** Limits are based on Dam Open.  
Limits for Heflin WWTP under open dam stream flow conditions would equate to stream flow conditions should the dam ever be removed.  
See file for limits.



FORM <b>1</b> GENERAL	<b>EPA</b> U.S. ENVIRONMENTAL PROTECTION AGENCY <b>GENERAL INFORMATION</b> Consolidated Permits Program <i>(Read the "General Instructions" before starting.)</i>	I. EPA I.D. NUMBER <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:5%; text-align: center;">S</td> <td style="width:85%;"></td> <td style="width:5%; text-align: center;">T/A</td> <td style="width:5%; text-align: center;">C</td> </tr> <tr> <td style="text-align: center;">F</td> <td>AL0056146</td> <td></td> <td style="text-align: center;">D</td> </tr> <tr> <td style="text-align: center;">1</td> <td style="text-align: center;">2</td> <td style="text-align: center;">13</td> <td style="text-align: center;">14 15</td> </tr> </table>	S		T/A	C	F	AL0056146		D	1	2	13	14 15												
S		T/A	C																							
F	AL0056146		D																							
1	2	13	14 15																							
LABEL ITEMS	PLEASE PLACE LABEL IN THIS SPACE	<b>GENERAL INSTRUCTIONS</b> If a preprinted label has been provided, affix it in the designated space. Review the information carefully; if any of it is incorrect, cross through it and enter the correct data in the appropriate fill-in area below. Also, if any of the preprinted data is absent (the area to the left of the label space lists the information that should appear), please provide it in the proper fill-in area(s) below. If the label is complete and correct, you need not complete Items I, III, V, and VI (except VI-B which must be completed regardless). Complete all items if no label has been provided. Refer to the instructions for detailed item descriptions and for the legal authorizations under which this data is collected.																								
I. EPA I.D. NUMBER																										
III. FACILITY NAME																										
V. FACILITY MAILING ADDRESS																										
VI. FACILITY LOCATION																										
II. POLLUTANT CHARACTERISTICS INSTRUCTIONS: Complete A through J to determine whether you need to submit any permit application forms to the EPA. If you answer "yes" to any questions, you must submit this form and the supplemental form listed in the parenthesis following the question. Mark "X" in the box in the third column if the supplemental form is attached. If you answer "no" to each question, you need not submit any of these forms. You may answer "no" if your activity is excluded from permit requirements; see Section C of the instructions. See also, Section D of the instructions for definitions of <b>bold-faced terms</b> .																										
SPECIFIC QUESTIONS	Mark "X" <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%; text-align: center;">YES</td> <td style="width:33%; text-align: center;">NO</td> <td style="width:33%; text-align: center;">FORM ATTACHED</td> </tr> </table>	YES	NO	FORM ATTACHED	Mark "X" <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%; text-align: center;">YES</td> <td style="width:33%; text-align: center;">NO</td> <td style="width:33%; text-align: center;">FORM ATTACHED</td> </tr> </table>	YES	NO	FORM ATTACHED																		
YES	NO	FORM ATTACHED																								
YES	NO	FORM ATTACHED																								
A. Is this facility a <b>publicly owned treatment works</b> which results in a <b>discharge to waters of the U.S.?</b> (FORM 2A)	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%; text-align: center;">X</td> <td style="width:33%;"></td> <td style="width:33%;"></td> </tr> <tr> <td style="text-align: center;">16</td> <td style="text-align: center;">17</td> <td style="text-align: center;">18</td> </tr> </table>	X			16	17	18	B. Does or will this facility (either existing or proposed) include a <b>concentrated animal feeding operation</b> or <b>aquatic animal production facility</b> which results in a <b>discharge to waters of the U.S.?</b> (FORM 2B) <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%;"></td> <td style="width:33%; text-align: center;">X</td> <td style="width:33%;"></td> </tr> <tr> <td style="text-align: center;">19</td> <td style="text-align: center;">20</td> <td style="text-align: center;">21</td> </tr> </table>		X		19	20	21												
X																										
16	17	18																								
	X																									
19	20	21																								
C. Is this a facility which currently results in <b>discharges to waters of the U.S.</b> other than those described in A or B above? (FORM 2C)	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%;"></td> <td style="width:33%; text-align: center;">X</td> <td style="width:33%;"></td> </tr> <tr> <td style="text-align: center;">22</td> <td style="text-align: center;">23</td> <td style="text-align: center;">24</td> </tr> </table>		X		22	23	24	D. Is this a proposed facility (other than those described in A or B above) which will result in a <b>discharge to waters of the U.S.?</b> (FORM 2D) <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%;"></td> <td style="width:33%; text-align: center;">X</td> <td style="width:33%;"></td> </tr> <tr> <td style="text-align: center;">25</td> <td style="text-align: center;">26</td> <td style="text-align: center;">27</td> </tr> </table>		X		25	26	27												
	X																									
22	23	24																								
	X																									
25	26	27																								
E. Does or will this facility treat, store, or dispose of <b>hazardous wastes?</b> (FORM 3)	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%;"></td> <td style="width:33%; text-align: center;">X</td> <td style="width:33%;"></td> </tr> <tr> <td style="text-align: center;">28</td> <td style="text-align: center;">29</td> <td style="text-align: center;">30</td> </tr> </table>		X		28	29	30	F. Do you or will you inject at this facility industrial or municipal effluent below the lowest stratum containing, within one quarter mile of the well bore, underground sources of drinking water? (FORM 4) <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%;"></td> <td style="width:33%; text-align: center;">X</td> <td style="width:33%;"></td> </tr> <tr> <td style="text-align: center;">31</td> <td style="text-align: center;">32</td> <td style="text-align: center;">33</td> </tr> </table>		X		31	32	33												
	X																									
28	29	30																								
	X																									
31	32	33																								
G. Do you or will you inject at this facility any produced water or other fluids which are brought to the surface in connection with conventional oil or natural gas production, inject fluids used for enhanced recovery of oil or natural gas, or inject fluids for storage of liquid hydrocarbons? (FORM 4)	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%;"></td> <td style="width:33%; text-align: center;">X</td> <td style="width:33%;"></td> </tr> <tr> <td style="text-align: center;">34</td> <td style="text-align: center;">35</td> <td style="text-align: center;">36</td> </tr> </table>		X		34	35	36	H. Do you or will you inject at this facility fluids for special processes such as mining of sulfur by the Frasch process, solution mining of minerals, in situ combustion of fossil fuel, or recovery of geothermal energy? (FORM 4) <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%;"></td> <td style="width:33%; text-align: center;">X</td> <td style="width:33%;"></td> </tr> <tr> <td style="text-align: center;">37</td> <td style="text-align: center;">38</td> <td style="text-align: center;">39</td> </tr> </table>		X		37	38	39												
	X																									
34	35	36																								
	X																									
37	38	39																								
I. Is this facility a proposed <b>stationary source</b> which is one of the 28 industrial categories listed in the instructions and which will potentially emit 100 tons per year of any air pollutant regulated under the Clean Air Act and may affect or be located in an attainment area? (FORM 5)	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%;"></td> <td style="width:33%; text-align: center;">X</td> <td style="width:33%;"></td> </tr> <tr> <td style="text-align: center;">40</td> <td style="text-align: center;">41</td> <td style="text-align: center;">42</td> </tr> </table>		X		40	41	42	J. Is this facility a proposed <b>stationary source</b> which is NOT one of the 28 industrial categories listed in the instructions and which will potentially emit 250 tons per year of any air pollutant regulated under the Clean Air Act and may affect or be located in an attainment area? (FORM 5) <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%;"></td> <td style="width:33%; text-align: center;">X</td> <td style="width:33%;"></td> </tr> <tr> <td style="text-align: center;">43</td> <td style="text-align: center;">44</td> <td style="text-align: center;">45</td> </tr> </table>		X		43	44	45												
	X																									
40	41	42																								
	X																									
43	44	45																								
III. NAME OF FACILITY <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:5%; text-align: center;">C</td> <td style="width:5%; text-align: center;">SKIP</td> <td style="width:90%;"></td> </tr> <tr> <td style="text-align: center;">1</td> <td></td> <td>HEFLIN LAGOON</td> </tr> <tr> <td style="text-align: center;">15</td> <td style="text-align: center;">16 - 29</td> <td style="text-align: center;">30</td> </tr> </table>			C	SKIP		1		HEFLIN LAGOON	15	16 - 29	30															
C	SKIP																									
1		HEFLIN LAGOON																								
15	16 - 29	30																								
IV. FACILITY CONTACT <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:60%; text-align: center;">A. NAME &amp; TITLE (last, first, &amp; title)</td> <td style="width:40%; text-align: center;">B. PHONE (area code &amp; no.)</td> </tr> <tr> <td style="text-align: center;">C</td> <td style="text-align: center;">D</td> </tr> <tr> <td style="text-align: center;">2</td> <td>           DONALD DEWBERRY, SUPERINTENDENT            (256) 463-2011         </td> </tr> <tr> <td style="text-align: center;">15</td> <td style="text-align: center;">16 45 46 48 49 51 52 55</td> </tr> </table>			A. NAME & TITLE (last, first, & title)	B. PHONE (area code & no.)	C	D	2	DONALD DEWBERRY, SUPERINTENDENT (256) 463-2011	15	16 45 46 48 49 51 52 55																
A. NAME & TITLE (last, first, & title)	B. PHONE (area code & no.)																									
C	D																									
2	DONALD DEWBERRY, SUPERINTENDENT (256) 463-2011																									
15	16 45 46 48 49 51 52 55																									
V. FACILITY MAILING ADDRESS <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:60%; text-align: center;">A. STREET OR P.O. BOX</td> <td style="width:40%;"></td> </tr> <tr> <td style="text-align: center;">C</td> <td style="text-align: center;">D</td> </tr> <tr> <td style="text-align: center;">3</td> <td>P.O. Box 488</td> </tr> <tr> <td style="text-align: center;">15</td> <td style="text-align: center;">16 45</td> </tr> <tr> <td style="width:50%; text-align: center;">B. CITY OR TOWN</td> <td style="width:50%; text-align: center;">C. STATE D. ZIP CODE</td> </tr> <tr> <td style="text-align: center;">C</td> <td style="text-align: center;">D</td> </tr> <tr> <td style="text-align: center;">4</td> <td>HEFLIN AL 36264</td> </tr> <tr> <td style="text-align: center;">15</td> <td style="text-align: center;">16 40 41 42 47 51</td> </tr> </table>			A. STREET OR P.O. BOX		C	D	3	P.O. Box 488	15	16 45	B. CITY OR TOWN	C. STATE D. ZIP CODE	C	D	4	HEFLIN AL 36264	15	16 40 41 42 47 51								
A. STREET OR P.O. BOX																										
C	D																									
3	P.O. Box 488																									
15	16 45																									
B. CITY OR TOWN	C. STATE D. ZIP CODE																									
C	D																									
4	HEFLIN AL 36264																									
15	16 40 41 42 47 51																									
VI. FACILITY LOCATION <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:60%; text-align: center;">A. STREET, ROUTE NO. OR OTHER SPECIFIC IDENTIFIER</td> <td style="width:40%;"></td> </tr> <tr> <td style="text-align: center;">C</td> <td style="text-align: center;">D</td> </tr> <tr> <td style="text-align: center;">5</td> <td>U. S. HIGHWAY 78 WEST</td> </tr> <tr> <td style="text-align: center;">15</td> <td style="text-align: center;">16 65</td> </tr> <tr> <td style="width:60%; text-align: center;">B. COUNTY NAME</td> <td style="width:40%;"></td> </tr> <tr> <td style="text-align: center;">C</td> <td style="text-align: center;">D</td> </tr> <tr> <td style="text-align: center;">6</td> <td>CLEBURNE</td> </tr> <tr> <td style="text-align: center;">15</td> <td style="text-align: center;">16 46 70</td> </tr> <tr> <td style="width:50%; text-align: center;">C. CITY OR TOWN</td> <td style="width:50%; text-align: center;">D. STATE E. ZIP CODE F. COUNTY CODE (if known)</td> </tr> <tr> <td style="text-align: center;">C</td> <td style="text-align: center;">D</td> </tr> <tr> <td style="text-align: center;">6</td> <td>HEFLIN AL 36264</td> </tr> <tr> <td style="text-align: center;">15</td> <td style="text-align: center;">16 40 41 42 47 51 52 54</td> </tr> </table>			A. STREET, ROUTE NO. OR OTHER SPECIFIC IDENTIFIER		C	D	5	U. S. HIGHWAY 78 WEST	15	16 65	B. COUNTY NAME		C	D	6	CLEBURNE	15	16 46 70	C. CITY OR TOWN	D. STATE E. ZIP CODE F. COUNTY CODE (if known)	C	D	6	HEFLIN AL 36264	15	16 40 41 42 47 51 52 54
A. STREET, ROUTE NO. OR OTHER SPECIFIC IDENTIFIER																										
C	D																									
5	U. S. HIGHWAY 78 WEST																									
15	16 65																									
B. COUNTY NAME																										
C	D																									
6	CLEBURNE																									
15	16 46 70																									
C. CITY OR TOWN	D. STATE E. ZIP CODE F. COUNTY CODE (if known)																									
C	D																									
6	HEFLIN AL 36264																									
15	16 40 41 42 47 51 52 54																									



CONTINUED FROM THE FRONT

## VII. SIC CODES (4-digit, in order of priority)

A. FIRST										B. SECOND														
C	7	4	9	5	2	(specify)					C	7	(specify)											
15	16	17	18	19	SEWERAGE SYSTEM										15	16	17	18	19					
C. THIRD										D. FOURTH														
C	7	(specify)									C	7	(specify)											
15	16	17	18	19											15	16	17	18	19					

## VIII. OPERATOR INFORMATION

A. NAME															B. Is the name listed in Item VIII-A also the owner?													
C	8	HEFLIN WATER WORKS AND SEWER BOARD													<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO													
15	16														55	56												
C. STATUS OF OPERATOR (Enter the appropriate letter into the answer box: if "Other," specify.)															D. PHONE (area code & no.)													
F = FEDERAL S = STATE P = PRIVATE										M = PUBLIC (other than federal or state) O = OTHER (specify)					M (specify)					(256) 463-2011								
										56					15					16	17	18	19	20	21	22	23	24

E. STREET OR P.O. BOX															
P.O. Box 488															
25															55

F. CITY OR TOWN										G. STATE		H. ZIP CODE		IX. INDIAN LAND	
C	B	HEFLIN								AL		36264		Is the facility located on Indian lands? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO	
15	16									40	41	42	43	44	45

## X. EXISTING ENVIRONMENTAL PERMITS

A. NPDES (Discharges to Surface Water)										D. PSD (Air Emissions from Proposed Sources)									
C	T	I	AL0056146							C	T	I	N/A						
9	N									9	P								
15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30				
B. UIC (Underground Injection of Fluids)										E. OTHER (specify)									
C	T	I	N/A							C	T	I	N/A						
9	U									9									
15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30				
C. RCRA (Hazardous Wastes)										E. OTHER (specify)									
C	T	I	N/A							C	T	I	N/A						
9	R									9									
15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30				

## XI. MAP


Attach to this application a topographic map of the area extending to at least one mile beyond property boundaries. The map must show the outline of the facility, the location of each of its existing and proposed intake and discharge structures, each of its hazardous waste treatment, storage, or disposal facilities, and each well where it injects fluids underground. Include all springs, rivers, and other surface water bodies in the map area. See instructions for precise requirements.

## XII. NATURE OF BUSINESS (provide a brief description)

PROVIDE WATER AND SEWER TO HEFLIN, ALABAMA

## XIII. CERTIFICATION (see instructions)

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this application and all attachments and that, based on my inquiry of those persons immediately responsible for obtaining the information contained in the application, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

A. NAME & OFFICIAL TITLE (type or print)										B. SIGNATURE										C. DATE SIGNED									
DAVID J. NORTON, CHAIRMAN																				03/10/2014									

## COMMENTS FOR OFFICIAL USE ONLY

C															
15	16														55



FORM  
**2A**  
NPDES**NPDES FORM 2A APPLICATION OVERVIEW****APPLICATION OVERVIEW**


Form 2A has been developed in a modular format and consists of a "Basic Application Information" packet and a "Supplemental Application Information" packet. The Basic Application Information packet is divided into two parts. All applicants must complete Parts A and C. Applicants with a design flow greater than or equal to 0.1 mgd must also complete Part B. Some applicants must also complete the Supplemental Application Information packet. The following items explain which parts of Form 2A you must complete.

**BASIC APPLICATION INFORMATION:**

- A. **Basic Application Information for all Applicants.** All applicants must complete questions A.1 through A.8. A treatment works that discharges effluent to surface waters of the United States must also answer questions A.9 through A.12.
- B. **Additional Application Information for Applicants with a Design Flow  $\geq 0.1$  mgd.** All treatment works that have design flows greater than or equal to 0.1 million gallons per day must complete questions B.1 through B.6.
- C. **Certification.** All applicants must complete Part C (Certification).

**SUPPLEMENTAL APPLICATION INFORMATION:**

- D. **Expanded Effluent Testing Data.** A treatment works that discharges effluent to surface waters of the United States and meets one or more of the following criteria must complete Part D (Expanded Effluent Testing Data):
  - 1. Has a design flow rate greater than or equal to 1 mgd,
  - 2. Is required to have a pretreatment program (or has one in place), or
  - 3. Is otherwise required by the permitting authority to provide the information.
- E. **Toxicity Testing Data.** A treatment works that meets one or more of the following criteria must complete Part E (Toxicity Testing Data):
  - 1. Has a design flow rate greater than or equal to 1 mgd,
  - 2. Is required to have a pretreatment program (or has one in place), or
  - 3. Is otherwise required by the permitting authority to submit results of toxicity testing.
- F. **Industrial User Discharges and RCRA/CERCLA Wastes.** A treatment works that accepts process wastewater from any significant industrial users (SIUs) or receives RCRA or CERCLA wastes must complete Part F (Industrial User Discharges and RCRA/CERCLA Wastes). SIUs are defined as:
  - 1. All industrial users subject to Categorical Pretreatment Standards under 40 Code of Federal Regulations (CFR) 403.6 and 40 CFR Chapter I, Subchapter N (see instructions); and
  - 2. Any other industrial user that:
    - a. Discharges an average of 25,000 gallons per day or more of process wastewater to the treatment works (with certain exclusions); or
    - b. Contributes a process wastestream that makes up 5 percent or more of the average dry weather hydraulic or organic capacity of the treatment plant; or
    - c. Is designated as an SIU by the control authority.
- G. **Combined Sewer Systems.** A treatment works that has a combined sewer system must complete Part G (Combined Sewer Systems).

**ALL APPLICANTS MUST COMPLETE PART C (CERTIFICATION)**



**BASIC APPLICATION INFORMATION****PART A. BASIC APPLICATION INFORMATION FOR ALL APPLICANTS:**

All treatment works must complete questions A.1 through A.8 of this Basic Application Information packet.

**A.1. Facility Information.**

Facility name Heflin Lagoon

Mailing Address P.O. Box 488 Heflin, AL 36264

Contact person Donald Dewberry

Title Superintendent

Telephone number (256) 463-2011

Facility Address U. S. Highway 78 West Heflin, AL 36264

(not P.O. Box) \_\_\_\_\_

**A.2. Applicant Information.** If the applicant is different from the above, provide the following:

Applicant name Heflin Water Works & Sewer Board

Mailing Address P.O. Box 488  
Heflin, AL 36264

Contact person David J. Norton

Title Chairman

Telephone number (256) 463-2011

Is the applicant the owner or operator (or both) of the treatment works?

☒ owner ☒ operator

Indicate whether correspondence regarding this permit should be directed to the facility or the applicant.

☐ facility ☒ applicant**A.3. Existing Environmental Permits.** Provide the permit number of any existing environmental permits that have been issued to the treatment works (include state-issued permits).

NPDES AL0056146 PSD N/A

UIC N/A Other N/A

RCRA N/A Other N/A

**A.4. Collection System Information.** Provide information on municipalities and areas served by the facility. Provide the name and population of each entity and, if known, provide information on the type of collection system (combined vs. separate) and its ownership (municipal, private, etc.).

Name	Population Served	Type of Collection System	Ownership
<u>Heflin</u>	<u></u>	<u></u>	<u>Municipal</u>
<u></u>	<u></u>	<u></u>	<u></u>
<u></u>	<u></u>	<u></u>	<u></u>
Total population served <u>725</u>			



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

## A.5. Indian Country.

- a. Is the treatment works located in Indian Country?

☐ Yes ☒ No

- b. Does the treatment works discharge to a receiving water that is either in Indian Country or that is upstream from (and eventually flows through) Indian Country?

☐ Yes ☒ No

## A.6. Flow. Indicate the design flow rate of the treatment plant (i.e., the wastewater flow rate that the plant was built to handle). Also provide the average daily flow rate and maximum daily flow rate for each of the last three years. Each year's data must be based on a 12-month time period with the 12th month of "this year" occurring no more than three months prior to this application submittal.

- a. Design flow rate
- 0.60
- mgd

	<u>Two Years Ago</u>	<u>Last Year</u>	<u>This Year</u>
b. Annual average daily flow rate	<u>0.280</u>	<u>0.251</u>	<u>0.251</u> mgd
c. Maximum daily flow rate	<u>0.767</u>	<u>0.827</u>	<u>1.445</u> mgd

## A.7. Collection System. Indicate the type(s) of collection system(s) used by the treatment plant. Check all that apply. Also estimate the percent contribution (by miles) of each.

<input checked="" type="checkbox"/> Separate sanitary sewer	<u>100</u> %
<input type="checkbox"/> Combined storm and sanitary sewer	<u>        </u> %

## A.8. Discharges and Other Disposal Methods.

- a. Does the treatment works discharge effluent to waters of the U.S.?

☒ Yes ☐ No

If yes, list how many of each of the following types of discharge points the treatment works uses:

i. Discharges of treated effluent	<u>1</u>
ii. Discharges of untreated or partially treated effluent	<u>N/A</u>
iii. Combined sewer overflow points	<u>N/A</u>
iv. Constructed emergency overflows (prior to the headworks)	<u>N/A</u>
v. Other <u>                                </u>	<u>N/A</u>

- b. Does the treatment works discharge effluent to basins, ponds, or other surface impoundments that do not have outlets for discharge to waters of the U.S.?

☐ Yes ☒ No

If yes, provide the following for each surface impoundment:

Location: N/AAnnual average daily volume discharged to surface impoundment(s) N/A mgdIs discharge          continuous or          intermittent?

- c. Does the treatment works land-apply treated wastewater?

☐ Yes ☒ No

If yes, provide the following for each land application site:

Location: N/ANumber of acres: N/AAnnual average daily volume applied to site: N/A MgdIs land application          continuous or          intermittent?

- d. Does the treatment works discharge or transport treated or untreated wastewater to another treatment works?

☐ Yes ☒ No



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

If yes, describe the mean(s) by which the wastewater from the treatment works is discharged or transported to the other treatment works (e.g., tank truck, pipe).

N/A

If transport is by a party other than the applicant, provide:

Transporter name: N/AMailing Address: N/AContact person: N/ATitle: N/A

Telephone number: \_\_\_\_\_

For each treatment works that receives this discharge, provide the following:

Name: N/AMailing Address: N/AContact person: N/ATitle: N/A

Telephone number: \_\_\_\_\_

If known, provide the NPDES permit number of the treatment works that receives this discharge.

N/A

Provide the average daily flow rate from the treatment works into the receiving facility.

N/A mgd

- e. Does the treatment works discharge or dispose of its wastewater in a manner not included in A.8.a through A.8.d above (e.g., underground percolation, well injection)?

☐ Yes

No

If yes, provide the following for each disposal method:

Description of method (including location and size of site(s) if applicable):

N/A

Annual daily volume disposed of by this method:

N/A

Is disposal through this method

☐ continuous or☐ intermittent?



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

## WASTEWATER DISCHARGES:

If you answered "yes" to question A.8.a, complete questions A.9 through A.12 once for each outfall (including bypass points) through which effluent is discharged. Do not include information on combined sewer overflows in this section. If you answered "no" to question A.8.a, go to Part B, "Additional Application Information for Applicants with a Design Flow Greater than or Equal to 0.1 mgd."

## A.9. Description of Outfall.

- a. Outfall number 001
- b. Location Heflin 36264  
(City or town, if applicable) (Zip Code)  
Cleburne Alabama  
(County) (State)  
(Latitude) (Longitude)
- c. Distance from shore (if applicable) N/A ft.
- d. Depth below surface (if applicable) N/A ft.
- e. Average daily flow rate 0.3 mgd
- f. Does this outfall have either an intermittent or a periodic discharge?  
           Yes   ✓   No (go to A.9.g.)
- If yes, provide the following information:
- Number of times per year discharge occurs: N/A
- Average duration of each discharge: N/A
- Average flow per discharge: N/A mgd
- Months in which discharge occurs: N/A
- g. Is outfall equipped with a diffuser?   ✓   Yes            No

## A.10. Description of Receiving Waters.

- a. Name of receiving water Tallapoosa River
- b. Name of watershed (if known) N/A
- United States Soil Conservation Service 14-digit watershed code (if known): N/A
- c. Name of State Management/River Basin (if known): N/A
- United States Geological Survey 8-digit hydrologic cataloging unit code (if known): N/A
- d. Critical low flow of receiving stream (if applicable):  
acute N/A cfs chronic N/A cfs
- e. Total hardness of receiving stream at critical low flow (if applicable): N/A mg/l of CaCO<sub>3</sub>



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

## A.11. Description of Treatment.

- a. What levels of treatment are provided? Check all that apply.

☒ Primary ☒ Secondary  
☐ Advanced ☐ Other. Describe: \_\_\_\_\_

- b. Indicate the following removal rates (as applicable):

Design BOD<sub>5</sub> removal or Design CBOD<sub>5</sub> removal 90 %  
 Design SS removal 90 %  
 Design P removal N/A %  
 Design N removal N/A %  
 Other                      N/A %

- c. What type of disinfection is used for the effluent from this outfall? If disinfection varies by season, please describe.

Chlorination

If disinfection is by chlorination, is dechlorination used for this outfall?

           Yes ☒ No

- d. Does the treatment plant have post aeration?

           Yes ☒ No

**A.12. Effluent Testing Information.** All Applicants that discharge to waters of the US must provide effluent testing data for the following parameters. Provide the indicated effluent testing required by the permitting authority for each outfall through which effluent is discharged. Do not include information on combined sewer overflows in this section. All information reported must be based on data collected through analysis conducted using 40 CFR Part 136 methods. In addition, this data must comply with QA/QC requirements of 40 CFR Part 136 and other appropriate QA/QC requirements for standard methods for analytes not addressed by 40 CFR Part 136. At a minimum, effluent testing data must be based on at least three samples and must be no more than four and one-half years apart.

Outfall number: 001

PARAMETER	MAXIMUM DAILY VALUE		AVERAGE DAILY VALUE		
	Value	Units	Value	Units	Number of Samples
pH (Minimum)	6.9	s.u.			
pH (Maximum)		s.u.			
Flow Rate	0.251	MGD			
Temperature (Winter)	9°				
Temperature (Summer)	77°	F			

\* For pH please report a minimum and a maximum daily value

POLLUTANT	MAXIMUM DAILY DISCHARGE		AVERAGE DAILY DISCHARGE			ANALYTICAL METHOD	ML / MDL
	Conc.	Units	Conc.	Units	Number of Samples		

## CONVENTIONAL AND NONCONVENTIONAL COMPOUNDS.

BIOCHEMICAL OXYGEN DEMAND (Report one)	BOD-5	31.0					
	CBOD-5		mg/L	19.0	mg/L	m5210	
FECAL COLIFORM	16	cfu/100mL				A908C	
TOTAL SUSPENDED SOLIDS (TSS)	14.0	mg/L	14.1	mg/L			

## END OF PART A.

REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM 2A YOU MUST COMPLETE



FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

## BASIC APPLICATION INFORMATION

### PART B. ADDITIONAL APPLICATION INFORMATION FOR APPLICANTS WITH A DESIGN FLOW GREATER THAN OR EQUAL TO 0.1 MGD (100,000 gallons per day).

All applicants with a design flow rate  $\geq 0.1$  mgd must answer questions B.1 through B.6. All others go to Part C (Certification).

**B.1. Inflow and Infiltration.** Estimate the average number of gallons per day that flow into the treatment works from inflow and/or infiltration.

40,000 gpd

Briefly explain any steps underway or planned to minimize inflow and infiltration.

The board has undertaken an I/I sewer rehab problem: Some sewers have been rehabed; work is still underway.

**B.2. Topographic Map.** Attach to this application a topographic map of the area extending at least one mile beyond facility property boundaries. This map must show the outline of the facility and the following information. (You may submit more than one map if one map does not show the entire area.)

- The area surrounding the treatment plant, including all unit processes.
- The major pipes or other structures through which wastewater enters the treatment works and the pipes or other structures through which treated wastewater is discharged from the treatment plant. Include outfalls from bypass piping, if applicable.
- Each well where wastewater from the treatment plant is injected underground.
- Wells, springs, other surface water bodies, and drinking water wells that are: 1) within 1/4 mile of the property boundaries of the treatment works, and 2) listed in public record or otherwise known to the applicant.
- Any areas where the sewage sludge produced by the treatment works is stored, treated, or disposed.
- If the treatment works receives waste that is classified as hazardous under the Resource Conservation and Recovery Act (RCRA) by truck, rail, or special pipe, show on the map where that hazardous waste enters the treatment works and where it is treated, stored, and/or disposed.

**B.3. Process Flow Diagram or Schematic.** Provide a diagram showing the processes of the treatment plant, including all bypass piping and all backup power sources or redundancy in the system. Also provide a water balance showing all treatment units, including disinfection (e.g., chlorination and dechlorination). The water balance must show daily average flow rates at influent and discharge points and approximate daily flow rates between treatment units. Include a brief narrative description of the diagram.

**B.4. Operation/Maintenance Performed by Contractor(s).**

Are any operational or maintenance aspects (related to wastewater treatment and effluent quality) of the treatment works the responsibility of a contractor? Yes ☒ No

If yes, list the name, address, telephone number, and status of each contractor and describe the contractor's responsibilities (attach additional pages if necessary).

Name: \_\_\_\_\_

Mailing Address: \_\_\_\_\_

Telephone Number: \_\_\_\_\_

Responsibilities of Contractor: \_\_\_\_\_

**B.5. Scheduled Improvements and Schedules of Implementation.** Provide information on any uncompleted implementation schedule or uncompleted plans for improvements that will affect the wastewater treatment, effluent quality, or design capacity of the treatment works. If the treatment works has several different implementation schedules or is planning several improvements, submit separate responses to question B.5 for each. (If none, go to question B.6.)

- a. List the outfall number (assigned in question A.9) for each outfall that is covered by this implementation schedule.

N/A

- b. Indicate whether the planned improvements or implementation schedule are required by local, State, or Federal agencies.

Yes ☒ No



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

- c If the answer to B.5.b is "Yes," briefly describe, including new maximum daily inflow rate (if applicable).

N/A

- d. Provide dates imposed by any compliance schedule or any actual dates of completion for the implementation steps listed below, as applicable. For improvements planned independently of local, State, or Federal agencies, indicate planned or actual completion dates, as applicable. Indicate dates as accurately as possible.

Implementation Stage	Schedule	Actual Completion
	MM / DD / YYYY	MM / DD / YYYY
- Begin construction	___/___/___	___/___/___
- End construction	___/___/___	___/___/___
- Begin discharge	___/___/___	___/___/___
- Attain operational level	___/___/___	___/___/___

- e. Have appropriate permits/clearances concerning other Federal/State requirements been obtained?
- ☐
- Yes
- ☐
- No

Describe briefly: N/A**B.6. EFFLUENT TESTING DATA (GREATER THAN 0.1 MGD ONLY).**

Applicants that discharge to waters of the US must provide effluent testing data for the following parameters. Provide the indicated effluent testing required by the permitting authority for each outfall through which effluent is discharged. Do not include information on combined sewer overflows in this section. All information reported must be based on data collected through analysis conducted using 40 CFR Part 136 methods. In addition, this data must comply with QA/QC requirements of 40 CFR Part 136 and other appropriate QA/QC requirements for standard methods for analytes not addressed by 40 CFR Part 136. At a minimum, effluent testing data must be based on at least three pollutant scans and must be no more than four and one-half years old.

Outfall Number: 001-1

POLLUTANT	MAXIMUM DAILY DISCHARGE		AVERAGE DAILY DISCHARGE			ANALYTICAL METHOD	ML / MDL
	Conc.	Units	Conc.	Units	Number of Samples		
CONVENTIONAL AND NONCONVENTIONAL COMPOUNDS.							
AMMONIA (as N)			4.67	mg/L	3	M4500	
CHLORINE (TOTAL RESIDUAL, TRC)			0.32	mg/L	3		
DISSOLVED OXYGEN							
TOTAL KJELDAHL NITROGEN (TKN)			6.82	mg/L	3	M4500	
NITRATE PLUS NITRITE NITROGEN			4.04	mg/L	3	M4500	
OIL and GREASE							
PHOSPHORUS (Total)			3.90	mg/L	3	M4500	
TOTAL DISSOLVED SOLIDS (TDS)			224	mg/L	3	M4500	
OTHER							

**END OF PART B.**

**REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM 2A YOU MUST COMPLETE**



**FACILITY NAME AND PERMIT NUMBER:**

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086**BASIC APPLICATION INFORMATION****PART C. CERTIFICATION**

All applicants must complete the Certification Section. Refer to instructions to determine who is an officer for the purposes of this certification. All applicants must complete all applicable sections of Form 2A, as explained in the Application Overview. Indicate below which parts of Form 2A you have completed and are submitting. By signing this certification statement, applicants confirm that they have reviewed Form 2A and have completed all sections that apply to the facility for which this application is submitted.

Indicate which parts of Form 2A you have completed and are submitting:

☒ Basic Application Information packet

Supplemental Application Information packet:

☐ Part D (Expanded Effluent Testing Data)

☒ Part E (Toxicity Testing: Biomonitoring Data)


☐ Part F (Industrial User Discharges and RCRA/CERCLA Wastes)

☐ Part G (Combined Sewer Systems)

**ALL APPLICANTS MUST COMPLETE THE FOLLOWING CERTIFICATION.**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name and official title David J. Norton, Chairman

Signature 

Telephone number (256) 463-2011

Date signed 03/10/2014

Upon request of the permitting authority, you must submit any other information necessary to assess wastewater treatment practices at the treatment works or identify appropriate permitting requirements.

**SEND COMPLETED FORMS TO:**



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

## SUPPLEMENTAL APPLICATION INFORMATION

## PART D. EXPANDED EFFLUENT TESTING DATA

Refer to the directions on the cover page to determine whether this section applies to the treatment works.

**Effluent Testing: 1.0 mgd and Pretreatment Treatment Works.** If the treatment works has a design flow greater than or equal to 1.0 mgd or it has (or is required to have) a pretreatment program, or is otherwise required by the permitting authority to provide the data, then provide effluent testing data for the following pollutants. Provide the indicated effluent testing information and any other information required by the permitting authority for each outfall through which effluent is discharged. Do not include information on combined sewer overflows in this section. All information reported must be based on data collected through analyses conducted using 40 CFR Part 136 methods. In addition, these data must comply with QA/QC requirements of 40 CFR Part 136 and other appropriate QA/QC requirements for standard methods for analytes not addressed by 40 CFR Part 136. Indicate in the blank rows provided below any data you may have on pollutants not specifically listed in this form. At a minimum, effluent testing data must be based on at least three pollutant scans and must be no more than four and one-half years old.

Outfall number: \_\_\_\_\_ (Complete once for each outfall discharging effluent to waters of the United States.)

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/ MDL
	Conc.	Units	Mass	Units	Conc.	Units	Mass	Units	Number of Samples		
<b>METALS (TOTAL RECOVERABLE), CYANIDE, PHENOLS, AND HARDNESS.</b>											
ANTIMONY	<.005	mg/L			<.005	mg/L			3	E200.7	
ARSENIC	<.010	mg/L			<.010	mg/L			3	E200.7	
BERYLLIUM	<.001	mg/L			<.001	mg/L			3	E200.7	
CADMIUM	<.001	mg/L			<.001	mg/L			3	E200.7	
CHROMIUM	<.050	mg/L			<.050	mg/L			3	E200.7	
COPPER	0.058	mg/L			<.023	mg/L			3	E200.7	
LEAD	<.005	mg/L			<.005	mg/L			3	E200.7	
MERCURY	.007	µg/L			<0.5	µg/L			12		
NICKEL	<.050	mg/L			<.050	mg/L			3	E200.7	
SELENIUM	<.010	mg/L			<.010	mg/L			3	E200.9	
SILVER	<.050	mg/L			<.040	mg/L			3	E200.7	
THALLIUM	<.001	mg/L			<.001	mg/L			3	E200.9	
ZINC	<.050	mg/L			<.050	mg/L			3	E200.7	
CYANIDE	0.015	mg/L			<.010	mg/L			3	M4500-CN CE	
TOTAL PHENOLIC COMPOUNDS	<.010	mg/L			<.010	mg/L			3	M510AC	
HARDNESS (AS CaCO <sub>3</sub> )	69.5	mg/L			58.7	mg/L			3	E200.7	
Use this space (or a separate sheet) to provide information on other metals requested by the permit writer.											



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

Outfall number: \_\_\_\_\_ (Complete once for each outfall discharging effluent to waters of the United States.)

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/ MDL
	Conc.	Units	Mass	Units	Conc.	Units	Mass	Units	Number of Samples		
VOLATILE ORGANIC COMPOUNDS.											
ACROLEIN	<.100	mg/L			<.100	mg/L			3	SW8260B	
ACRYLONITRILE	<.100	mg/L			<.100	mg/L			3	SW8260B	
BENZENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
BROMOFORM	<.005	mg/L			<.005	mg/L			3	SW8260B	
CARBON TETRACHLORIDE	<.005	mg/L			<.005	mg/L			3	SW8260B	
CLOROBENZENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
CHLORODIBROMO-METHANE	<.005	mg/L			<.005	mg/L			3	SW8260B	
CHLOROETHANE	<.005	mg/L			<.010	mg/L			3	SW8260B	
2-CHLORO-ETHYL VINYL ETHER	<.010	mg/L			<.010	mg/L			3	SW8260B	
CHLOROFORM	<.010	mg/L			<.005	mg/L			3	SW8260B	
DICHLOROBROMO-METHANE	<.005	mg/L			<.005	mg/L			3	SW8260B	
1,1-DICHLOROETHANE	<.055	mg/L			<.005	mg/L			3	SW8260B	
1,2-DICHLOROETHANE	<.005	mg/L			<.005	mg/L			3	SW8260B	
TRANS-1,2-DICHLORO-ETHYLENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
1,1-DICHLOROETHYLENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
1,2-DICHLOROPROPANE	<.005	mg/L			<.005	mg/L			3	SW8260B	
1,3-DICHLORO-PROPYLENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
ETHYLBENZENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
METHYL BROMIDE	<.010	mg/L			<.010	mg/L			3	SW8260B	
METHYL CHLORIDE	<.005	mg/L			<.005	mg/L			3	SW8260B	
METHYLENE CHLORIDE	<.005	mg/L			<.005	mg/L			3	SW8260B	
1,1,2,2-TETRACHLORO-ETHANE	<.005	mg/L			<.005	mg/L			3	SW8260B	
TETRACHLORO-ETHYLENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
TOLUENE	<.005	mg/L			<.005	mg/L			3	SW8260B	



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

Outfall number: \_\_\_\_\_ (Complete once for each outfall discharging effluent to waters of the United States.)

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/ MDL
	Conc.	Units	Mass	Units	Conc.	Units	Mass	Units	Number of Samples		
1,1,1-TRICHLOROETHANE	<.005	mg/L			<.005	mg/L			3	SW8260B	
1,1,2-TRICHLOROETHANE	<.005	mg/L			<.005	mg/L			3	SW8260B	
TRICHLORETHYLENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
VINYL CHLORIDE	<.002	mg/L			<.002	mg/L			3	SW8260B	

Use this space (or a separate sheet) to provide information on other volatile organic compounds requested by the permit writer.

## ACID-EXTRACTABLE COMPOUNDS

P-CHLORO-M-CRESOL	<.010	mg/L			<.010	mg/L			3	E625	
2-CHLOROPHENOL	<.010	mg/L			<.010	mg/L			3	E625	
2,4-DICHLOROPHENOL	<.010	mg/L			<.010	mg/L			3	E625	
2,4-DIMETHYLPHENOL	<.010	mg/L			<.010	mg/L			3	E625	
4,6-DINITRO-O-CRESOL	<.050	mg/L			<.050	mg/L			3	E625	
2,4-DINITROPHENOL	<.050	mg/L			<.050	mg/L			3	E625	
2-NITROPHENOL	<.010	mg/L			<.010	mg/L			3	E625	
4-NITROPHENOL	<.050	mg/L			<.050	mg/L			3	E625	
PENTACHLOROPHENOL	<.025	mg/L			<.025	mg/L			3	E625	
PHENOL	<.010	mg/L			<.010	mg/L			3	E625	
2,4,6-TRICHLOROPHENOL	<.010	mg/L			<.010	mg/L			3	E625	

Use this space (or a separate sheet) to provide information on other acid-extractable compounds requested by the permit writer.

## BASE-NEUTRAL COMPOUNDS.

ACENAPHTHENE	<.010	mg/L			<.010	mg/L			3	E625	
ACENAPHTHYLENE	<.010	mg/L			<.010	mg/L			3	E625	
ANTHRACENE	<.010	mg/L			<.010	mg/L			3	E625	
BENZIDINE	<.050	mg/L			<.050	mg/L			3	E625	
BENZO(A)ANTHRACENE	<.010	mg/L			<.010	mg/L			3	E625	
BENZO(A)PYRENE	<.010	mg/L			<.010	mg/L			3	E625	



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

Outfall number: \_\_\_\_\_ (Complete once for each outfall discharging effluent to waters of the United States.)

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/ MDL
	Conc.	Units	Mass	Units	Conc.	Units	Mass	Units	Number of Samples		
3,4 BENZO-FLUORANTHENE	<.010	mg/L			<.010	mg/L			3	E625	
BENZO(GH)PERYLENE	<.010	mg/L			<.010	mg/L			3	E625	
BENZO(K)FLUORANTHENE	<.010	mg/L			<.010	mg/L			3	E625	
BIS (2-CHLOROETHOXY) METHANE	<.010	mg/L			<.010	mg/L			3	E625	
BIS (2-CHLOROETHYL)-ETHER	<.010	mg/L			<.010	mg/L			3	E625	
BIS (2-CHLOROISO-PROPYL) ETHER	<.010	mg/L			<.010	mg/L			3	E625	
BIS (2-ETHYLHEXYL) PHTHALATE	<.010	mg/L			<.010	mg/L			3	E625	
4-BROMOPHENYL PHENYL ETHER	<.010	mg/L			<.010	mg/L			3	E625	
BUTYL BENZYL PHTHALATE	<.010	mg/L			<.010	mg/L			3	E625	
2-CHLORONAPHTHALENE	<.010	mg/L			<.010	mg/L			3	E625	
4-CHLORPHENYL PHENYL ETHER	<.010	mg/L			<.010	mg/L			3	E625	
CHRYSENE	<.010	mg/L			<.010	mg/L			3	E625	
DI-N-BUTYL PHTHALATE	<.010	mg/L			<.010	mg/L			3	E625	
DI-N-OCTYL PHTHALATE	<.010	mg/L			<.010	mg/L			3	E625	
DIBENZO(A,H) ANTHRACENE	<.010	mg/L			<.010	mg/L			3	E625	
1,2-DICHLOROBENZENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
1,3-DICHLOROBENZENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
1,4-DICHLOROBENZENE	<.005	mg/L			<.005	mg/L			3	SW8260B	
3,3-DICHLOROBENZIDINE	<.020	mg/L			<.020	mg/L			3	E625	
DIETHYL PHTHALATE	<.010	mg/L			<.010	mg/L			3	E625	
DIMETHYL PHTHALATE	<.010	mg/L			<.010	mg/L			3	E625	
2,4-DINITROTOLUENE	<.010	mg/L			<.010	mg/L			3	E625	
2,6-DINITROTOLUENE	<.010	mg/L			<.010	mg/L			3	E625	
1,2-DIPHENYLHYDRAZINE	<.050	mg/L			<.050	mg/L			3	E625	



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

Outfall number: \_\_\_\_\_ (Complete once for each outfall discharging effluent to waters of the United States.)

POLLUTANT	MAXIMUM DAILY DISCHARGE				AVERAGE DAILY DISCHARGE					ANALYTICAL METHOD	ML/ MDL
	Conc.	Units	Mass	Units	Conc.	Units	Mass	Units	Number of Samples		
FLUORANTHENE	<.010	mg/L			<.010	mg/L			3	E625	
FLUORENE	<.010	mg/L			<.010	mg/L			3	E625	
HEXACHLOROBENZENE	<.010	mg/L			<.010	mg/L			3	E625	
HEXACHLOROBUTADIENE	<.010	mg/L			<.010	mg/L			3	E625	
HEXACHLOROCYCLO-PENTADIENE	<.010	mg/L			<.010	mg/L			3	E625	
HEXACHLOROETHANE	<.010	mg/L			<.010	mg/L			3	E625	
INDENO(1,2,3-CD)PYRENE	<.010	mg/L			<.010	mg/L			3	E625	
ISOPHORONE	<.010	mg/L			<.010	mg/L			3	E625	
NAPHTHALENE	<.010	mg/L			<.010	mg/L			3	E625	
NITROBENZENE	<.010	mg/L			<.010	mg/L			3	E625	
N-NITROSODI-N-PROPYLAMINE	<.010	mg/L			<.010	mg/L			3	E625	
N-NITROSODI- METHYLAMINE	<.010	mg/L			<.010	mg/L			3	E625	
N-NITROSODI-PHENYLAMINE	<.010	mg/L			<.010	mg/L			3	E625	
PHENANTHRENE	<.010	mg/L			<.010	mg/L			3	E625	
PYRENE	<.010	mg/L			<.010	mg/L			3	E625	
1,2,4-TRICHLOROBENZENE	<.010	mg/L			<.010	mg/L			3	E625	

Use this space (or a separate sheet) to provide information on other base-neutral compounds requested by the permit writer.

Use this space (or a separate sheet) to provide information on other pollutants (e.g., pesticides) requested by the permit writer.

## END OF PART D.

REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM 2A YOU MUST COMPLETE



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

## SUPPLEMENTAL APPLICATION INFORMATION

## PART E. TOXICITY TESTING DATA

POTWs meeting one or more of the following criteria must provide the results of whole effluent toxicity tests for acute or chronic toxicity for each of the facility's discharge points: 1) POTWs with a design flow rate greater than or equal to 1.0 mgd; 2) POTWs with a pretreatment program (or those that are required to have one under 40 CFR Part 403); or 3) POTWs required by the permitting authority to submit data for these parameters.

- At a minimum, these results must include quarterly testing for a 12-month period within the past 1 year using multiple species (minimum of two species), or the results from four tests performed at least annually in the four and one-half years prior to the application, provided the results show no appreciable toxicity, and testing for acute and/or chronic toxicity, depending on the range of receiving water dilution. Do not include information on combined sewer overflows in this section. All information reported must be based on data collected through analysis conducted using 40 CFR Part 136 methods. In addition, this data must comply with QA/QC requirements of 40 CFR Part 136 and other appropriate QA/QC requirements for standard methods for analytes not addressed by 40 CFR Part 136.
- In addition, submit the results of any other whole effluent toxicity tests from the past four and one-half years. If a whole effluent toxicity test conducted during the past four and one-half years revealed toxicity, provide any information on the cause of the toxicity or any results of a toxicity reduction evaluation, if one was conducted.
- If you have already submitted any of the information requested in Part E, you need not submit it again. Rather, provide the information requested in question E.4 for previously submitted information. If EPA methods were not used, report the reasons for using alternate methods. If test summaries are available that contain all of the information requested below, they may be submitted in place of Part E.

If no biomonitoring data is required, do not complete Part E. Refer to the Application Overview for directions on which other sections of the form to complete.

## E.1. Required Tests.

Indicate the number of whole effluent toxicity tests conducted in the past four and one-half years.

☒ chronic ☐ acute

E.2. Individual Test Data. Complete the following chart for each whole effluent toxicity test conducted in the last four and one-half years. Allow one column per test (where each species constitutes a test). Copy this page if more than three tests are being reported.

Test number: 1Test number: 1

Test number: \_\_\_\_\_

## a. Test information.

Test species & test method number	Ceriodaphnia dubia	Pimephales promelas	
Age at initiation of test	< 24 hours	< 24 hours	
Outfall number	001	001	
Dates sample collected	09/20 - 09/26/11	09/18 - 09/23/11	
Date test started	09/20/11	09/20/11	
Duration	7 days	7 days	

## b. Give toxicity test methods followed.

Manual title			
Edition number and year of publication			
Page number(s)			

## c. Give the sample collection method(s) used. For multiple grab samples, indicate the number of grab samples used.

24-Hour composite	X	X	
Grab			

## d. Indicate where the sample was taken in relation to disinfection. (Check all that apply for each)

Before disinfection			
After disinfection			
After dechlorination			



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086Test number: 1Test number: 1

Test number: \_\_\_\_\_

e. Describe the point in the treatment process at which the sample was collected.

Sample was collected:

Lagoon effluent

Lagoon effluent

f. For each test, include whether the test was intended to assess chronic toxicity, acute toxicity, or both.

Chronic toxicity

X

X

Acute toxicity

g. Provide the type of test performed.

Static

Static-renewal

X

X

Flow-through

h. Source of dilution water. If laboratory water, specify type; if receiving water, specify source.

Laboratory water

X

X

Receiving water

i. Type of dilution water. If salt water, specify "natural" or type of artificial sea salts or brine used.

Fresh water

X

X

Salt water

j. Give the percentage effluent used for all concentrations in the test series.

3%

3%

3%

3%

3%

3%

k. Parameters measured during the test. (State whether parameter meets test method specifications)

pH

7.8

7.8

Salinity

Temperature

25 °C

25 °C

Ammonia

Dissolved oxygen

7.2 - 8.3

6.4 - 8.3

l. Test Results.

Acute:

Percent survival in 100%  
effluent

%

%

%

LC<sub>50</sub>

95% C.I.

%

%

%

Control percent survival

%

%

%

Other (describe)



**FACILITY NAME AND PERMIT NUMBER:**

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086**Chronic:**

NOEC	100 %	100 %	%
IC <sub>25</sub>	100 %	100 %	%
Control percent survival	100 %	100 %	%
Other (describe)			

**m. Quality Control/Quality Assurance.**

Is reference toxicant data available?	on file at ADEM		
Was reference toxicant test within acceptable bounds?			
What date was reference toxicant test run (MM/DD/YYYY)?			
Other (describe)			

**E.3. Toxicity Reduction Evaluation. Is the treatment works involved in a Toxicity Reduction Evaluation?**

     Yes ☒ No      If yes, describe: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**E.4. Summary of Submitted Biomonitoring Test Information.** If you have submitted biomonitoring test information, or information regarding the cause of toxicity, within the past four and one-half years, provide the dates the information was submitted to the permitting authority and a summary of the results.Date submitted: 10/11/2014 (MM/DD/YYYY)

Summary of results: (see instructions)

passed  
\_\_\_\_\_

**END OF PART E.**  
**REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM 2A YOU MUST COMPLETE.**



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

## SUPPLEMENTAL APPLICATION INFORMATION

## PART E. TOXICITY TESTING DATA

POTWs meeting one or more of the following criteria must provide the results of whole effluent toxicity tests for acute or chronic toxicity for each of the facility's discharge points: 1) POTWs with a design flow rate greater than or equal to 1.0 mgd; 2) POTWs with a pretreatment program (or those that are required to have one under 40 CFR Part 403); or 3) POTWs required by the permitting authority to submit data for these parameters.

- At a minimum, these results must include quarterly testing for a 12-month period within the past 1 year using multiple species (minimum of two species), or the results from four tests performed at least annually in the four and one-half years prior to the application, provided the results show no appreciable toxicity, and testing for acute and/or chronic toxicity, depending on the range of receiving water dilution. Do not include information on combined sewer overflows in this section. All information reported must be based on data collected through analysis conducted using 40 CFR Part 136 methods. In addition, this data must comply with QA/QC requirements of 40 CFR Part 136 and other appropriate QA/QC requirements for standard methods for analytes not addressed by 40 CFR Part 136.
- In addition, submit the results of any other whole effluent toxicity tests from the past four and one-half years. If a whole effluent toxicity test conducted during the past four and one-half years revealed toxicity, provide any information on the cause of the toxicity or any results of a toxicity reduction evaluation, if one was conducted.
- If you have already submitted any of the information requested in Part E, you need not submit it again. Rather, provide the information requested in question E.4 for previously submitted information. If EPA methods were not used, report the reasons for using alternate methods. If test summaries are available that contain all of the information requested below, they may be submitted in place of Part E.

If no biomonitoring data is required, do not complete Part E. Refer to the Application Overview for directions on which other sections of the form to complete.

## E.1. Required Tests.

Indicate the number of whole effluent toxicity tests conducted in the past four and one-half years.

☒ chronic ☐ acute

E.2. Individual Test Data. Complete the following chart for each whole effluent toxicity test conducted in the last four and one-half years. Allow one column per test (where each species constitutes a test). Copy this page if more than three tests are being reported.

Test number: 2Test number: 2

Test number: \_\_\_\_\_

## a. Test information.

Test species & test method number	Ceriodaphnia dubia	Pimephales promelas	
Age at initiation of test	< 24 hours	24 - 36 hours	
Outfall number	001	001	
Dates sample collected	09/23 - 09/28/12	09/23 - 09/28/12	
Date test started	09/25 - 10/01/12	09/25 - 10/02/12	
Duration	3 BROOD	7 days	

## b. Give toxicity test methods followed.

Manual title	EPA Chronic Manual	EPA Chronic Manual	
Edition number and year of publication	4th Edition 2002	4th Edition 2002	
Page number(s)			

## c. Give the sample collection method(s) used. For multiple grab samples, indicate the number of grab samples used.

24-Hour composite	X	X	
Grab			

## d. Indicate where the sample was taken in relation to disinfection. (Check all that apply for each)

Before disinfection			
After disinfection			
After dechlorination			



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086Test number: 2Test number: 2

Test number: \_\_\_\_\_

e. Describe the point in the treatment process at which the sample was collected.

Sample was collected:

Discharge at Lagoon

Discharge at Lagoon

f. For each test, include whether the test was intended to assess chronic toxicity, acute toxicity, or both.

Chronic toxicity

X

X

Acute toxicity

g. Provide the type of test performed.

Static

Static-renewal

X

X

Flow-through

h. Source of dilution water. If laboratory water, specify type; if receiving water, specify source.

Laboratory water

20% dilute mineral water

Receiving water

i. Type of dilution water. If salt water, specify "natural" or type of artificial sea salts or brine used.

Fresh water

X

X

Salt water

j. Give the percentage effluent used for all concentrations in the test series.

2.04 %

2.04 %

2.04 %

2.04 %

2.04 %

2.04 %

k. Parameters measured during the test. (State whether parameter meets test method specifications)

pH

7.8

7.8

Salinity

Temperature

25 °C

25 °C

Ammonia

Dissolved oxygen

8.43

8.43

l. Test Results.

Acute:

Percent survival in 100%  
effluent

%

%

%

LC<sub>50</sub>

95% C.I.

%

%

%

Control percent survival

%

%

%

Other (describe)



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

Chronic:

NOEC	2.04 %	2.04 %	%
IC <sub>25</sub>	0.1678 %	0.6383 %	%
Control percent survival	100 %	100 %	%
Other (describe)			

m. Quality Control/Quality Assurance.

Is reference toxicant data available?	yes		
Was reference toxicant test within acceptable bounds?	yes		
What date was reference toxicant test run (MM/DD/YYYY)?		09/05/2012	
Other (describe)			

## E.3. Toxicity Reduction Evaluation. Is the treatment works involved in a Toxicity Reduction Evaluation?

☐ Yes ☒ No

If yes, describe:

## E.4. Summary of Submitted Biomonitoring Test Information. If you have submitted biomonitoring test information, or information regarding the cause of toxicity, within the past four and one-half years, provide the dates the information was submitted to the permitting authority and a summary of the results.

Date submitted: 10/11/2014 (MM/DD/YYYY)

Summary of results: (see instructions)

passed

END OF PART E.

REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM 2A YOU MUST COMPLETE.



**SUPPLEMENTAL APPLICATION INFORMATION****PART E. TOXICITY TESTING DATA**

POTWs meeting one or more of the following criteria must provide the results of whole effluent toxicity tests for acute or chronic toxicity for each of the facility's discharge points: 1) POTWs with a design flow rate greater than or equal to 1.0 mgd; 2) POTWs with a pretreatment program (or those that are required to have one under 40 CFR Part 403); or 3) POTWs required by the permitting authority to submit data for these parameters.

- At a minimum, these results must include quarterly testing for a 12-month period within the past 1 year using multiple species (minimum of two species), or the results from four tests performed at least annually in the four and one-half years prior to the application, provided the results show no appreciable toxicity, and testing for acute and/or chronic toxicity, depending on the range of receiving water dilution. Do not include information on combined sewer overflows in this section. All information reported must be based on data collected through analysis conducted using 40 CFR Part 136 methods. In addition, this data must comply with QA/QC requirements of 40 CFR Part 136 and other appropriate QA/QC requirements for standard methods for analytes not addressed by 40 CFR Part 136.
- In addition, submit the results of any other whole effluent toxicity tests from the past four and one-half years. If a whole effluent toxicity test conducted during the past four and one-half years revealed toxicity, provide any information on the cause of the toxicity or any results of a toxicity reduction evaluation, if one was conducted.
- If you have already submitted any of the information requested in Part E, you need not submit it again. Rather, provide the information requested in question E.4 for previously submitted information. If EPA methods were not used, report the reasons for using alternate methods. If test summaries are available that contain all of the information requested below, they may be submitted in place of Part E.

If no biomonitoring data is required, do not complete Part E. Refer to the Application Overview for directions on which other sections of the form to complete.

**E.1. Required Tests.**

Indicate the number of whole effluent toxicity tests conducted in the past four and one-half years.

☒ chronic      ☐ acute

**E.2. Individual Test Data.** Complete the following chart for each whole effluent toxicity test conducted in the last four and one-half years. Allow one column per test (where each species constitutes a test). Copy this page if more than three tests are being reported.

Test number: 3

Test number: 3

Test number: \_\_\_\_\_

**a. Test information.**

Test species & test method number	Ceriodaphnia dubia	Pimephales promelas	
Age at initiation of test	< 24 hours	24 - 36 hours	
Outfall number	001	001	
Dates sample collected	10/20 - 10/25/2013	10/22 - 10/28/13	
Date test started	10/22/13	10/22/13	
Duration	7 days	7 days	

**b. Give toxicity test methods followed.**

Manual title			
Edition number and year of publication			
Page number(s)			

**c. Give the sample collection method(s) used. For multiple grab samples, indicate the number of grab samples used.**

24-Hour composite	X	X	
Grab			

**d. Indicate where the sample was taken in relation to disinfection. (Check all that apply for each)**

Before disinfection			
After disinfection			
After dechlorination			



**FACILITY NAME AND PERMIT NUMBER:**  
Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

Test number: <u>3</u>		Test number: <u>3</u>		Test number: _____	
e. Describe the point in the treatment process at which the sample was collected.					
Sample was collected:	Lagoon effluent	Lagoon effluent			
f. For each test, include whether the test was intended to assess chronic toxicity, acute toxicity, or both.					
Chronic toxicity	X	X			
Acute toxicity					
g. Provide the type of test performed.					
Static					
Static-renewal	X	X			
Flow-through					
h. Source of dilution water. If laboratory water, specify type; if receiving water, specify source.					
Laboratory water	X	X			
Receiving water					
i. Type of dilution water. It salt water, specify "natural" or type of artificial sea salts or brine used.					
Fresh water					
Salt water					
j. Give the percentage effluent used for all concentrations in the test series.					
	65%	65%			
	65%	65%			
	65%	65%			
k. Parameters measured during the test. (State whether parameter meets test method specifications)					
pH	6.38 - 7.68	6.38 - 7.68			
Salinity					
Temperature					
Ammonia	0.68 - 1.3	0.68 - 1.3			
Dissolved oxygen					
l. Test Results.					
Acute:					
Percent survival in 100% effluent		%		%	%
LC <sub>50</sub>					
95% C.I.		%		%	%
Control percent survival		%		%	%
Other (describe)					



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

Chronic:

NOEC	100 %	100 %	%
IC <sub>25</sub>	100 %	100 %	%
Control percent survival	100 %	100 %	%
Other (describe)			

## m. Quality Control/Quality Assurance.

Is reference toxicant data available?	yes		
Was reference toxicant test within acceptable bounds?	yes		
What date was reference toxicant test run (MM/DD/YYYY)?		09/05/2012	
Other (describe)			

## E.3. Toxicity Reduction Evaluation. Is the treatment works involved in a Toxicity Reduction Evaluation?

☐ Yes ☒ No

If yes, describe: \_\_\_\_\_

## E.4. Summary of Submitted Biomonitoring Test Information. If you have submitted biomonitoring test information, or information regarding the cause of toxicity, within the past four and one-half years, provide the dates the information was submitted to the permitting authority and a summary of the results.

Date submitted: 10/11/2014 (MM/DD/YYYY)

Summary of results: (see instructions)

passed

END OF PART E.

REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM  
2A YOU MUST COMPLETE.



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

## SUPPLEMENTAL APPLICATION INFORMATION

## PART F. INDUSTRIAL USER DISCHARGES AND RCRA/CERCLA WASTES

All treatment works receiving discharges from significant industrial users or which receive RCRA, CERCLA, or other remedial wastes must complete Part F.

## GENERAL INFORMATION:

F.1. Pretreatment Program. Does the treatment works have, or is it subject to, an approved pretreatment program?

☐ Yes ☐ No

F.2. Number of Significant Industrial Users (SIUs) and Categorical Industrial Users (CIUs). Provide the number of each of the following types of industrial users that discharge to the treatment works.

- a. Number of non-categorical SIUs. \_\_\_\_\_
- b. Number of CIUs. \_\_\_\_\_

## SIGNIFICANT INDUSTRIAL USER INFORMATION:

Supply the following information for each SIU. If more than one SIU discharges to the treatment works, copy questions F.3 through F.8 and provide the information requested for each SIU.

F.3. Significant Industrial User Information. Provide the name and address of each SIU discharging to the treatment works. Submit additional pages as necessary.

Name: \_\_\_\_\_

Mailing Address: \_\_\_\_\_

F.4. Industrial Processes. Describe all of the industrial processes that affect or contribute to the SIU's discharge.

\_\_\_\_\_

F.5. Principal Product(s) and Raw Material(s). Describe all of the principal processes and raw materials that affect or contribute to the SIU's discharge.

Principal product(s): \_\_\_\_\_

Raw material(s): \_\_\_\_\_

F.6. Flow Rate.

- a. Process wastewater flow rate. Indicate the average daily volume of process wastewater discharged into the collection system in gallons per day (gpd) and whether the discharge is continuous or intermittent.

\_\_\_\_\_ gpd (☐ continuous or ☐ intermittent)

- b. Non-process wastewater flow rate. Indicate the average daily volume of non-process wastewater flow discharged into the collection system in gallons per day (gpd) and whether the discharge is continuous or intermittent.

\_\_\_\_\_ gpd (☐ continuous or ☐ intermittent)

F.7. Pretreatment Standards. Indicate whether the SIU is subject to the following:

- a. Local limits ☐ Yes ☐ No

- b. Categorical pretreatment standards ☐ Yes ☐ No

If subject to categorical pretreatment standards, which category and subcategory?

\_\_\_\_\_



**FACILITY NAME AND PERMIT NUMBER:**

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

**F.8. Problems at the Treatment Works Attributed to Waste Discharged by the SIU.** Has the SIU caused or contributed to any problems (e.g., upsets, interference) at the treatment works in the past three years?

☐ Yes ☐ No If yes, describe each episode.

\_\_\_\_\_  
\_\_\_\_\_

**RCRA HAZARDOUS WASTE RECEIVED BY TRUCK, RAIL, OR DEDICATED PIPELINE:**

**F.9. RCRA Waste.** Does the treatment works receive or has it in the past three years received RCRA hazardous waste by truck, rail, or dedicated pipe? ☐ Yes ☐ No (go to F.12.)

**F.10. Waste Transport.** Method by which RCRA waste is received (check all that apply):

☐ Truck ☐ Rail ☐ Dedicated Pipe

**F.11. Waste Description.** Give EPA hazardous waste number and amount (volume or mass, specify units).

<u>EPA Hazardous Waste Number</u>	<u>Amount</u>	<u>Units</u>
_____	_____	_____
_____	_____	_____
_____	_____	_____

**CERCLA (SUPERFUND) WASTEWATER, RCRA REMEDIATION/CORRECTIVE ACTION WASTEWATER, AND OTHER REMEDIAL ACTIVITY WASTEWATER:**

**F.12. Remediation Waste.** Does the treatment works currently (or has it been notified that it will) receive waste from remedial activities?

☐ Yes (complete F.13 through F.15.) ☐ No

Provide a list of sites and the requested information (F.13 - F.15.) for each current and future site.

**F.13. Waste Origin.** Describe the site and type of facility at which the CERCLA/RCRA/or other remedial waste originates (or is expected to originate in the next five years).

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**F.14. Pollutants.** List the hazardous constituents that are received (or are expected to be received). Include data on volume and concentration, if known. (Attach additional sheets if necessary).

\_\_\_\_\_  
\_\_\_\_\_

**F.15. Waste Treatment.**

a. Is this waste treated (or will it be treated) prior to entering the treatment works?

☐ Yes ☐ No

If yes, describe the treatment (provide information about the removal efficiency):

\_\_\_\_\_  
\_\_\_\_\_

b. Is the discharge (or will the discharge be) continuous or intermittent?

☐ Continuous ☐ Intermittent If intermittent, describe discharge schedule.

\_\_\_\_\_

**END OF PART F.**  
**REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM 2A YOU MUST COMPLETE**



## FACILITY NAME AND PERMIT NUMBER:

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

## SUPPLEMENTAL APPLICATION INFORMATION

## PART G. COMBINED SEWER SYSTEMS

If the treatment works has a combined sewer system, complete Part G.

G.1. System Map. Provide a map indicating the following: (may be included with Basic Application Information)

- a. All CSO discharge points.
- b. Sensitive use areas potentially affected by CSOs (e.g., beaches, drinking water supplies, shellfish beds, sensitive aquatic ecosystems, and outstanding natural resource waters).
- c. Waters that support threatened and endangered species potentially affected by CSOs.

G.2. System Diagram. Provide a diagram, either in the map provided in G.1. or on a separate drawing, of the combined sewer collection system that includes the following information:

- a. Locations of major sewer trunk lines, both combined and separate sanitary.
- b. Locations of points where separate sanitary sewers feed into the combined sewer system.
- c. Locations of in-line and off-line storage structures.
- d. Locations of flow-regulating devices.
- e. Locations of pump stations.

## CSO OUTFALLS:

Complete questions G.3 through G.6 once for each CSO discharge point.

G.3. Description of Outfall.

- a. Outfall number \_\_\_\_\_
- b. Location \_\_\_\_\_  
 (City or town, if applicable) \_\_\_\_\_ (Zip Code) \_\_\_\_\_  
 (County) \_\_\_\_\_ (State) \_\_\_\_\_  
 (Latitude) \_\_\_\_\_ (Longitude) \_\_\_\_\_
- c. Distance from shore (if applicable) \_\_\_\_\_ ft.
- d. Depth below surface (if applicable) \_\_\_\_\_ ft.
- e. Which of the following were monitored during the last year for this CSO?  
 \_\_\_\_\_ Rainfall \_\_\_\_\_ CSO pollutant concentrations \_\_\_\_\_ CSO frequency  
 \_\_\_\_\_ CSO flow volume \_\_\_\_\_ Receiving water quality
- f. How many storm events were monitored during the last year? \_\_\_\_\_

G.4. CSO Events.

- a. Give the number of CSO events in the last year.  
 \_\_\_\_\_ events (\_\_\_\_ actual or \_\_\_\_ approx.)
- b. Give the average duration per CSO event.  
 \_\_\_\_\_ hours (\_\_\_\_ actual or \_\_\_\_ approx.)



**FACILITY NAME AND PERMIT NUMBER:**

Heflin Lagoon - AL0056146

Form Approved 1/14/99  
OMB Number 2040-0086

- c. Give the average volume per CSO event.  
\_\_\_\_\_ million gallons (\_\_\_\_\_ actual or \_\_\_\_\_ approx.)
- d. Give the minimum rainfall that caused a CSO event in the last year.  
\_\_\_\_\_ inches of rainfall

**G.5. Description of Receiving Waters.**

- a. Name of receiving water: \_\_\_\_\_
- b. Name of watershed/river/stream system: \_\_\_\_\_  
  
United States Soil Conservation Service 14-digit watershed code (if known): \_\_\_\_\_
- c. Name of State Management/River Basin: \_\_\_\_\_  
  
United States Geological Survey 8-digit hydrologic cataloging unit code (if known): \_\_\_\_\_

**G.6. CSO Operations.**

Describe any known water quality impacts on the receiving water caused by this CSO (e.g., permanent or intermittent beach closings, permanent or intermittent shell fish bed closings, fish kills, fish advisories, other recreational loss, or violation of any applicable State water quality standard).

\_\_\_\_\_  
\_\_\_\_\_

**END OF PART G.  
REFER TO THE APPLICATION OVERVIEW TO DETERMINE WHICH OTHER PARTS OF FORM  
2A YOU MUST COMPLETE.**

Additional information, if provided, will appear on the following pages.



**SUPPLEMENTARY INFORMATION**  
**NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES)**  
**PERMIT APPLICATION FORM 188- Municipal, Semi-Public & Private Facilities**

ALABAMA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT  
WATER DIVISION – MUNICIPAL PERMIT SECTION  
POST OFFICE BOX 301463  
MONTGOMERY, ALABAMA 36130-1463

**INSTRUCTIONS:** APPLICATIONS SHOULD BE TYPED OR PRINTED IN INK AND SUBMITTED TO THE DEPARTMENT. PLEASE CONTINUE ON AN ATTACHED SHEET OF PAPER IF INSUFFICIENT SPACE IS AVAILABLE TO ADDRESS ANY ITEM BELOW. PLEASE MARK N/A IN THE APPROPRIATE BOX WHEN AN ITEM IS NON-APPLICABLE TO THE APPLICANT.

**PURPOSE OF THIS APPLICATION**

- |   |  |
|---|--|
| <input type="checkbox"/> INITIAL PERMIT APPLICATION FOR NEW FACILITY<br><input type="checkbox"/> MODIFICATION OF EXISTING PERMIT<br><input type="checkbox"/> REVOCATION & REISSUANCE OF EXISTING PERMIT | <input type="checkbox"/> INITIAL PERMIT APPLICATION FOR EXISTING FACILITY<br><input checked="" type="checkbox"/> REISSUANCE OF EXISTING PERMIT |
|---|--|

**SECTION A – GENERAL INFORMATION**

1. Facility Name: Heflin Lagoon
  - a. Operator Name: Heflin Water Works and Sewer Board
  - b. Is the operator identified in 1.a, the owner of the facility? Yes ☒ No ☐  
If no, provide name and address of the operator and submit information indicating the operator's scope of responsibility for the facility.  
N/A
  - c. Name of Permittee\* if different than Operator: N/A  
*\*Permittee will be responsible for compliance with the conditions of the permit*
2. NPDES Permit Number AL 0056146 (Not applicable if initial permit application)
3. Facility Location: (**Attach a map with location marked; street, route no. or other specific identifier**)  
Street: U. S. Highway 78 West  
City: Heflin County: Cleburne State: Alabama Zip: 36264  
Facility (Front Gate) Location: Latitude (Deg Min Sec): 33° 18' 22" Longitude (Deg. Min Sec): 85° 36' 22"
4. Facility Mailing Address (Street or Post Office Box): P.O. Box 488  
City: Heflin County: Cleburne State: Alabama Zip: 36264
5. Responsible Official (as described on page 7 of this application):  
Name and Title: David J. Norton, Chairman  
Address: P. O. Box 488  
City: Heflin State: Alabama Zip: 36264  
Phone Number: (205) 463-2011  
Email Address: (Optional): \_\_\_\_\_

6. Designated Facility/DMR Contact:

Name and Title: Donald Dewberry, Superintendent

Phone Number: (256) 463-2011

DMR Email Address (Optional – for receipt of blank DMR Forms): \_\_\_\_\_

7. Please complete this section if the Applicant's business entity is a Proprietorship or limited liability Corporation with a responsible official not listed in Item 5.

a) Proprietor:

Name: N/A

Address: N/A

City: N/A

State: N/A

Zip: N/A

8. Permit numbers for Applicant's previously issued NPDES Permits and identification of any other State Environmental Permits presently held by the Applicant within the State of Alabama:

<u>Permit Name</u>	<u>Permit Number</u>	<u>Held by</u>
<u>NPDES - Heflin Lagoon</u>	<u>AL0056146</u>	<u>Heflin Water Works &amp; Sewer Board</u>
<u>Backwash Water Plant</u>	<u>ALG640040</u>	<u>Heflin Water Works &amp; Sewer Board</u>
_____	_____	_____
_____	_____	_____

9. Identify all Administrative Complaints, Notices of Violation, Directives, or Administrative Orders, Consent Decrees, or Litigation concerning water pollution or other permit violations, if any against the Applicant within the State of Alabama in the past five years (attach additional sheets if necessary):

<u>Facility Name</u>	<u>Permit Number</u>	<u>Type of Action</u>	<u>Date of Action</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

**SECTION B – WASTEWATER DISCHARGE INFORMATION**

1. List the following historical monthly flow rates recorded for the past five years for each outfall:

<u>Outfall Number</u>	<u>Highest in Last 12 Months MGD</u>	<u>Highest Daily Flow MGD</u>	<u>Average Flow MGD</u>
<u>001-1 2013</u>	<u>0.351</u>	<u>1.445</u>	<u>0.251</u>
<u>2012</u>	<u>0.422</u>	<u>0.827</u>	<u>0.2508</u>



2. Report E-coli (Freshwater) or Enterococci (Coastal Waters) monitoring results for the past five years for each outfall if available:

Outfall Number	Ecoli or Enterococci	Maximum Daily E-coli / Enterococci Discharge (per 100 ml)	Maximum Monthly Average E-Coli / Enterococci Discharge (per 100 ml)	No. of Analyses	Analytical Method	ML/MDL
N/A	N/A	N/A	N/A	N/A	N/A	N/A

3. Attached a process flow schematic of the treatment process, including the size of each unit operation.
4. Do you have, or plan to have, automatic sampling equipment or continuous wastewater flow metering equipment at this facility?

Current:	Flow Metering	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	N/A <input type="checkbox"/>
	Sampling Equipment	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	N/A <input type="checkbox"/>
Planned:	Flow Metering	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Sampling Equipment	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>

If so, please attach a schematic diagram of the sewer system indicating the present or future location of this equipment and describe the equipment below:

The flow metering equipment is an in-line propeller flow meter installed in the 16 inch diameter effluent force downstream of the effluent pumping station

5. Are any wastewater collection or treatment modifications or expansions planned during the next three years that could alter wastewater volumes or characteristics (Note: Permit Modification may be required)? Yes ☐ No ☒

Briefly describe these changes and any potential or anticipated effects on the wastewater quality and quantity: (Attach additional sheets if needed.)

## SECTION C – WASTE STORAGE AND DISPOSAL INFORMATION

Describe the location of all sites used for the storage of solids or liquids that have any potential for accidental discharge to a water of the state, either directly or indirectly via storm sewer, municipal sewer, municipal wastewater treatment plants, or other collection or distribution systems that are located at or operated by the subject existing or proposed NPDES-permitted facility. Indicate the location of any potential release areas and provide a map or detailed narrative description of the areas of concern as an attachment to this application:

Description of Waste

Description of Storage Location

Describe the location of any sites used for the ultimate disposal of solid or liquid waste materials or residuals (e.g. sludges) generated by any wastewater treatment system located at the facility.

Description of Waste

Quantity  
(lbs/day)

Disposal Method\*

\*Indicate any wastes disposed at an off-site treatment facility and any wastes that are disposed on-site



## SECTION D – INDUSTRIAL INDIRECT DISCHARGE CONTRIBUTORS

1. List the existing and proposed industrial source wastewater contributions to the municipal wastewater treatment system (Attach other sheets if necessary)

Company Name	Description of Industrial Wastewater	Existing or Proposed	Flow (MGD)	Subject to SID Permit? Y/N
Forte, Inc.	Wire Cooling & Makeup Water	Existing	0.020	Y #1U341500162

2. Are industrial wastewater contributions regulated via a locally approved sewer use ordinance Y/N? If so, please attach a copy of the ordinance.

## SECTION E – COASTAL ZONE INFORMATION

Is the discharge(s) located within the 10-foot elevation contour and within the limits of Mobile or Baldwin County?  
Yes ☐ No ☒ If yes, then complete items A through M below:

	YES	NO
A. Does the project require new construction?	<input type="checkbox"/>	<input type="checkbox"/>
B. Will the project be a source of new air emissions?	<input type="checkbox"/>	<input type="checkbox"/>
C. Does the project involve dredging and/or filling of a wetland area or water way?	<input type="checkbox"/>	<input type="checkbox"/>
Has the Corps of Engineers (COE) permit been issued?	<input type="checkbox"/>	<input type="checkbox"/>
Corps Project Number _____		
D. Does the project involve wetlands and/or submersed grassbeds?	<input type="checkbox"/>	<input type="checkbox"/>
E. Are oyster reefs located near the project site? (Include a map showing project and discharge location with respect to oyster reefs)	<input type="checkbox"/>	<input type="checkbox"/>
F. Does the project involve the site development, construction and operation of an energy facility as defined in ADEM Admin. Code R. 335-8-1-.02(bb)?	<input type="checkbox"/>	<input type="checkbox"/>
G. Does the project involve mitigation of shoreline or coastal area erosion?	<input type="checkbox"/>	<input type="checkbox"/>
H. Does the project involve construction on beaches or dunes areas?	<input type="checkbox"/>	<input type="checkbox"/>
I. Will the project interfere with public access to coastal waters?	<input type="checkbox"/>	<input type="checkbox"/>
J. Does the project lie within the 100-year floodplain?	<input type="checkbox"/>	<input type="checkbox"/>
K. Does the project involve the registration, sale, use, or application of pesticides?	<input type="checkbox"/>	<input type="checkbox"/>
L. Does the project propose or require construction of a new well or to alter an existing groundwater well to pump more than 50 gallons per day (GPD)?	<input type="checkbox"/>	<input type="checkbox"/>
M. Has the applicable permit for groundwater recovery or for groundwater well installation been obtained?	<input type="checkbox"/>	<input type="checkbox"/>



---

## SECTION F – ANTI-DEGRADATION EVALUATION

It is the applicant's responsibility to demonstrate the social and economic importance of the proposed activity, if subject to antidegradation requirements. In accordance with 40 CFR 131.12 and Section 335-6-10-.04 of the Alabama Department of Environmental Management Administrative Code, the following information must be provided, if applicable. If further information is required to make this demonstration, attach additional sheets to the application.

1. Is this a new or increased discharge that began after April 3, 1991? Yes ☐ No ☒.  
If "yes", complete question 2 below. If "no", do not complete this section.
2. Has an Anti-Degradation Analysis been previously conducted and submitted to the Department for the new or increased discharge referenced in question 1? Yes ☐ No ☐.

If "no" and the discharge is to a Tier II waterbody as defined in ADEM Admin. Code r. 335-6-10-.12(4), complete questions A through F below and also ADEM forms 311 and 312 or 313, whichever is applicable, (attached). Form 312 or 313, whichever is applicable, must be provided for each treatment discharge alternative considered technically viable. If "yes", do not complete this section.

Information required for new or increased discharges to high quality waters:

- A. What environmental or public health problem will the discharger be correcting?
- B. Explain if and to what degree the discharger will be increasing employment as a result of the proposed discharge, either at its existing facility or as the result of the start-up of a related new facility or industry.
- C. Explain if and to what degree the discharge will prevent employment reductions?
- D. Describe any additional state or local taxes that the prospective discharger will be paying.
- E. Describe any public service the discharger will be providing to the community.
- F. Describe the economic or social benefit the discharger will be providing to the community.

---

## SECTION G – EPA Application Forms

All Applicants must submit certain EPA permit application forms. More than one application form may be required from a municipal facility depending on the number and types of discharges or outfalls. The EPA application forms are found on the Department's website at <http://www.adem.state.al.us/> and are also listed in Attachment 4.

---

## SECTION H– ENGINEERING REPORT/BMP PLAN REQUIREMENTS

Any Engineering Report or Best Management Practice (BMP) Plans required to be submitted to ADEM by the applicant must be in accordance with ADEM 335-6-6-.08(i) & (j).

---

## SECTION I– RECEIVING WATERS

Receiving Water(s)	303(d) Segment? (Y / N)	Included in TMDL?* (Y / N)

\*If a TMDL Compliance Schedule is requested the following should be attached as supporting documentation:

(1) Justification for the proposed Compliance Schedule (e.g. time for design and installation of control equipment, etc.); (2) Monitoring results for the pollutant(s) of concern which have not previously been submitted to the Department (sample collection dates, analytical results (mass and concentration), methods utilized, MDL/ML, etc. should be reported as available); (3) Requested interim limitations, if applicable; (4) Date of final compliance with the TMDL limitations; and (5) Any other additional information available to support the requested compliance schedule.




## SECTION J – APPLICATION CERTIFICATION

THE INFORMATION CONTAINED IN THIS FORM MUST BE CERTIFIED BY A RESPONSIBLE OFFICIAL AS DEFINED IN ADEM ADMINISTRATIVE RULE 335-6-6-.09 "SIGNATORY REQUIREMENTS FOR PERMIT APPLICATIONS" (SEE BELOW).

"I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHER AND EVALUATE THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS."

"I FURTHER CERTIFY UNDER PENALTY OF LAW THAT THE RESULTS OF ANY ANALYSES REPORTED AS LESS THAN DETECTABLE IN THIS APPLICATION OR IN ATTACHMENTS THERETO WERE PERFORMED USING THE EPA APPROVED TEST METHOD HAVING THE LOWEST DETECTION LIMIT READILY ACHIEVABLE FOR THE SUBSTANCE TESTED."

SIGNATURE OF  
RESPONSIBLE OFFICIAL:



DATE  
SIGNED:

03/10/2014

(TYPE OR PRINT)

NAME OF RESPONSIBLE OFFICIAL:

David J. Norton

OFFICIAL TITLE OF RESPONSIBLE OFFICIAL:

Chairman

MAILING ADDRESS:

P. O. Box 488 Heflin, AL 36264

AREA CODE & PHONE NUMBER:

(256) 463-2011

### SIGNATORY REQUIREMENTS FOR PERMIT APPLICATIONS

Responsible official is defined as follows:

1. In the case of a corporation, by a principal executive officer of at least the level of vice president, or a manager assigned or delegated in accordance with corporate procedures, with such delegation submitted in writing if required by the Department, who is responsible for manufacturing, production, or operating facilities and is authorized to make management decisions which govern the operation of the regulated facility
2. In the case of a partnership, by a general partner
3. In the case of a sole proprietorship, by the proprietor, or
4. In the case of a municipal, state, federal, or other public facility, by either a principal executive officer, or a ranking elected official.
5. In the case of a private or semi-public facility, the responsible official is either a principal executive officer or the owner of the corporation or other entity.



# Attachment 1 to Supplementary Form ADEM Form 311

## *Alternatives Analysis*

*Applicant/Project:* N/A

All new or expanded discharges (except discharges eligible for coverage under general permits) covered by the NPDES permitting program are subject to the provisions of ADEM's antidegradation policy. Applicants for such discharges to Tier 2 waters are required to demonstrate "... that the proposed discharge is necessary for important economic or social development." As a part of this demonstration, the applicant must complete an evaluation of the discharge alternatives listed below, including a calculation of the total annualized project costs for each technically feasible alternative (using ADEM Form 312 for public-sector projects and ADEM Form 313 for private-sector projects). Alternatives with total annualized project costs that are less than 110% of the total annualized project costs for the Tier 2 discharge proposal are considered viable alternatives.

Alternative	Viable	Non-Viable	Comment
1 Land Application			
2 Pretreatment/Discharge to POTW			
3 Relocation of Discharge			
4 Reuse/Recycle			
5 Process/Treatment Alternatives			
6 On-site/Sub-surface Disposal			
<i>(other project-specific alternatives considered by the applicant; attach additional sheets if necessary)</i>			
7			
8			
9			

Pursuant to ADEM Administrative Code Rule 335-6-3-.04, I certify on behalf of the applicant that I have completed an evaluation of the discharge alternatives identified above, and reached the conclusions indicated.

Signature: \_\_\_\_\_  
(Professional Engineer)

Date: \_\_\_\_\_

*(Supporting documentation to be attached, referenced, or otherwise handled as appropriate.)*

ADEM Form 311 3/02



## Attachment 2 to Supplementary Form

### Calculation of Total Annualized Project Costs for Public-Sector Projects

#### A. Capital Costs

Capital Cost of Project

\$ N/A

Other One-Time Costs of Project (Please List, if any):

\$ N/A

\$ N/A

\$ N/A

**Total Capital Costs (Sum column)**

\$ N/A (1)

Portion of Capital Costs to be Paid for with Grant Monies

\$ N/A (2)

Capital Costs to be Financed [Calculate: (1) – (2) ]

\$ N/A (3)

Type of Financing (e.g., G.O. bond, revenue bond, bank loan)

N/A

Interest Rate for Financing (expressed as decimal)

N/A (i)

Time Period of Financing (in years)

N/A (n)

Annualization Factor =  $\frac{i}{(1+i)^n - 1} + i$

N/A (4)

**Annualized Capital Cost** [Calculate: (3) x (4) ]

N/A (5)

#### B. Operating and Maintenance Costs

Annual Costs of Operation and Maintenance (including but not limited to: monitoring, inspection, permitting fees, waste disposal charges, repair, administration and replacement.) (Please list below.)

\$ N/A

\$ N/A

\$ N/A

\$ N/A

**Total Annual O & M Costs (Sum column)**

\$ N/A (6)

#### C. Total Annual Cost of Pollution Control Project

Total Annual Cost of Pollution Control Project [ (5) + (6) ]

\$ N/A (7)

## Attachment 3 to Supplementary Form ADEM Form 313

### Calculation of Total Annualized Project Costs for Private-Sector Projects

Capital Costs to be Financed (Supplied by applicant)	<u>\$ N/A</u>	<u>(1)</u>
Interest rate for Financing (Expressed as a decimal)	<u>N/A</u>	<u>(i)</u>
Time Period of Financing (Assume 10 years <sup>*</sup> )	<u>10 years</u>	<u>(n)</u>
Annualization Factor = $\frac{i}{(1+i)^{10} - 1} + i$	<u>N/A</u>	<u>(2)</u>
Annualized Capital Cost [Calculate: (1) x (2) ]	<u>\$ N/A</u>	<u>(3)</u>
Annual Cost of Operation and Maintenance (including but not limited to monitoring, inspection, permitting fees, waste disposal charges, repair, administration and replacement) <sup>**</sup>	<u>\$ N/A</u>	<u>(4)</u>
 <b>Total Annual Cost of Pollution Control Project [ (3) + (4) ]</b>	 <div style="border: 1px solid black; padding: 5px; display: inline-block;"><u>\$ N/A</u></div>	 <div style="border: 1px solid black; padding: 5px; display: inline-block;"><u>(5)</u></div>

<sup>\*</sup> While actual payback schedules may differ across projects and companies, assume equal annual payments over a 10-year period for consistency in comparing projects.

<sup>\*\*</sup> For recurring costs that occur less frequently than once a year, pro rate the cost over the relevant number of years (e.g., for pumps replaced once every three years, include one-third of the cost in each year).



## Attachment 4 to Supplementary Form

### NPDES PROGRAM PERMIT APPLICATION FORMS ALABAMA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT


TYPE DISCHARGE	ADEM FORMS	EPA FORMS
New or existing once through non-contact cooling water and/or cooling tower blowdown, and/or sanitary wastewater (non-process wastewater only). Note: POTWs and privately owned domestic treatment works should use Form 2A.	Supplemental Information Form 187 – (Industrial) or Form 188 (Municipal)	Forms 1 and 2E
Existing discharges of process wastewater	Supplemental Information Form 187 – (Industrial) or Form 188 (Municipal)	Forms 1 and 2C
New discharges of process wastewater	Supplemental Information Form 187 – (Industrial) or Form 188 (Municipal)	Forms 1 and 2D
New or existing discharges composed entirely of stormwater meeting the EPA definition of stormwater associated with industrial activity	Supplemental Information Form 187 – (Industrial) or Form 188 (Municipal)	Forms 1 and 2F
New or existing discharges composed of stormwater meeting the EPA definition of stormwater associated with industrial activity, and any other non-stormwater discharges.	Supplemental Information Form 187 – (Industrial) or Form 188 (Municipal)	Forms 1 and 2F and, as appropriate, Forms 2E, 2C, and/or 2D
New or existing Publicly-Owned Treatment Works (POTWs) and Privately-Owned Treatment Works composed of sanitary wastewater	Supplemental Information Form 187 – (Industrial) or Form 188 (Municipal)	Forms 1 and 2A
New or existing land application of process wastewater. Form 2F is required for stormwater runoff from the land application site, if the site is not completely bermed to prevent runoff.	Supplemental Information Form 187 – (Industrial)	Forms 1, 2F, and 2C or 2D, as appropriate
New or existing land application of sanitary wastewater. Form 2F is required for stormwater runoff from the land application site, if the site is not completely bermed to prevent runoff.	Supplemental Information Form 187 – (Industrial) or Form 188 (Municipal)	Forms 1, 2A, and 2F

Testing requirements: Test procedures for all analyses shall conform to 40 CFR Part 136 or an alternate method specifically approved by the Department. If more than one method of analysis is approved, then the method having the lowest detection level shall be used.









SHEET TITLE

# PLANT FLOW SCHEMATIC

SHEET NO.

2

PROJECT NO.

N/A

SCALE

NO SCALE

DATE

2-19-2014

THE WATER WORKS AND SEWER BOARD  
OF THE CITY OF HEFLIN

HEFLIN, ALABAMA



**Utility  
Engineering  
Consultants, LLC**  
WATER DESIGN • WASTEWATER DESIGN • OPERATOR TRAINING • O&M